

# P441 and P444 Alignment Pit System

## Pit Rack




### SPECIFICATIONS



**P444 Pit Installation**

Site Specifications	
Pit Construction	Refer to Forms 6120-T (P441) or 6121-T (P444)
Minimum Concrete Spec.	6 in. (152 mm) thick, 3000 PSI (20700 kPA) rating
<b>Pre-Installation Kit ▲ Required before pouring pit. ▲</b>	
Pit Contractor Pre-Pack	None Available
Pit Edging	Field Fabricated / Purchased
Product Specification	
Max. Vehicle Gross Weight	18,000 lbs. (8165 kg)
Jack Rail	Integrated Rails on Runways
Track Width (inside and outside width)	Fixed Runway, Typical Spacing 40 - 85 inches (1016 - 2159 mm)
Pit Depth	Standard New Pit: 36 inches (914 mm)
	Optional New Pit: 30 inches (762 mm)
	Available for Existing Pit: 24 inches (610 mm)



**P444 Pit Illustration**

### MODEL COMPARISON

Features	PT	PF	RKHD	PE	P44x
Capacity	Heavy Duty 18,000 lbs. / axle (8165 kg)	Heavy Duty 18,000 lbs. / axle (8165 kg)	Heavy Duty 20,000 lbs. / axle (9072 kg)	Medium Duty 10,000 lbs. / axle (4535 kg)	Light Duty 18,000 lbs. Total (8165 kg)
Axle Jack Rail	✓	optional T-Pit	optional jack tray	N/A	✓
Work Beam	N/A	✓	N/A	✓	N/A
Pit Depth	58 in. (1473 mm)	58 in. (1473 mm)	24 or 30 in. (610 mm or 762 mm)	36 in. (914 mm)	36 in. (30 & 24 in. available) (914, 762 or 610 mm)
Track Width (inside - outside width)	Adjustable Runways 48 in. - 120 in (1219 mm - 3048 mm)	Adjustable Runways 48 in. - 120 in (1219 mm - 3048 mm)	Fixed Runways 40 in. - 106 in. (1016 mm - 2692 mm)	Adjustable Runways 48 in. - 120 in (1219 mm - 3048 mm)	Fixed Runways 40 in. - 85 in. (1016 mm - 2159 mm)

**Continued on Page 2** → → →

For lift rack information visit:  
[www.hunter.com/rack](http://www.hunter.com/rack)

For general inquiries visit:  
[www.hunter.com](http://www.hunter.com)  
or call  
**800-448-6848**


For local contact visit:  
[www.hunter.com/company/findrep.cfm](http://www.hunter.com/company/findrep.cfm)

# P441 and P444 HD Alignment Pit System

## Pit Rack

**HUNTER**  
Engineering Company

**LAY-OUT** ▲ Construct pit per referenced forms. ▲



The following items are to be supplied by the customer:

Concrete to construct pit / Concrete reinforcement / Electrical fixtures, wiring, and power (if necessary) / Piping / Pit ventilation materials / Drainage materials / Edging / Railings / lifting equipment for installation.