Catalog 0611CT1001 R01/14

2014

Class 0611



#### CONTENTS

Description
Catalog Numbering
General Information
Circuit Breakers
Automatic Switches
Motor Circuit Protection
Trip Units
Accessories for Micrologic™ Trip Units
Accessories and Auxiliaries
Circuit Breaker Mounting and Connections
Installation Recommendations129
Wiring Diagrams139
Dimensions
Trip Curves171
Catalog Numbers
Glossary



01/2014

SEC	TION 1: CATALOG NUMBERING	1
	PowerPact™ with Micrologic™ Circuit Breakers	7
	Catalog Numbering	8
SEC	CTION 2: GENERAL INFORMATION	10
SEC	Applications	
	Mission Critical Circuit Breakers	
	Flexible Configurations	
	General Characteristics	
	PowerPact H-, J-, and L-frame Circuit Breaker Trip Units	
	Toward doct 11, 0, and 2 mains chook Broaks. The office	
SEC	CTION 3: CIRCUIT BREAKERS	.22
	Dual-Break Rotating Contacts	. 22
	High Ampere Interrupting Ratings (AIR)	. 22
	Internal Operating Mechanism	. 22
	Handle Position Indication	. 23
	Circuit Breaker Ratings	. 23
	Special Applications	. 25
	H- and J-Frame Catalog Numbers	. 26
	L-Frame Circuit Breaker Catalog Numbers	. 36
SEC	CTION 4: AUTOMATIC SWITCHES	.42
	Automatic Switch Functions	. 42
	Specifications	. 43
	Catalog Numbers	. 44
SEC	CTION 5: MOTOR CIRCUIT PROTECTION	16
SEC	General Information	
	Motor Branch Circuit Protection Function	
	Trip Class of a Overload Relay Device	
	Asynchronous-Motor Starting Parameters	
	Motor-Feeder Solutions	
	Electronic Motor Circuit Protectors (AC Only)	
	Micrologic 1.3 M Electronic Trip Units for Instantaneous	. →≎
	Protection Only (L-Frame Circuit Breakers Only)	. 52
	Micrologic 2.2 M and 2.3 M Electronic Trip Units	. 53
	Indications	. 54



SECTION 6	6: TRIP UNITS	58
Availab	ole Trip Units	58
Protec	ion of Distribution Systems	61
SECTION 7	7: ACCESSORIES FOR MICROLOGIC™ TRIP UNITS	77
Display	Options	77
Circuit	Breaker Communication Network Options	80
SECTION 8	B: ACCESSORIES AND AUXILIARIES	94
Comm	unication Network	94
Access	ory Connections	97
Auxilia	ry and Alarm Indication Contacts	97
SDx ar	nd SDTAM Modules for Micrologic	99
Shunt	Trip (MX) and Undervoltage Trip (MN)	101
Motor	Operator	102
Add-O	n Ground-Fault Module (GFM) (H- and J-Frame Only)	104
Earth L	eakage Module (ELM) (H- and J-Frame Only)	105
Rotary	Operating Handles	106
Class 9	9422 Flange-Mounted Variable-Depth Operating Mechanism	109
Locking	g Systems	109
Manua	Mechanical Interlocking Systems	110
Sealing	g Accessory	113
Front-F	Panel Escutcheons	113
Toggle	Collars (For Drawout Mounting)	114
Toggle	Boot	114
Handle	Extension	114
Circuit	Breaker Enclosures and Enclosure Accessories	115
SECTION 9	E CIRCUIT BREAKER MOUNTING AND CONNECTIONS	117
Mounti	ng Configurations	117
Unit-M	ount Circuit Breakers	118
I-Line™	Circuit breakers	119

SECTION 10: INSTALLATION RECOMMENDATIONS	129
Operating Conditions	129
Installation in Equipment	132
Safety Clearances and Minimum Distances	132
Safety Clearance	133
Control Wiring	134
24 Vdc Power Supply Module	136
Wiring	137
Modbus	138
SECTION 11: WIRING DIAGRAMS	139
SECTION 12: DIMENSIONS	148
SECTION 13: TRIP CURVES	171
CATALOG NUMBERS	230
CLOCCARV	000

# **Section 1—Catalog Numbering**

# PowerPact™ with Micrologic™ Circuit Breakers


The PowerPact H-, J-, and L-frame circuit breakers are designed to protect electrical systems from damage caused by overloads and short circuits. H- and J-frame circuit breakers are available with either thermal-magnetic or Micrologic electronic trip units. L-frame circuit breakers are available with Micrologic electronic trip unit.



#### **Direct Access to Energy Management**

The new generation PowerPact with Micrologic circuit breakers set the standard with direct access to energy management. Integrated metering enhances their protective functions. For the first time, Schneider Electric™ users can monitor energy from 15 A to 3000 A, offering new performance in a remarkably compact device.

- Smart A meter in every breaker
- Safe Combines safety and performance in one compact device
- Simple To select, install, and use



# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Catalog Numbering

## **Catalog Numbering**




Table 1: Interrupting Rating

	UL® / CSA® / NOM®				IEC 647-2 lcu/lcs						
	240 Vac	480 Vac	600 Vac	250 Vdc <sup>1</sup>	500 Vdc <sup>2</sup>	220/240 Vac	380/440/415 Vac	500/525 Vac	690 Vac	250 Vdc <sup>1</sup>	500 Vdc <sup>3</sup>
D	25 kA	18 kA	14 kA	20 kA	_	25/25 kA	18/18 kA	14/14 kA	_	20 kA	20 kA
G	65 kA	35 kA	18 kA	20 kA	20 kA	65/65 kA	35/35 kA	18/18 kA	_	20 kA	20 kA
J	100 kA	65 kA	25 kA	20 kA	_	100/100 kA	65/65 kA	25/25 kA	_	20 kA	20 kA
L	125 kA	100 kA	50 kA	20 kA	_	125/125 kA	100/100 kA	50/50 kA	_	20 kA	20 kA
R	200 kA	200 kA	100 kA	_	_	150 kA	125 kA	75 kA	20 kA	_	_

<sup>1 250</sup> Vdc ratings only available with PowerPact H or J circuit breakers with thermal-magnetic trip units (not including MCP).

01/2014

UL 500 Vdc ratings only available with PowerPact J circuit breakers with thermal-magnetic trip units (not including MCP).

<sup>3</sup> IEC 500 Vdc rating only available on PowerPact J-frame circuit beakers.

#### PowerPact™ H-, J-, and L-Frame Circuit Breakers **Catalog Numbering**

Factory Installed Accessory Suffix Codes (Building Sequence as Listed) and Field-Installable Kit Number Table 2:

(1) Communication Networks <sup>1</sup>							
Suffix	Description	Kit No.					
EA	NSX Cord 1.3 m, V ≤ 480 V	S434201					
EB	NSX Cord 3 m, V ≤ 480 V	S434202					
ED	NSX Cord 1.3 m, V > 480 V	S434204					
EE	NSX Cord 3 m, V > 480 V	S434303					
EG <sup>4</sup>	BSCM + NSX Cord 1.3 m, V ≤ 480 V	S434201BS					
EH <sup>4</sup>	BSCM + NSX Cord 3 m, V ≤ 480 V	S434202BS					
EK <sup>4</sup>	BSCM + NSX Cord 1.3 m, V > 480 V	S434204BS					
EL <sup>4</sup>	BSCM + NSX Cord 3 m, V > 480 V	S434303BS					
EN	24 Vdc Power Supply Terminal Block	S434210					

#### (2) Indication Contacts

Suffix	Description	Kit No.
V	SDX	S429532
	SDTAM (motor only trip units)	S429424

#### (3) Auxiliary Switch

Suffix	Contacts	Kit No.	Kit Qty.
AA	1A/1B Standard	S29450	1
AB	2A/2B Standard	S29450	2
AC	3A/3B Standard (L-frame only)	S29450	3
AE	1A/1B Low-Level	S29452	1
AF	2A/2B Low-Level	S29452	2
AG	3A/3B Low Level (L-frame only)	S29452	3

#### (4) Alarm/Overcurrent Trip Switch

Suffix	Switch	Kit No.	Kit Qty.			
PowerPact L-Frame and PowerPact H/J-Frame with Micrologic 5/6 trip units						
BC	Alarm Switch	S29450	1			
BH	Alarm Switch Low-Level	S29452	1			
BD	Overcurrent Trip Switch, Standard SDE Actuator	S29450 S29451	1			
BJ	Overcurrent Trip Switch, Low-Level SDE Actuator	S29452 S29451	1 1			
BE	Alarm Switch and Overcurrent Trip Switch, Standard	S29450	2			
BK	Alarm Switch and Overcurrent Trip Switch, Low-Level	S29452	2			
PowerP	act H/J-Frame with Thermal-Magnetic or Micrologic	1/2/3 trip un	its			
BC	Alarm Switch	S29450	1			
BH	Alarm Switch Low-Level	S29452	1			
BD	Overcurrent Trip Switch, Standard SDE Actuator	S29450 S29451	1			
BJ	Overcurrent Trip Switch, Low-Level SDE Actuator	S29452 S29451	1 1			
BE	Alarm Switch and Overcurrent Trip Switch, Standard	S29450	2			
	SDE Actuator	S29451	1			
BK	Alarm Switch and Overcurrent Trip Switch, Low-Level	S29452	2			
	SDE Actuator	S29451	1			

Except for 24 Vdc Power Supply Terminal Block, installation requires IFM (STRV00210) for Modbus communication and/or FDM (STRV00121) for external display.

YH2 = ENCT and all installed accessories

YH3 = ZSI and all installed accessories

YH4 = ZSI, ENCT and all installed accessories

(5) Shunt Trip		(6) Undervol	Voltage	
Suffix	Kit No.	Suffix	Kit No.	
SK	S29384	UK	S29404	24 Vac
SL	S29385	UL	S29405	48 Vac
SA	S29386	UA	S29406	120 Vac
SD	S29387	UD	S29407	208/277 Vac
SH	S29388	UH	S29408	380/480 Vac
SJ	S29389	UJ	S29409	525/600 Vac
SN	S29382	UN	S29402	12 Vdc
SO	S29390	UO	S29410	24 Vdc
SU	S29391	UU	S29411	30 Vdc
SP	S29392	UP	S29412	48 Vdc
SV	S29383	UV	S29403	60 Vdc
SR	S29393	UR	S29413	125 Vdc
SS	S29394	US	S29414	250 Vdc

#### (6) Communicating Motor Operator<sup>5</sup>

Suffix Voltage		H-Frame	J-Frame	L-Frame	
NC	220/240 Vac	S429441	S431549	S432652	

#### (7) Motor Operator

Suffix	Voltage	H-Frame	J-Frame	L-Frame
ML	48/60 Vac	S29440	S31548	S432639
MA	120 Vac	S29433	S31540	S432640
MD	277 Vac	S29434	S31541	S432641
MF	380/415 Vac	_	_	S432642
МН	440/480 Vac	S29435	S31542	S432647
MO	24/30 Vdc	S29436	S31543	S432643
MV	48/60 Vdc	S29437	S31544	S432644
MR	110/130 Vdc	S29438	S31545	S432645
MS	250 Vdc	S29439	S31546	S432646

#### (8) Rotary Handle

Suffix	Handle Type (color)	H/J-Frame	L-Frame
RD10	Direct Mount (black)	S29337	S32597
RD20	Direct Mount (red)	S29339	S32599
RE10	Extended Door Mount (black)	S29338	S32598
RT10	Telescoping (black)	S29343	S32603
RE20	Extended Door Mount (red)	S29340	S32600

#### (9) Wire Harnesses<sup>2</sup>

Suffix	Harness <sup>2</sup>	Kit No.
YH3	ZSI Wire Harness, H/J Frame	S434300
YH3	ZSI Wire Harness, L-Frame	S434301
YH2	ENCT Wire Harness	S434302
YH1	OF Wire Harness	S434500
YH1	SD/SDE Wire Harness	S434501
YH1	SDx/SDTAM Wire Harness	S434502
YH1	MN Wire Harness	S434503
YH1	MX Wire Harness	S434504
YH1	Motor Operator Wire Harness	S434506
YH1	Communicating Motor Operator Wire Harness	S434507
YH1 <sup>3</sup>	NSX Wire Harness	S434508
YH4	ENCT and ZSI Wire Harnesses	-
YH1 <sup>3</sup>	24 Vdc Power Supply Wire Harness	S434505

#### (10) Handle Padlocks

Suffix	Padlock Type	H/J-Frame	L-Frame
YP	Handle Padlock, ON or OFF	S29371	S32631
YQ	Handle Padlock, OFF Only	S37422	NJPAF



YH1 = all installed accessories but ZSI and ENCT

I-Line wire harness included for communication network accessories.

Optional wire harness for unit mount requires YH1 suffix.

If using with a motor operator, requires Communicating Motor Operator (suffix NC).

Requires Micrologic trip unit U43, U44, U53, or U54 and communication accessories EG, EH, EK,

#### Section 2—General Information

The PowerPact™ H-, J-, and L-frame circuit breakers are designed to protect electrical systems from damage caused by overloads and short circuits. H- and J-frame circuit breakers are available with either thermal-magnetic or Micrologic™ electronic trip units. L-frame circuit breakers are available with Micrologic electronic trip unit.

H- and J-frame circuit breakers with thermal-magnetic trip units contain individual thermal (overload) and instantaneous (short circuit) sensing elements in each pole. The amperage ratings of the thermal trip elements are calibrated at 104°F (40°C) free air ambient temperature. Per the National Electric Code® (NEC®) and the Canadian Electrical Code, standard circuit breakers may only be applied continuously at up to 80% of their rating. Circuit breakers rated for 100% operation are available but require specially-designed enclosures, copper lugs, and 194°F (90°C) rated wire.

Devices with the Micrologic electronic trip unit provide adjustable protection settings for greater system flexibility. In addition to electronic protection, Micrologic trip units allow users to monitor both energy and power. Through direct access to in-depth information and networking using open protocols, PowerPact circuit breakers with Micrologic trip units let operators optimize the management of their electrical installations. Far more than a circuit breaker, these circuit breakers are a measurement and communication tool ready to meet energy-efficiency needs through optimized power requirements, increased energy availability, and improved installation management.

# **Applications**

PowerPact H-, J-, and L-frame circuit breakers offer high performance and a wide range of interchangeable trip units to protect most applications.

Electronic trip units provide highly accurate protection with wide setting ranges and can integrate measurement, metering and communication functions. They can be combined with the front display module (FDM121) to provide functions similar to a power meter.

Table 3: Applications

Power Meter	PowerPact H-, J-, and L-frame circuit breakers equipped with Micrologic 5 / 6 trip units offer type A (ammeter) or E (energy) metering functions as well as communication capability. Using Micrologic trip unit sensors and intelligence, PowerPact H-, J-, and L-frame circuit breakers provide access to measurements of all the main electrical parameters on the built-in screen, on a dedicated front display module (FDM121) or through the communication network.
Operating assistance	Integration of measurement functions provides operators with operating assistance functions including alarms tripped by user-selected measurement values, time-stamped event tables and histories, and maintenance indicators.
Front display module	The main measurements can be read on the built-in screen of Micrologic 5 / 6 trip units. They can also be displayed on the equipment FDM121 along with pop-up windows signalling the main alarms.
Communication Network	PowerPact H-, J-, and L-frame circuit breakers equipped with Micrologic 5 / 6 trip units provide communication capabilities. Simple RJ45 cables connect to a Modbus communication interface module.

01/2014

Table 3: Applications

Protection of distribution systems  Mission critical applications	The PowerPact H-, J-, and L-frame circuit breakers provide protection against short circuits and overloads for:  distribution systems supplied by transformers distribution systems supplied by engine generator sets They are easily installed at all levels in distribution systems, from the main LV switchboard to the subdistribution boards and enclosures. All PowerPact circuit breakers can protect against insulation faults by adding an external Vigirex relay.  The PowerPact H-, J-, and L-frame mission critical circuit breakers provide high levels of selective coordination with QO and ED/EG/EJ circuit breakers.
Protection of motors	The PowerPact H-, J-, and L-frame circuit breakers include a number of versions to protect motor applications:  • basic short-circuit protection with electronic instantaneous only MCP or the electronic Micrologic 1.3 M trip units, combined with a special overload relay to provide thermal protection  • protection against overloads, short circuit and phase unbalance or loss with Micrologic 2 M trip units  The exceptional limiting capacity of the PowerPact circuit breakers automatically provides coordination with the motor starter.
Protection of special applications	The PowerPact H-, J-, and L-frame circuit breakers offer a number of version for special protection applications:  • industrial control panels with:  — compliance with international standards IEC 60947-2 and UL 508/CSA 22.2 N°14  —compliance with UL 489  — installation in universal and functional enclosures  • 400 Hz systems
Control using automatic switches	An automatic switch version of PowerPact H-, J-, and L-frame circuit breakers is available for circuit control. All add-on functions for the circuit breakers may be combined with the basic automatic switch function, including motor operators.  For information on other automatic switches, contact Schneider Electric.
Manual transfer systems	To ensure a continuous supply of power, some electrical installations are connected to two power systems:  • the normal source, usually the utility (U)  • a replacement source to supply the installation when the normal source is not available, generally from a generator (G)  A mechanical and/or electrical interlocking system between two circuit breakers or automatic switches avoids all risk of parallel connection of the sources during switching.  A system can be manual transfer mechanical device interlocking.

#### **Mission Critical Circuit Breakers**

The PowerPact<sup>™</sup> J- and L-Frame Mission Critical circuit breakers deliver high levels of selective coordination in a flexible design that can be easily configured for a variety of applications. Tested to be selectively coordinated with the QO<sup>™</sup> family of miniature circuit breakers and the ED, EG, and EJ circuit breakers, this solution provides peace of mind when power availability is critical.

An electronic trip unit provides adjustable long-time settings in three sensor sizes, allowing coverage from 70 through 600 A on 120-240, 208Y/120, 240, and 480Y/277 V systems.

#### Ratings

UL 489 Listed CSA Certified Voltage: 480Y/277 V

#### **Available Configurations**

- I-Line mounting
- Main circuit breaker in NQ and NF panelboards
- Unit mount for OEM users
- · Plug-in base for OEM users
- Drawout base for OEM users

In addition to unique design attributes, the PowerPact Mission Critical circuit breakers have also undergone rigorous testing procedures to certify the coordination with downstream circuit breakers—combining innovative engineering with validated test results.

Apply Schneider Electric Mission Critical circuit breakers in emergency power distribution systems, data centers, hospitals, or anywhere continuity of service is desired.

#### **Theory of Operation**

There are several dynamic forces between the PowerPact Mission Critical circuit breakers and downstream circuit breakers when a fault occurs downstream of the branch circuit breaker. Many of these events cannot be shown on the trip curve.

The PowerPact Mission Critical circuit breakers analyze the fault current to make decisions which maximize selectivity with downstream circuit breakers. The trip units deploy a special selectivity delay to allow downstream circuit breakers to clear. However, on very high faults or if the downstream circuit breaker does not trip, the circuit breaker trips the mechanism instantaneously.

The combination of the PowerPact Mission Critical circuit breaker and downstream circuit breakers shown in the selectivity charts in the instruction bulletin are selective due to the fact that the series impedance and the let-through from the downstream circuit breaker does not produce enough energy to trip the PowerPact Mission Circuit circuit breaker.

This system maximizes the interaction of the circuit breakers in series to allow selectivity.

#### **Trip Units and Trip Curves**

The PowerPact J- and L-Frame Mission Critical circuit breakers deliver high levels of selective coordination with the QO<sup>™</sup> family of miniature circuit breakers and the ED, EG, and EJ circuit breakers in a flexible design that can be easily configured for a variety of applications. These circuit breaker can be equipped with 3.2-W, 3.2S-W, 5.2A-W, 5.2E-W, 6.2A-W, 3.3S-W, 5.3A-W, 6.3A-2, and 6.3E-2 Micrologic trip units. See the catalog numbers and references beginning in Table 17.

The mission critical trip units have the same settings and trip curves as the standard trip units as described in this document.

For more information see the trip unit user guides 48940-310-01 and 48940-312-01 on the Schneider Electric website.



J-frame mission critical circuit breakers are selective with QO or E-frame circuit breakers per Table 4 when the amperage of the main circuit breaker is at least two times the amperage of the branch circuit breaker.

Table 4: J-Frame Selectivity with QO and E-Frame Circuit Breakers<sup>1</sup>

Circuit Breaker			Voltage Current		One Line	e Diagram	
Main	Branch			Voltage	Current	One-Line	e Diagrain
			10–30 A		18 kA		
	QO(B)	1P, 2P	35–60 A	240/120 V 120 V	15 kA		J-Frame Mission Critical Circuit Breaker
J-W, 250 A	QO(B)-H		70–125 A	1	12 kA		J 3-Frame Mission Chical Circuit Breaker
J-VV, 250 A	QO(B)-VH QH				15 kA	$\sim$	
	QH	3P	35–60 A	240 V 208 V	13 kA	QO 20 A 1P	OO 20 A 1P Load
			70–125 A		10 kA		Load Load
			15–125 A	240 V	18 kA		FAULT
			15–60 A		10 kA		
J–W, 250 A	E-Frame	1P, 2P, 3P	70–125 A	480Y/277 V	7 kA		QO 100 A 2P Load

<sup>&</sup>lt;sup>1</sup> Including AFI, CAFI, EPD and GFI circuit breakers.

L-frame mission critical circuit breakers are selective with QO-style and E-frame circuit breakers per Table 5 when the amperage of the main circuit breaker is at least two times greater than the amperage of the branch circuit breaker.

Table 5: L-Frame Selectivity with QO and E-Frame Circuit Breakers<sup>1</sup>

Circuit Breaker			Voltage Current		One-Line Diagram
Main	Branch		voitage	Current	One-Line Diagram
L-W, 250 A	QO(B) QO(B)-H	10–60 A	240 V	18 kA	
L-VV, 250 A	QO(B)-VH QH	70–125 A	240 V	10 kA	L-Frame Mission Critical Circuit Breaker
L-W, 400 A L-W, 600 A	QO(B) QO(B)-H QO(B)-VH QH	15–150 A	240 V	30 kA	QO 20 A 1P Load
L-W, 250 A			240 V	30 kA	FAULT
L-W, 400 A L-W, 600 A	E-Frame	15–125 A	480Y/277	30 kA	FAULT
					QO 100 A 2P Load


<sup>1</sup> Including AFI, CAFI, EPD and GFI circuit breakers.

# **Flexible Configurations**

The PowerPact H-, J- and L-frame circuit breakers may be configured with lugs, bus bar connections, rear connections, I-Line $^{TM}$ , drawout cradle, or plug-in base.


# Field Installable Accessories and Trip Units

Figure 1: Field Installable Accessories and Trip Units



#### **General Characteristics**

#### **Faceplate Label**



Characteristics indicated on the faceplate label:

- A. Circuit breaker type
- B. Circuit breaker disconnector symbol
- C. Performance levels
- D. Standards
- E. Ue: Operating voltage per IEC
- F. Icu: Ultimate breaking capacity per IEC
- G. Ics: Service breaking capacity per IEC
- H. Uimp: Rated impulse withstand voltage per IEC
- I. Ui: Insulation voltage per IEC
- J. Certification marks

**NOTE:** When the circuit breaker is equipped with an extended rotary handle, the door must be opened to view the faceplate.

#### **Codes and Standards**

H-, J-, and L-frame circuit breakers, automatic switches and electronic motor circuit protectors are manufactured and tested in accordance with the following standards.

**NOTE:** Apply circuit breakers according to guidelines detailed in the National Electric Code (NEC) and other local wiring codes.

Table 6: Codes and Standards (Domestic)

PowerPact H-, J-, and L-Frame Circuit Breakers	H-, J-, and L-Frame Switches	PowerPact H-, J-, and L-Frame Motor Circuit Protectors				
UL 489 <sup>1</sup>	UL 489 <sup>3</sup>	UL 508				
IEC 60947-2	IEC 60947-3	IEC 60947-2				
CSA C22.2 No. 5 <sup>2</sup>	CSA C22.2 No. 5 <sup>4</sup>	CSA C22.2 No. 14				
Federal Specification W-C-375B/GEN	Federal Specification W-C-375B/GEN	NEMA AB1				
NEMA AB1	NEMA AB1	ccc				
NMX J-266	NMX J-266	CE Marking				
CCC	CE Marking					
CE Marking						

- 1 PowerPact H- and J-frame circuit breakers are in UL File E10027. PowerPact L-frame circuit breakers are in UL File E63335.
- <sup>2</sup> PowerPact H- and J-frame circuit breakers are in CSA File LR40970. PowerPact L-frame circuit breakers are in CSA File 69561.
- <sup>3</sup> PowerPact H- and J-frame switches are in UL File E87159.
- <sup>4</sup> PowerPact H- and J-frame switches are in CSA File LR32390.







PowerPact H-, J-, and L-frame devices resist mechanical vibration.

Tests are carried out in compliance with standard UL 489 SA and SB for the levels required by merchant-marine inspection organizations (Veritas, Lloyd's, etc.):


PowerPact H-, J-, and L-frame circuit breaker meet IEC 60068-2-6 for vibration:


- 2.0 to 25.0 Hz and amplitude +/- 1.6 mm
- 25.0 to 100 Hz acceleration +/- 4.0 g

Excessive vibration may cause tripping, breaks in connections or damage to mechanical parts.

#### Electromagnetic disturbances

PowerPact H-, J-, and L-frame devices are protected against:





- devices emitting radio waves (radios, walkie-talkies, radar, etc.)
- electrostatic discharges produced directly by users

PowerPact H-, J-, and L-frame devices have successfully passed the electromagnetic-compatibility tests (EMC) defined by the following international standards:



- Annex F: Immunity tests for circuit breakers with electronic protection
- Annex B: Immunity tests for residual current protection
- IEC/EN 61000-4-2: Electrostatic-discharge immunity tests
- IEC/EN 61000-4-3: Radiated, radio-frequency, electromagnetic-field immunity tests
- IEC/EN 61000-4-4: Electrical fast transient/burst immunity tests
- IEC/EN 61000-4-5: Surge immunity tests
- IEC/EN 61000-4-6: Immunity tests for conducted disturbances induced by radio frequency fields
- CISPR 11: Limits and methods of measurement of electromagnetic disturbance characteristics of industrial, scientific and medical (ISM) radio-frequency equipment.

These tests ensure that:

- no nuisance tripping occurs
- · tripping times are respected

#### **Tropicalization**

The materials used in PowerPact circuit breakers will not support the growth of fungus and mold.

PowerPact circuit breakers have passed the test defined below for extreme atmospheric conditions.

Dry cold and dry heat:

- IEC 68-2-1-dry cold at -55 °C
- IEC 68-2-2-dry heat at +85° C

Damp heat (tropicalization)

- IEC 68-2-30-damp heat (temperature + 55° C and relative humidity of 95%)
- IEC 68-2-52 level 2-salt mist



#### **Special Ratings**

The H-frame and J-frame circuit breakers also comply with the following special ratings:

- HACR rating
- SWD switch duty rating (applies only to 15 and 20 A / 277 Vac or less, 2P and 3P)
- HID high intensity discharge lighting rating (15–50 A)

The L-frame circuit breakers complies with the following special rating:

HACR rating

#### **Marine Ratings**

#### UL Marine Listed/CSA Certified Circuit Breakers (UL 489 Supplement SA)

The PowerPact H- and J-frame circuit breakers with thermal-magnetic trip units meet the UL 489 Supplement SA requirements for use on vessels of any length under or over 65 ft. (19.8 m). The PowerPact H-, J-, and L-frame circuit breakers with Micrologic electronic trip units meet the UL 489 Supplement SA for use on vessels over 65 ft. (19.8 m) in length. Marine circuit breakers must not use aluminum or aluminum alloys for terminal connections and must be calibrated at an ambient temperature of 104° F (40° C). Standard circuit breakers should not be specified or used in the place of marine rated circuit breakers.

Circuit breakers can be ordered with the Marine SA listing by adding the suffixes "LC" (copper lugs) and "YA" (marine) to the catalog number.

#### UL Naval Listed/CSA Certified Circuit Breakers (UL 489 Supplement SB)

The PowerPact H-, J-, and L-frame circuit breakers with Micrologic trip units meet the UL 489 Supplement SB requirements for use on naval vessels. These circuit breakers are subject to various vibration tests as described in UL 489 Supplement SB. Naval circuit breakers must not use aluminum or aluminum alloys for terminal connections and must be calibrated at an ambient temperature of 122° F (50° C). Standard circuit breakers should not be specified or used in the place of navel rated circuit breakers.

Circuit breakers can be ordered with the Naval SB listing by adding the suffixes "LC" (copper lugs) and "YA1" (naval) to the catalog number.

#### American Bureau of Shipping (ABS)


The PowerPact H-, J-, and L-Frame circuit breakers are certified to ABS-NVR (American Bureau of Shipping - Naval Vessel Rules), for use on Naval vessels.



#### **UL 489 SC Listed 500 Vdc Circuit Breakers**

The UL Listed/CSA Certified thermal-magnetic J-Frame molded case circuit breakers are specifically designed for use on ungrounded dc systems having a maximum short-circuit voltage of 500 Vdc or a maximum floating (unloaded) voltage of 600 Vdc. The circuit breakers are suitable for use only with UPS (uninterruptable power supplies) and ungrounded systems. This two-level voltage rating allows these circuit breakers to be applied to battery sources having a short-circuit availability of 20,000 amperes at 500 Vdc.

These circuit breakers are UL Listed/CSA Certified for the interrupting ratings shown only if applied with three poles connected in series (series connection is external to circuit breaker). See diagram below.



Source = 600 Vdc max. (floating) 500 Vdc max. (loaded)

**NOTE:** Due to external series connection, I-Line circuit breakers are not available for this application.

Table 7: DC Molded Case Circuit Breakers

Ampere	Circuit Breaker	Adjustable Magnetic	Adjustable Magnetic Trip Range—DC Amperes						
Rating	Cat. No.	Low	High	@ 500 Vdc					
100 A	JGL37100D81	400	600						
125 A	JGL37125D81	400	600	00 1: AID					
150 A	JGL37150D81	400	600	20 k AIR					
175 A	JGL37175D81	400	600	=					
200 A	JGL37200D82	500	850						
225 A	JGL37225D82	500	850	20 k AIR					
250 A	JGL37250D82	500	850						

01/2014

Table 8: Circuit Breakers

Circuit Breaker			150 A H-Frame				250	0 A	J-Fr	ame		400 A L-Frame					600 A L-Frame					
Circuit Breaker Type			HG	HJ	HL	HR	JD	JG	JJ	JL	JR	LD	LG	LJ	LL	LR	LD	LG	LJ	LL	LR	
Number of poles <sup>1</sup>			}			3	2, 3	3			3	3, 4	ŀ				3, 4	ļ				
Amperage Range (A)		15-	150				70-	250		1		70-	400				200	)-600	)			
UL 489 Circuit Breaker Rating	js																					
	240 Vac	25	65	100	125	200	25	65	100	125	200	25	65	100	125	200	25	65	100	125	200	
UL/CSA/NOM	480 Vac	18	35	65	100	200	18	35	65	100	200	18	35	65	100	200	18	35	65	100	200	
	600 Vac	14	18	25	50	100	14	18	25	50	100	14	18	25	50	100	14	18	25	50	100	
(kA rms)	250 Vdc <sup>2</sup>	20	20	20	20		20	20	20	20												
	500 Vdc <sup>2, 3</sup>							20														
IEC 947-2 Circuit Breaker Ra	tings																					
	220/240 Vac	25	65	100	125	150	25	65	100	125	150	25	65	100	125	150	25	65	100	125	150	
	380/415 Vac	18	35	65	100	125	18	35	65	100	125	18	35	65	100	125	18	35	65	100	125	
Ultimate breaking capacity	440/480 Vac	18	35	65	100	125	18	35	65	100	125	18	35	65	100	125	18	35	65	100	125	
(Icu)	500/525 Vac	14	18	25	50	75	14	18	25	50	75	14	18	25	50	75	14	18	25	50	75 <sup>4</sup>	
(kA rms)	690 Vac					20					20					20					20	
	250 Vdc <sup>2</sup>						20	20	20	20												
	500 Vdc <sup>2, 3</sup>						20	20	20	20												
Service breaking capacity (Ics	) % Icu	100	1%	•			100	)%				100	)%	•			100	)%			•	
Insulation Voltage	V <sub>i</sub>	750	Vac	:			750	) Va	0			750	) Va	С			750	) Va	5			
Impulse Withstand Voltage	V <sub>imp</sub>	8 k\	Vac				8 k'	Vac				8 k'	Vac				8 k\	Vac				
Operational Voltage	V <sub>e</sub>	690	Vac	:			690	) Va	0			690	) Va	С			690 Vac					
Sensor Rating	In	150	Α				250	) A				400	) A				600 A					
Utilization Category		Α					Α					Α					A					
Operations (Open-Close Cycl	es)																					
Without Current		400	0				500	00				500	00				500	0				
With Current		4000					1000					1000				1000						
Protection and Measurements	6																					
Short-circuit protection	Magnetic only	•	•		-		•	•	-	•	-	•	•			•	•					
	Thermal-magnetic	•	•			•	•	•	-	•												
	Electronic	•	•			•	•	•	-	•		•				•	•			•		
Overload/short-circuit protection	with neutral protection (Off-0.5-1-OSN)5	•	•	•		•	•	•	-	•	•	•				•	•			•		
protection	with ground fault protection			-	-	•	•	•	-	•	-			-					-	-	-	
	with zone selective interlocking (ZSI)6	•	•	•		•	•	•	-	•	•	•				•	•			•		
Display / I, V, f, P, E, THD mea measurement	surements / interrupted-current	•				•	•	•		•	•		-	•		•	•	•			•	
	Front display module (FDM121)	•	-		-	-	•	•		•	-				-	-	•			-		
	Operating assistance		•	-		-	•	•		•	-			-		•	•			-	-	
Outions	Counters		•	-		-	•	•		•	-	•		-		•	•			-	-	
Options	Histories and alarms	•	•	•	•	•	•	•	-	•	•	•		•	•	•	•	•	•	•	•	
	Metering Com	•	•	•	•	•	•	•	-	•	•	•		•	•	•	•	•	•	•	•	
	Device status/control com	•	•	•	•	•	•	•	-	•	•	•		•	•	•	•	•	•	•	•	
Dimensions / Weight / Conne	ctions		•			•							•		•	•						
Dimensions 3P	Height	6.4	(163	)			7.5	(19	1)			13.	38 (	340)			13.38 (340)					
(Unit Mount)	Width	4.1	(104	)			4.1	(104	4)			5.5	1 (14	40)			5.51 (140)					
in. (mm) Depth		3.4	(86)				3.4	(86)	)			4.3	3 (1	10)			4.33 (110)					
Weight 3P - lb. (Kg)		4.8	(2.2)	1			5.3	(2.4	)			13.	2 (6.	0)			13.	7 (6.	2)			
	Unit Mount	•					•					•					•					
	I-Line	•					•										•					
l l	Rear Connection	•					•					•					•					
Connections / Tarminations		+			-				-					•								
Connections / Terminations	Plug-In	•																				
	Plug-In Drawout	-					•					•					-					

<sup>1</sup> H and J-frame breakers with Micrologic trip units available only with 3P. The HJ, HL and the J-Frame 2P breakers are 3P modules.

<sup>&</sup>lt;sup>2</sup> DC not available with PowerPact H, J or L-frame circuit breakers with Micrologic trip units.

 $<sup>^{\</sup>rm 3}$   $\,$  500 Vdc specific catalog numbers, ungrounded UPS systems only.

 $<sup>^4</sup>$   $\,$  I  $_{\rm CS}$  for 600 A L-frame circuit breaker at 525 V is 19 kA.

<sup>&</sup>lt;sup>5</sup> OSN: Over Sized Neutral protection for neutrals carrying high currents (e.g. 3rd harmonics).

<sup>&</sup>lt;sup>6</sup> ZSI using restraint wires.

# PowerPact H-, J-, and L-frame Circuit Breaker Trip Units

Table 9: Micrologic Trip Unit Features

	Micrologic Trip Unit (X = Standard Feature, O = Available Option												
Features	Sta	ndard	Amn	neter	Energy								
	3.2/3.3	3.2\$/3.3\$	5.2A/5.3A	6.2A/6.3A	5.2E/5.3E	6.2E/6.3E							
LI	Х												
LSI <sup>1</sup>		X	Х		Х								
LSIG/Ground Fault Trip <sup>2</sup>				Х		Х							
Ground-Fault Alarm Trip				Х		Х							
Current Settings Directly in Amperes	Х	Х	Х	Х	Х	Х							
True RMS Sensing	Х	Х	Х	Х	Х	Х							
UL Listed	Х	Х	Х	Х	Х	Х							
Thermal Imaging	Х	Х	Х	Х	Х	Х							
LED for Long-Time Pickup	Х	Х	Х	Х	Х	Х							
LED for Long-Time Alarm	Х	Х	Х	Х	Х	Х							
LED Green "Ready" Indicator	Х	Х	Х	Х	Х	Х							
Up to 12 Alarms Used Together			Х	Х	Х	Х							
Digital Ammeter			Х	Х	Х	Х							
Zone-Selective Interlocking <sup>3</sup>			Х	Х	Х	Х							
Communications	0	0	0	0	0	0							
LCD Display			Х	Х	Х	Х							
Front Display Module FDM121			0	0	0	0							
Advanced User Interface			Х	Х	Х	Х							
Neutral Protection			Х	Х	Х	Х							
Contact Wear Indication <sup>4</sup>			Х	Х	Х	Х							
Incremental Fine Tuning of Settings			Х	Х	Х	Х							
Load Profile <sup>4</sup> , <sup>5</sup>			Х	Х	Х	Х							
Power Measurement					Х	Х							
Power Quality Measurements	1		1	1	Х	Х							

 $<sup>^{1}\,\,</sup>$  The LSI with 3.2S/3.3S trip units have fixed short time and long time delays.

### **Thermal-Magnetic or Electronic Trip Unit?**

Thermal-magnetic trip units (available on H- and J-frame circuit breakers only) protect against overcurrents and short-circuits using tried and true techniques. For applications requiring installation optimization and energy efficiency, electronic trip units offering more advanced protection functions combined with measurements.

Trip units using digital electronics are faster as well as more accurate. Wide setting ranges make installation upgrades easier. Designed with processing capabilities, Micrologic trip units can provide measurement information and device operating assistance. With this information, users can avoid or deal more effectively with disturbances and can play a more active role in system operation. They can manage the installation, anticipate events and plan any necessary servicing.

<sup>&</sup>lt;sup>2</sup> Requires neutral current transformer on three-phase four-wire loads.

 $<sup>^{\</sup>rm 3}$   $\,$  ZSI for H/J-frame devices is only IN. ZSI for L-frame devices is IN and OUT.

<sup>&</sup>lt;sup>4</sup> Indication available using the communication system only.

 $<sup>^{5}</sup>$  % of hours in 4 current ranges: 0–49%, 50–79%, 80–89%, and >90%  $I_{n}$ .


#### **Accurate Measurements for Complete Protection**

PowerPact H-, J-, and L-frame circuit breakers devices offer excellent measurement accuracy from 15 amperes on up to the short-circuit currents. This is made possible by a new generation of current transformers combining "iron-core" sensors for self-powered electronics and "air core" sensors (Rogowski coils) for measurements. The protection functions are managed by an ASIC (Application Specific Integrated Circuit) component that is independent of the measurement functions. This independence ensures immunity to conducted and radiated disturbances and increases reliability.

#### **Numerous Security Functions**

Torque-limiting screws	The screws secure the trip unit to the circuit breaker. When the correct tightening torque is reached, the screw heads break off. Optimum tightening avoids any risk of temperature rise. A torque wrench is no longer required.						
Easy and sure changing of trip units	All trip units are interchangeable, without wiring. A mechanical mismatch-protection system makes it impossible to mount a trip unit on a circuit breaker with a lower rating.						
"Ready" LED for a continuous self-test	The LED on the front of the electronic trip units indicates the result of the self-test running continuously on the measurement system and the tripping release. As long as the green LED is flashing, the links between the CTs, the processing electronics and the tripping mechanism are operational. The circuit breaker is ready to protect. A minimum current of 15 to 50 A, depending on the device, is required for this indication function.						
	Available on Micrologic 5 / 6 trip units, the system consists of:						
A patented dual adjustment system for protection functions.	<ul> <li>an adjustment using rotary switches sets the maximum value</li> <li>an adjustment using the keypad or made remotely, fine-tunes the setting. This setting may not exceed the first one. It can be read directly on the Micrologic trip unit screen, to within one ampere and a fraction of a second.</li> </ul>						

#### Section 3—Circuit Breakers



# **Dual-Break Rotating Contacts**

All PowerPact<sup>TM</sup> H-, J-, and L-frame circuit breakers are equipped with dual-break rotating contacts that reduce the amount of peak current during a short circuit fault. This reduces the let-through currents and enhances equipment protection.

#### **Reduced Let-Through Currents**

The moving contact has the shape of an elongated "S" and rotates around a floating axis. The shape of the fixed and moving contacts are such that the repelling forces appear as soon as the circuit reaches approximately 15 times  $I_n$ .

Due to the rotating movement, repulsion is rapid and the device greatly limits short-circuit currents, whatever the interrupting level of the unit (D, G, J or L). The fault current is extinguished before it can fully develop. Lower let-through currents provide less peak energy, reducing the required bus bar bracing, lowering enclosure pressure, and delivering improved series or combination ratings. See page 23 for UL Current Limiting labels.




# **High Ampere Interrupting Ratings (AIR)**

Circuit breakers are available with interrupting ratings up to:

- 200 kA at 240 Vac delta
- 200 kA at 480 Vac delta
- 100 kA at 600 Vac delta.

See Table 1 for additional performance levels.

# **Internal Operating Mechanism**




PowerPact H-, J-, and L-frame circuit breakers have an over-center toggle mechanism providing quick-make, quick-break operation. The operating mechanism is also trip-free, which allows tripping even when the circuit breaker handle is held in the "ON" position.

Internal cross-bars provide common opening and closing of all poles with a single operating handle.

All PowerPact circuit breakers have an integral push-to-trip button in the cover to manually trip the circuit breaker. This should be used as part of a regular preventive maintenance program.

#### **Handle Position Indication**



The circuit breaker handle can assume any of three positions, ON, tripped or OFF as shown. The center tripped position provides positive visual indication that the circuit breaker has tripped.

The circuit breaker can be reset by first pushing the handle to the extreme "OFF" position. Power can then be restored to the load by pushing the handle to the "ON" position.

## **Circuit Breaker Ratings**

The interrupting rating is the highest current at rated voltage the circuit breaker is designed to safely interrupt under standard test conditions. Circuit breakers must be selected with interrupting ratings equal to or greater than the available short-circuit current at the point where the circuit breaker is applied to the system (unless it is a branch device in a series rated combination). Interrupting ratings are shown on Table 8: Circuit Breakers on page 19 and on the faceplate label on the front of the circuit breaker.

#### **Reverse Feeding of Circuit Breakers**

The standard unit-mount H-, J-, and L-frame circuit breakers have sealed trip units and may be reverse fed. See Tables 14–15 and 28–36 for catalog numbers.

Circuit breakers with field-interchangeable trip units (designated by the suffix T and labeled "LINE" and "LOAD") cannot be reverse fed. Neither can circuit breaker frames without terminations or trip units.

#### **Current Limiting**

The current limiting attributes of PowerPact H-, J-, and L-frame circuit breakers provide greater protection for downstream devices by limiting the let-through current in the event of a fault. The current-limiting capabilities of HJ/HL/HR, JJ/JL/JR, and LJ/LL/LR frame circuit breakers are documented with Underwriters Laboratories and Canadian Standards Association. These current-limiting circuit breakers ship with a label that identifies them as UL/CSA Current Limiting Circuit Breakers. (The HD/HG, JD/JG, and LD/LG circuit breakers do not carry the UL Current Limiting label)

The trip curves with let-through data are available in the trip curve section in this catalog.

Please note that as let-through curves for UL Listed/CSA Certified Current-Limiting Circuit Breakers, these curves are maximum let-through values.

#### 100% Rated

Some models of the H-, J-, and L-frame circuit breakers are UL Listed/CSA Certified to be applied at up to 100% of their current rating. Because of the additional heat generated, the use of specially-designed enclosures, copper lugs on H- and J-frame circuit breakers, and 194°F (90°C) rated wire is required when applying circuit breakers at 100% of continuous current rating. (L-frame circuit breakers can use aluminum or copper lugs.) Markings on the circuit breaker indicate the minimum enclosure size and ventilation required. The 194°F (90°C) wire must be sized according to the ampacities of the 167°F (75°C) wire column in the NEC. Circuit breakers with 100% rating can also be used in applications requiring only standard (80%) continuous loading.



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Circuit Breakers

100% ratings valid for:

- 3P H/J-frame unit mount construction only
- 3P/4P L-frame 250 A and 400 A unit mount construction
- 3P L-frame 250 A and 400 A I-Line™ construction

# Corner Grounded Delta Ratings (1Ø-3Ø)


Circuit breakers suitable for corner-grounded circuits are marked 1Ø-3Ø. For additional information, refer to data bulletin 2700DB0202R2/09.

Table 10: Corner Grounded Delta Ratings (1Ø-3Ø)

		2P	H-Fram	ne		2P J-Frame				
	HD	HG	HJ <sup>1</sup>	HL <sup>1</sup>	HR1	JD1	JG <sup>1</sup>	JJ <sup>1</sup>	JL <sup>1</sup>	JR <sup>1</sup>
Ampere Rating (A)			15–150		•			150–250	•	
Voltage Rating (Vac)			240					240		
UL Interrupting Rating (kA)	42	42	65	100	200	42	42	65	100	200

<sup>&</sup>lt;sup>1</sup> Built using 3P module

Figure 2: Three-Phase 240 Vac Corner-Grounded Delta System



# **Special Applications**

#### **Protection of Industrial Control Panels**

PowerPact H-, J-, and L-frame circuit breakers are also used in industrial control panels. They serve as an incoming devices or can be combined with contactors to protect motor feeders:

- compliance with worldwide standards including IEC 60947-2 and UL 508 / CSA C22.2 N°14
- overload and short-circuit protection
- installation in universal and functional type

PowerPact H-, J-, and L-frame circuit breakers equipped for motor protection functions as described in the following pages can be used in industrial control panels. The accessories for the PowerPact H-, J-, and L-frame circuit breakers are suitable for the special needs of these applications.

#### 400 Hz Applications

Micrologic<sup>™</sup> 3.2/3, 5.2/3 A or E and 6.2/3 with A or E measurement functions are suitable for 400 Hz. The use of electronics offers the advantage of greater operating stability when the frequency varies. However the units are still subject to temperature rise caused by the frequency.

The practical consequences are:

- limit settings: see the I<sub>r</sub> derating table below
- the long-time, short-time and instantaneous pick-ups are not modified (see pages 62 or 64)
- the accuracy of the displayed measurements is 2% (class II).

Table 11: Thermal Derating Maximum I<sub>r</sub> Setting

Circuit Breaker	Maximum Setting Coefficient	Max I <sub>r</sub> Setting at 400 Hz
H-Frame, 150 A	0.9	135
J-Frame, 250 A	0.9	225
L-Frame, 400 A	0.8	320
L-Frame, 600 A	0.65	390

#### Auxiliary Switch (OF) in 400 Hz Networks

Table 12: Electrical Characteristics of Auxiliary Switches

Contact	Standar	d	Low Level		
Utilization cat. (IEC 60947-	5-1)	AC12	AC15	AC12	AC15
	24 V	6 A	6 A	5 A	3 A
	40 V	6 A	6 A	5 A	3 A
Operational current	110 V	6 A	5 A	5 A	2.5 A
	200/240 V	6 A	4 A	5 A	2 A
	380/415 V	6 A	2 A	5 A	1.5 A

#### Shunt Trip (MX) or Undervoltage Trip (MN) Voltage Release at 400 Hz and 440 V

For circuit breakers on 400 Hz systems, only 125 Vdc undervoltage trip (MN) or shunt trip (MX) releases may be used. The release must be supplied by the 400 Hz system through a rectifier bridge (to be selected from the table below) and an additional resistor with characteristics depending on the system voltage.

Table 13: Rectifier Bridges for MN or MX Releases

Voltage	Rectifier	Additional Resistor
220/240 V	Thomson 110 BHz or General Instrument W06 or Semikron SKB at 1.2/1.3	4.2 kΩ-5 W
380/240 V	Semikron SKB at 1.2/1.3	10.7 kΩ-10 W

01/2014

# H- and J-Frame Catalog Numbers

## **Unit-Mount Circuit Breaker Catalog Numbers**

Table 14: PowerPact H-Frame 150 A Unit-Mount<sup>1</sup> Thermal-Magnetic Circuit Breakers (600 Vac, 250 Vdc) with Factory Sealed Trip Unit (Suitable for Reverse Connection)

	Fixed A	С	Interrupting	g Rating						
Current	Magneti	ic Trip	D		G		J <sup>2</sup>		L <sup>2</sup>	
Rating @ 40 C	Hold	Trip	Standard (80%) Rated	100% Rated <sup>3</sup>	Standard (80%) Rated	100% Rated <sup>3</sup>	Standard (80%) Rated	100% Rated <sup>3</sup>	Standard (80%) Rated	100% Rated <sup>3</sup>
H-Frame,	150 A, 2F	P, 600 Vac	50/60Hz, 250	Vdc <sup>4</sup>						•
15 A	350 A	750 A	HDL26015	HDL26015C	HGL26015	HGL26015C	HJL26015	HJL26015C	HLL26015	HLL26015C
20 A	350 A	750 A	HDL26020	HDL26020C	HGL26020	HGL26020C	HJL26020	HJL26020C	HLL26020	HLL26020C
25 A	350 A	750 A	HDL26025	HDL26025C	HGL26025	HGL26025C	HJL26025	HJL26025C	HLL26025	HLL26025C
30 A	350 A	750 A	HDL26030	HDL26030C	HGL26030	HGL26030C	HJL26030	HJL26030C	HLL26030	HLL26030C
35 A	400 A	850 A	HDL26035	HDL26035C	HGL26035	HGL26035C	HJL26035	HJL26035C	HLL26035	HLL26035C
40 A	400 A	850 A	HDL26040	HDL26040C	HGL26040	HGL26040C	HJL26040	HJL26040C	HLL26040	HLL26040C
45 A	400 A	850 A	HDL26045	HDL26045C	HGL26045	HGL26045C	HJL26045	HJL26045C	HLL26045	HLL26045C
50 A	400 A	850 A	HDL26050	HDL26050C	HGL26050	HGL26050C	HJL26050	HJL26050C	HLL26050	HLL26050C
60 A	800 A	1450 A	HDL26060	HDL26060C	HGL26060	HGL26060C	HJL26060	HJL26060C	HLL26060	HLL26060C
70 A	800 A	1450 A	HDL26070	HDL26070C	HGL26070	HGL26070C	HJL26070	HJL26070C	HLL26070	HLL26070C
80 A	800 A	1450 A	HDL26080	HDL26080C	HGL26080	HGL26080C	HJL26080	HJL26080C	HLL26080	HLL26080C
90 A	800 A	1450 A	HDL26090	HDL26090C	HGL26090	HGL26090C	HJL26090	HJL26090C	HLL26090	HLL26090C
100 A	900 A	1700 A	HDL26100	HDL26100C	HGL26100	HGL26100C	HJL26100	HJL26100C	HLL26100	HLL26100C
110 A	900 A	1700 A	HDL26110	HDL26110C	HGL26110	HGL26110C	HJL26110	HJL26110C	HLL26110	HLL26110C
125 A	900 A	1700 A	HDL26125	HDL26125C	HGL26125	HGL26125C	HJL26125	HJL26125C	HLL26125	HLL26125C
150 A	900 A	1700 A	HDL26150	HDL26150C	HGL26150	HGL26150C	HJL26150	HJL26150C	HLL26150	HLL26150C
H-Frame,	150 A, 3F	, 600 Vac	50/60Hz, 250	) Vdc	I		ı	1	·I	
15 A	350 A	750 A	HDL36015	HDL36015C	HGL36015	HGL36015C	HJL36015	HJL36015C	HLL36015	HLL36015C
20 A	350 A	750 A	HDL36020	HDL36020C	HGL36020	HGL36020C	HJL36020	HJL36020C	HLL36020	HLL36020C
25 A	350 A	750 A	HDL36025	HDL36025C	HGL36025	HGL36025C	HJL36025	HJL36025C	HLL36025	HLL36025C
30 A	350 A	750 A	HDL36030	HDL36030C	HGL36030	HGL36030C	HJL36030	HJL36030C	HLL36030	HLL36030C
35 A	400 A	850 A	HDL36035	HDL36035C	HGL36035	HGL36035C	HJL36035	HJL36035C	HLL36035	HLL36035C
40 A	400 A	850 A	HDL36040	HDL36040C	HGL36040	HGL36040C	HJL36040	HJL36040C	HLL36040	HLL36040C
45 A	400 A	850 A	HDL36045	HDL36045C	HGL36045	HGL36045C	HJL36045	HJL36045C	HLL36045	HLL36045C
50 A	400 A	850 A	HDL36050	HDL36050C	HGL36050	HGL36050C	HJL36050	HJL36050C	HLL36050	HLL36050C
60 A	800 A	1450 A	HDL36060	HDL36060C	HGL36060	HGL36060C	HJL36060	HJL36060C	HLL36060	HLL36060C
70 A	800 A	1450 A	HDL36070	HDL36070C	HGL36070	HGL36070C	HJL36070	HJL36070C	HLL36070	HLL36070C
80 A	800 A	1450 A	HDL36080	HDL36080C	HGL36080	HGL36080C	HJL36080	HJL36080C	HLL36080	HLL36080C
90 A	800 A	1450 A	HDL36090	HDL36090C	HGL36090	HGL36090C	HJL36090	HJL36090C	HLL36090	HLL36090C
100 A	900 A	1700 A	HDL36100	HDL36100C	HGL36100	HGL36100C	HJL36100	HJL36100C	HLL36100	HLL36100C
110 A	900 A	1700 A	HDL36110	HDL36110C	HGL36110	HGL36110C	HJL36110	HJL36110C	HLL36110	HLL36110C
125 A	900 A	1700 A	HDL36125	HDL36125C	HGL36125	HGL36125C	HJL36125	HJL36125C	HLL36125	HLL36125C
150 A	900 A	1700 A	HDL36150	HDL36150C	HGL36150	HGL36150C	HJL36150	HJL36150C	HLL36150	HLL36150C

<sup>&</sup>lt;sup>1</sup> Standard Lug Kit: AL150HD Terminal Wire Range: 14–3/0 AWG Al or Cu

 $<sup>^2</sup>$   $\,$  UL Listed/CSA Certified as current limiting circuit breakers.

 $<sup>^{3}</sup>$  100% rated circuit breakers have copper lugs and can be used with copper wire only.

<sup>&</sup>lt;sup>4</sup> HD and HG circuit breakers are true 2-pole construction.

#### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 15: PowerPact J-Frame 250 A Unit-Mount Thermal-Magnetic Circuit Breakers with Factory Sealed Trip Unit (Suitable for Reverse Connection)

	Adjusta	ble AC	Interrupti	Interrupting Rating									
Current	Magnet	Magnetic Trip		D			J <sup>1</sup>		L <sup>1</sup>		R <sup>1</sup>		
Rating @ 40 C	Hold	Trip	Standard (80%) Rated	100% Rated <sup>2</sup>									
J-Frame,	250 A, 2	P, 600 V	ac 50/60Hz	, 250 Vdc				•			•		
150 A <sup>3</sup>	750 A	1500 A	JDL26150	JDL26150C	JGL26150	JGL26150C	JJL26150	JJL26150C	JLL26150	JLL26150C	_	_	
175 A <sup>3</sup>	875 A	1750 A	JDL26175	JDL26175C	JGL26175	JGL26175C	JJL26175	JJL26175C	JLL26175	JLL26175C	_	_	
200 A <sup>4</sup>	1000 A	2000 A	JDL26200	JDL26200C	JGL26200	JGL26200C	JJL26200	JJL26200C	JLL26200	JLL26200C	_	_	
225 A <sup>4</sup>	1125 A	2250 A	JDL26225	JDL26225C	JGL26225	JGL26225C	JJL26225	JJL26225C	JLL26225	JLL26225C	_	_	
250 A <sup>4</sup>	1250 A	2500 A	JDL26250	JDL26250C	JGL26250	JGL26250C	JJL26250	JJL26250C	JLL26250	JLL26250C	_	_	
J-Frame,	250 A, 3	3P, 600 V	ac 50/60Hz	, 250 Vdc									
150 A <sup>3</sup>	750 A	1500 A	JDL36150	JDL36150C	JGL36150	JGL36150C	JJL36150	JJL36150C	JLL36150	JLL36150C	JRL36150	JRL36150C	
175 A <sup>3</sup>	875 A	1750 A	JDL36175	JDL36175C	JGL36175	JGL36175C	JJL36175	JJL36175C	JLL36175	JLL36175C	JRL36175	JRL361750	
200 A <sup>4</sup>	1000 A	2000 A	JDL36200	JDL36200C	JGL36200	JGL36200C	JJL36200	JJL36200C	JLL36200	JLL36200C	JRL36200	JRL36200C	
225 A <sup>4</sup>	1125 A	2250 A	JDL36225	JDL36225C	JGL36225	JGL36225C	JJL36225	JJL36225C	JLL36225	JLL36225C	JRL36225	JRL36225C	
250 A <sup>4</sup>	1250 A	2500 A	JDL36250	JDL36250C	JGL36250	JGL36250C	JJL36250	JJL36250C	JLL36250	JLL36250C	JRL36250	JRL36250C	

<sup>&</sup>lt;sup>1</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>&</sup>lt;sup>2</sup> 100% rated circuit breakers have copper lugs and can be used with copper wire only.

<sup>&</sup>lt;sup>3</sup> Standard Lug Kit: AL175JD Terminal Wire Range: 4-4/0 AWG Al or Cu

<sup>&</sup>lt;sup>4</sup> Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 16: H-Frame 150 A and J-Frame 250 A Electronic Trip UL Rated Circuit Breakers (600 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Elec	tronic Trip	Unit	Sensor	Interrupting Ratin	ıg			
Туре	Function	Trip Unit	Rating	D	G	J1	L <sup>2</sup>	R <sup>2</sup>
Standard (	80%) Rated 0	ircuit Break	ers, 3P					
			60 A <sup>3</sup>	HDL36060U31X	HGL36060U31X	HJL36060U31X	HLL36060U31X	HRL36060U31X
Standard	LI	3.22	100 A <sup>3</sup>	HDL36100U31X	HGL36100U31X	HJL36100U31X	HLL36100U31X	HRL36100U31X
Staridard		0.2-	150 A <sup>3</sup>	HDL36150U31X	HGL36150U31X	HJL36150U31X	HLL36150U31X	HRL36150U31X
			250 A <sup>4</sup>	JDL36250U31X	JGL36250U31X	JJL36250U31X	JLL36250U31X	JRL36250U31X
			60 A <sup>3</sup>	HDL36060U33X	HGL36060U33X	HJL36060U33X	HLL36060U33X	HRL36060U33X
Ctandard	LSI	3.2S <sup>2</sup>	100 A <sup>3</sup>	HDL36100U33X	HGL36100U33X	HJL36100U33X	HLL36100U33X	HRL36100U33X
Standard	LSI	3.23-	150 A <sup>3</sup>	HDL36150U33X	HGL36150U33X	HJL36150U33X	HLL36150U33X	HRL36150U33X
			250 A <sup>4</sup>	JDL36250U33X	JGL36250U33X	JJL36250U33X	JLL36250U33X	JRL36250U33X
			60 A <sup>3</sup>	HDL36060U43X	HGL36060U43X	HJL36060U43X	HLL36060U43X	HRL36060U43X
A 4	1.01	5.04	100 A <sup>3</sup>	HDL36100U43X	HGL36100U43X	HJL36100U43X	HLL36100U43X	HRL36100U43X
Ammeter	LSI	5.2A	150 A <sup>3</sup>	HDL36150U43X	HGL36150U43X	HJL36150U43X	HLL36150U43X	HRL36150U43X
			250 A <sup>4</sup>	JDL36250U43X	JGL36250U43X	JJL36250U43X	JLL36250U43X	JRL36250U43X
			60 A <sup>3</sup>	HDL36060U53X	HGL36060U53X	HJL36060U53X	HLL36060U53X	HRL36060U53X
_	1.01	5.05	100 A <sup>3</sup>	HDL36100U53X	HGL36100U53X	HJL36100U53X	HLL36100U53X	HRL36100U53X
Energy	Energy LSI 5.2E	5.2E	150 A <sup>3</sup>	HDL36150U53X	HGL36150U53X	HJL36150U53X	HLL36150U53X	HRL36150U53X
			250 A <sup>4</sup>	JDL36250U53X	JGL36250U53X	JJL36250U53X	JLL36250U53X	JRL36250U53X
-			60 A <sup>3</sup>	HDL36060U44X	HGL36060U44X	HJL36060U44X	HLL36060U44X	HRL36060U44X
		6.2A	100 A <sup>3</sup>	HDL36100U44X	HGL36100U44X	HJL36100U44X	HLL36100U44X	HRL36100U44X
Ammeter	LSIG		150 A <sup>3</sup>	HDL36150U44X	HGL36150U44X	HJL36150U44X	HLL36150U44X	HRL36150U44X
			250 A <sup>4</sup>	JDL36250U44X	JGL36250U44X	JJL36250U44X	JLL36250U44X	JRL36250U44X
			60 A <sup>3</sup>	HDL36060U54X	HGL36060U54X	HJL36060U54X	HLL36060U54X	HRL36060U54X
			100 A <sup>3</sup>	HDL36100U54X	HGL36100U54X	HJL36100U54X	HLL36100U54X	HRL36100U54X
Energy	LSIG	6.2E	150 A <sup>3</sup>	HDL36150U54X	HGL36150U54X	HJL36150U54X	HLL36150U54X	HRL36150U54X
			250 A <sup>4</sup>	JDL36250U54X	JGL36250U54X	JJL36250U54X	JLL36250U54X	JRL36250U54X
100% Rate	d Circuit Bre	akers, 3P <sup>5</sup>	<u> </u>		1	1	ı	
	İ		60 A <sup>3</sup>	HDL36060CU31X	HGL36060CU31X	HJL36060CU31X	HLL36060CU31X	HRL36060CU31X
			100 A <sup>3</sup>	HDL36100CU31X	HGL36100CU31X	HJL36100CU31X	HLL36100CU31X	HRL36100CU31X
Standard	LI	3.22	150 A <sup>3</sup>	HDL36150CU31X	HGL36150CU31X	HJL36150CU31X	HLL36150CU31X	HRL36150CU31X
			250 A <sup>4</sup>	JDL36250CU31X	JGL36250CU31X	JJL36250CU31X	JLL36250CU31X	JRL36250CU31X
				HDL36060CU33X	HGL36060CU33X	HJL36060CU33X	HLL36060CU33X	HRL36060CU33X
			60 A <sup>3</sup> 100 A <sup>3</sup>	HDL36100CU33X	HGL36100CU33X	HJL36100CU33X	HLL36100CU33X	HRL36100CU33X
Standard	LSI	3.2S <sup>2</sup>	150 A <sup>3</sup>	HDL36150CU33X	HGL36150CU33X	HJL36150CU33X	HLL36150CU33X	HRL36150CU33X
			250 A <sup>4</sup>	JDL36250CU33X	JGL36250CU33X	JJL36250CU33X	JLL36250CU33X	JRL36250CU33X
				HDL36060CU43X	HGL36060CU43X	HJL36060CU43X	HLL36060CU43X	HRL36060CU43X
			60 A <sup>3</sup> 100 A <sup>3</sup>	HDL36100CU43X	HGL36100CU43X	HJL36100CU43X	HLL36100CU43X	HRL36100CU43X
Ammeter	LSI	5.2A	150 A <sup>3</sup>	HDL36150CU43X	HGL36150CU43X	HJL36150CU43X	HLL36150CU43X	HRL36150CU43X
			250 A <sup>4</sup>	JDL36250CU43X	JGL36250CU43X	JJL36250CU43X	JLL36250CU43X	JRL36250CU43X
				HDL36060CU53X	HGL36060CU53X	HJL36060CU53X	HLL36060CU53X	HRL36060CU53X
			60 A <sup>3</sup> 100 A <sup>3</sup>					HRL36100CU53X
Energy	LSI	5.2E	150 A <sup>3</sup>	HDL36100CU53X HDL36150CU53X	HGL36100CU53X HGL36150CU53X	HJL36100CU53X HJL36150CU53X	HLL36100CU53X HLL36150CU53X	HRL36150CU53X
				1	ļ	1	<del> </del>	+
	I		250 A <sup>4</sup>	JDL36250CU53X	JGL36250CU53X	JJL36250CU53X	JLL36250CU53X	JRL36250CU53X

<sup>&</sup>lt;sup>1</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>100%</sup> rated circuit breakers have copper lugs and can be used with copper wire only.



<sup>&</sup>lt;sup>2</sup> 3P circuit breakers with this trip unit can be used for 2P applications.

Standard Lug Kit: AL150HD Terminal Wire Range: 14–3/0 AWG Al or Cu

<sup>&</sup>lt;sup>4</sup> Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu

For smaller wire range (4–4/0 AWG AI or Cu), replace the lug's wire binding screws with the larger binding screws provided.

#### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 17: J-Frame 250 A Mission Critical Electronic Trip UL Rated Circuit Breakers (3P, 480Y/277 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Ele	Electronic Trip Unit		Sensor	Interrupting Rating <sup>1</sup>						
Туре	Function	Trip Unit	Rating	D	G	J	L			
Standard (80	•	<b>'</b>								
Standard	LI	3.2-W	250 A	JDL34250WU31X	JGL34250WU31X	JJL34250WU31X	JLL34250WU31X			
Standard	LSI	3.2S-W	250 A	JDL34250WU33X	JGL34250WU33X	JJL34250WU33X	JLL34250WU33X			
Ammeter	LSI	5.2A-W	250 A	JDL34250WU43X	JGL34250WU43X	JJL34250WU43X	JLL34250WU43X			
Energy	LSI	5.2E-W	250 A	JDL34250WU53X	JGL34250WU53X	JJL34250WU53X	JLL34250WU53X			
Ammeter	LSIG	6.2A-W	250 A	JDL34250WU44X	JGL34250WU44X	JJL34250WU44X	JLL34250WU44X			
Energy	LSIG	6.2E-W	250 A	JDL34250WU54X	JGL34250WU54X	JJL34250WU54X	JLL34250WU54X			

Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu For smaller wire range (4-4/0 AWG Al or Cu), replace the lug's wire binding screws with the larger binding screws provided.

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Circuit Breakers

# **I-Line Circuit Breaker Catalog Numbers**

Table 18: PowerPact H-Frame 150 A I-Line Thermal-Magnetic Circuit Breakers<sup>1</sup> with Factory Sealed Trip Unit (Suitable for Reverse Connection)<sup>2</sup>

Current	Fixed AC	Magnetic Trip	Interrupting Ra	ting <sup>3</sup> Standard (80	9%) Rated	
Rating at 40°C	Hold	Trip	D	G	J <sup>4</sup>	L <sup>4</sup>
H-Frame, 1	50 A, 2P, 60	00 Vac 50/60Hz	, 250 Vdc			•
15 A	350 A	750 A	HDA26015()	HGA26015()	HJA26015()	HLA26015()
20 A	350 A	750 A	HDA26020()	HGA26020()	HJA26020()	HLA26020()
25 A	350 A	750 A	HDA26025()	HGA26025()	HJA26025()	HLA26025()
30 A	350 A	750 A	HDA26030()	HGA26030()	HJA26030()	HLA26030()
35 A	400 A	850 A	HDA26035()	HGA26035()	HJA26035()	HLA26035()
40 A	400 A	850 A	HDA26040()	HGA26040()	HJA26040()	HLA26040()
45 A	400 A	850 A	HDA26045()	HGA26045()	HJA26045()	HLA26045()
50 A	400 A	850 A	HDA26050()	HGA26050()	HJA26050()	HLA26050()
60 A	800 A	1450 A	HDA26060()	HGA26060()	HJA26060()	HLA26060()
70 A	800 A	1450 A	HDA26070()	HGA26070()	HJA26070()	HLA26070()
80 A	800 A	1450 A	HDA26080()	HGA26080()	HJA26080()	HLA26080()
90 A	800 A	1450 A	HDA26090()	HGA26090()	HJA26090()	HLA26090()
100 A	900 A	1700 A	HDA26100()	HGA26100()	HJA26100()	HLA26100()
110 A	900 A	1700 A	HDA26110()	HGA26110()	HJA26110()	HLA26110()
125 A	900 A	1700 A	HDA26125()	HGA26125()	HJA26125()	HLA26125()
150 A	900 A	1700 A	HDA26150()	HGA26150()	HJA26150()	HLA26150()
H-Frame, 1	50 A, 3P, 60	00 Vac 50/60Hz	, 250 Vdc			•
15 A	350 A	750 A	HDA36015	HGA36015	HJA36015	HLA36015
20 A	350 A	750 A	HDA36020	HGA36020	HJA36020	HLA36020
25 A	350 A	750 A	HDA36025	HGA36025	HJA36025	HLA36025
30 A	350 A	750 A	HDA36030	HGA36030	HJA36030	HLA36030
35 A	400 A	850 A	HDA36035	HGA36035	HJA36035	HLA36035
40 A	400 A	850 A	HDA36040	HGA36040	HJA36040	HLA36040
45 A	400 A	850 A	HDA36045	HGA36045	HJA36045	HLA36045
50 A	400 A	850 A	HDA36050	HGA36050	HJA36050	HLA36050
60 A	800 A	1450 A	HDA36060	HGA36060	HJA36060	HLA36060
70 A	800 A	1450 A	HDA36070	HGA36070	HJA36070	HLA36070
80 A	800 A	1450 A	HDA36080	HGA36080	HJA36080	HLA36080
90 A	800 A	1450 A	HDA36090	HGA36090	HJA36090	HLA36090
100 A	900 A	1700 A	HDA36100	HGA36100	HJA36100	HLA36100
110 A	900 A	1700 A	HDA36110	HGA36110	HJA36110	HLA36110
125 A	900 A	1700 A	HDA36125	HGA36125	HJA36125	HLA36125
150 A	900 A	1700 A	HDA36150	HGA36150	HJA36150	HLA36150

<sup>&</sup>lt;sup>1</sup> Standard Lug Kit: AL150HD Terminal Wire Range: 14–3/0 AWG Al or Cu.

<sup>&</sup>lt;sup>2</sup> No 100% I-Line available.

<sup>&</sup>lt;sup>3</sup> () Indicates phasing. See "Catalog Numbering" on page 8.

<sup>&</sup>lt;sup>4</sup> UL Listed/CSA Certified as current limiting circuit breakers.

#### PowerPact™ H-, J-, and L-Frame Circuit Breakers **Circuit Breakers**

PowerPact J-Frame 250A I-Line Thermal-Magnetic Circuit Breakers with Factory Table 19: Sealed Trip Unit (Suitable for Reverse Connection)<sup>1</sup>

Current Rating @	Adjustable AC Magnetic Trip		Interrupting Rating <sup>2</sup> Standard (80%) Rated							
40 C	Hold	Trip	D	G	<b>J</b> 3	L <sup>3</sup>	R <sup>3</sup>			
J-Frame, 2	50 A, 2P, 60	00 Vac 50/6	60Hz, 250 Vdc							
150 A <sup>4</sup>	750 A	1500 A	JDA26150()	JGA26150()	JJA26150()	_	_			
175 A <sup>4</sup>	875 A	1750 A	JDA26175()	JGA26175()	JJA26175()	_	_			
200 A <sup>5</sup>	1000 A	2000 A	JDA26200()	JGA26200()	JJA26200()	_	_			
225 A <sup>5</sup>	1125 A	2250 A	JDA26225()	JGA26225()	JJA26225()	_	_			
250 A <sup>5</sup>	1250 A	2500 A	JDA26250()	JGA26250()	JJA26250()	_	_			
J-Frame, 2	50 A, 3P, 60	00 Vac 50/6	60Hz, 250 Vdc							
150 A <sup>4</sup>	750 A	1500 A	JDA36150	JGA36150	JJA36150	JLA36150	JRA36150			
175 A <sup>4</sup>	875 A	1750 A	JDA36175	JGA36175	JJA36175	JLA36175	JRA36175			
200 A <sup>5</sup>	1000 A	2000 A	JDA36200	JGA36200	JJA36200	JLA36200	JRA36200			
225 A <sup>5</sup>	1125 A	2250 A	JDA36225	JGA36225	JJA36225	JLA36225	JRA36225			
250 A <sup>5</sup>	1250 A	2500 A	JDA36250	JGA36250	JJA36250	JLA36250	JRA36250			

No 100% I-Line available.

 $<sup>^{2}</sup>$  () Indicates phasing. See "Catalog Numbering" on page 8.

<sup>&</sup>lt;sup>3</sup> UL Listed/CSA Certified as current limiting.

<sup>&</sup>lt;sup>4</sup> Standard Lug Kit: AL175JD Terminal Wire Range: 4–4/0 AWG Al or Cu.

<sup>&</sup>lt;sup>5</sup> Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu.

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 20: H-Frame 150 A and J-Frame 250 A I-Line Standard (80%) Rated Electronic Trip UL Rated Circuit Breakers (3P, 600 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection <sup>1</sup>

Elec	ctronic Trip	Unit	Sensor	Interrupting Ratin	g									
Туре	Function	Trip Unit	Rating	D	G	J <sup>2</sup>	L <sup>2</sup>	R <sup>2</sup>						
			60 A <sup>4</sup>	HDA36060U31X	HGA36060U31X	HJA36060U31X	HLA36060U31X	HRA36060U31X						
Standard	LI	3.23	100 A <sup>4</sup>	HDA36100U31X	HGA36100U31X	HJA36100U31X	HLA36100U31X	HRA36100U31X						
Standard	LI	3.20	150 A <sup>4</sup>	HDA36150U31X	HGA36150U31X	HJA36150U31X	HLA36150U31	HRA36150U31						
			250 A <sup>3</sup> , <sup>5</sup>	JDA36250U31X	JGA36250U31X	JJA36250U31X	JLA36250U31X	JRA36250U31X						
			60 A <sup>4</sup>	HDA36060U33X	HGA36060U33X	HJA36060U33X	HLA36060U33X	HRA36060U33X						
Standard	LSI	3.2S <sup>3</sup>	100 A <sup>4</sup>	HDA36100U33X	HGA36100U33X	HJA36100U33X	HLA36100U33X	HRA36100U33X						
Siariuaru	LOI	3.23	150 A <sup>4</sup>	HDA36150U33X	HGA36150U33X	HJA36150U33X	HLA36150U33X	HRA36150U33X						
			250 A <sup>3</sup> , <sup>5</sup>	JDA36250U33X	JGA36250U33X	JJA36250U33X	JLA36250U33X	JRA36250U33X						
			60 A <sup>4</sup>	HDA36060U43X	HGA36060U43X(	HJA36060U43X	HLA36060U43X	HRA36060U43X						
Ammeter	Ammeter LSI 5.2A	100 A <sup>4</sup>	HDA36100U43X	HGA36100U43X	HJA36100U43X	HLA36100U43X	HRA36100U43X							
Ammeter			5.2A	150 A <sup>4</sup>	HDA36150U43X	HGA36150U43X	HJA36150U43X	HLA36150U43X	HRA36150U43X					
			250 A <sup>3</sup> , <sup>5</sup>	JDA36250U43X	JGA36250U43X	JJA36250U43X	JLA36250U43X	JRA36250U43X						
						60 A <sup>4</sup>	HDA36060U53X	HGA36060U53X	HJA36060U53X	HLA36060U53X	HRA36060U53X			
Energy	LSI	E 0E	100 A <sup>4</sup>	HDA36100U53X	HGA36100U53X	HJA36100U53X	HLA36100U53X	HRA36100U53X						
Ellergy	LOI	5.2E	5.2E	5.2E	5.2E	5.2E	5.2E	5.2E	150 A <sup>4</sup>	HDA36150U53X	HGA36150U53X	HJA36150U53X	HLA36150U53X	HRA36150U53X
			250 A <sup>3</sup> , <sup>5</sup>	JDA36250U53X	JGA36250U53X	JJA36250U53X	JLA36250U53X	JRA36250U53X						
			60 A <sup>4</sup>	HDA36060U44X	HGA36060U44X	HJA36060U44X	HLA36060U44X	HRA36060U44X						
Ammeter	LSIG	6.2A	100 A <sup>4</sup>	HDA36100U44X	HGA36100U44X	HJA36100U44X	HLA36100U44X	HRA36100U44X						
Ammeter	LSIG	0.2A	150 A <sup>4</sup>	HDA36150U44X	HGA36150U44X	HJA36150U44X	HLA36150U44X	HRA36150U44X						
			250 A <sup>3</sup> , <sup>5</sup>	JDA36250U44X	JGA36250U44X	JJA36250U44X	JLA36250U44X	JRA36250U44X						
			60 A <sup>4</sup>	HDA36060U54X	HGA36060U54X	HJA36060U54X	HLA36060U54X	HRA36060U54X						
Enorm	LSIG	6.2E	0.05	0.05	100 A <sup>4</sup>	HDA36100U54X	HGA36100U54X	HJA36100U54X	HLA36100U54X	HRA36100U54X				
Energy	LSIG		150 44	HDA36150U54X	HGA36150U54X	HJA36150U54X(	HLA36150U54X	HRA36150U54X						
			250 A <sup>3</sup> , <sup>5</sup>	JDA36250U54X	JGA36250U54X	JJA36250U54X	JLA36250U54X	JRA36250U54X						

<sup>&</sup>lt;sup>1</sup> No 100% I-Line available.

Table 21: J-Frame 250 A Mission Critical I-Line Standard (80%) Rated Electronic Trip UL Rated Circuit Breakers (3P, 480Y/277 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Ele	Electronic Trip Unit		Sensor	Interrupting Rating <sup>1</sup> .						
Туре	Function	Trip Unit	Rating	D	G	J	L			
Standard	LI	3.2-W	250 A	JDA34250WU31X	JGA34250WU31X	JJA34250WU31X	JLA34250WU31X			
Standard	LSI	3.2S-W	250 A	JDA34250WU33X	JGA34250WU33X	JJA34250WU33X	JLA34250WU33X			
Ammeter	LSI	5.2A-W	250 A	JDA34250WU43X	JGA34250WU43X	JJA34250WU43X	JLA34250WU43X			
Energy	LSI	5.2E-W	250 A	JDA34250WU53X	JGA34250WU53X	JJA34250WU53X	JLA34250WU53X			
Ammeter	LSIG	6.2A-W	250 A	JDA34250WU44X	JGA34250WU44X	JJA34250WU44X	JLA34250WU44X			
Energy	LSIG	6.2E-W	250 A	JDA34250WU54X	JGA34250WU54X	JJA34250WU54X	JLA34250WU54X			

Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu For smaller wire range (4-4/0 AWG Al or Cu), replace the lug's wire binding screws with the larger binding screws provided.



<sup>&</sup>lt;sup>2</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>3 3</sup>P circuit breakers with this trip unit can be used for 2P applications.

Standard Lug Kit: AL150HD Terminal Wire Range: 14–3/0 AWG Al or Cu

<sup>5</sup> Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu For smaller wire range (4-4/0 AWG Al or Cu), replace the lug's wire binding screws with the larger binding screws provided.

#### Circuit Breakers with Field-Interchangeable Trip Units Catalog Numbers

Table 22: H-Frame 150 A Circuit Breaker Frame<sup>1</sup> with Field-Interchangeable Thermal-Magnetic Trip Units<sup>2</sup> (3P, 600 Vac, 250 Vdc)

Ampere Rating	Fixed AC Magnetic Trip		Interrupting Rating				
			D	G	J <sup>3</sup>	L <sup>3</sup>	
	Hold	Trip	Cat. No.	Cat. No.	Cat. No.	Cat. No.	
15 A	350 A	750 A	HDL36015T	HGL36015T	HJL36015T	HLL36015T	
20 A	350 A	750 A	HDL36020T	HGL36020T	HJL36020T	HLL36020T	
25 A	350 A	750 A	HDL36025T	HGL36025T	HJL36025T	HLL36025T	
30 A	350 A	750 A	HDL36030T	HGL36030T	HJL36030T	HLL36030T	
35 A	400 A	850 A	HDL36035T	HGL36035T	HJL36035T	HLL36035T	
40 A	400 A	850 A	HDL36040T	HGL36040T	HJL36040T	HLL36040T	
45 A	400 A	850 A	HDL36045T	HGL36045T	HJL36045T	HLL36045T	
50 A	400 A	850 A	HDL36050T	HGL36050T	HJL36050T	HLL36050T	
60 A	800 A	1450 A	HDL36060T	HGL36060T	HJL36060T	HLL36060T	
70 A	800 A	1450 A	HDL36070T	HGL36070T	HJL36070T	HLL36070T	
80 A	800 A	1450 A	HDL36080T	HGL36080T	HJL36080T	HLL36080T	
90 A	800 A	1450 A	HDL36090T	HGL36090T	HJL36090T	HLL36090T	
100 A	900 A	1700 A	HDL36100T	HGL36100T	HJL36100T	HLL36100T	
110 A	900 A	1700 A	HDL36110T	HGL36110T	HJL36110T	HLL36110T	
125 A	900 A	1700 A	HDL36125T	HGL36125T	HJL36125T	HLL36125T	
150 A	900 A	1700 A	HDL36150T	HGL36150T	HJL36150T	HLL36150T	

<sup>&</sup>lt;sup>1</sup> Standard Lug Kit: AL150HD Terminal Wire Range: 14–3/0 AWG Al or Cu.

Table 23: J-Frame 250 A Circuit Breaker Frame with Field-Interchangeable Thermal-Magnetic Trip Units<sup>1</sup> (3P, 600 Vac, 250 Vdc)

Ampere Rating	Adjustable AC Magnetic Trip		Interrupting F	Interrupting Rating				
			D	G	J <sup>2</sup>	L <sup>3</sup>		
	Low	High	Cat. No.	Cat. No.	Cat. No.	Cat. No.		
150 A <sup>3</sup>	750 A	1500 A	JDL36150T	JGL36150T	JJL36150T	JLL36150T		
175 A <sup>3</sup>	875 A	1750 A	JDL36175T	JGL36175T	JJL36175T	JLL36175T		
200 A <sup>4</sup>	1000 A	2000 A	JDL36200T	JGL36200T	JJL36200T	JLL36200T		
225 A <sup>4</sup>	1125 A	2250 A	JDL36225T	JGL36225T	JJL36225T	JLL36225T		
250 A <sup>4</sup>	1250 A	2500 A	JDL36250T	JGL36250T	JJL36250T	JLL36250T		

Circuit breakers will be labeled with Line and Load markings and are not suitable for reverse connections. Only available on standard (80%) rated 3P unit-mount circuit breakers. Not available in R interrupting rating. Not available with I-Line™ or Plug-In constructions.

<sup>&</sup>lt;sup>2</sup> Circuit breakers will be labeled with Line and Load markings and are not suitable for reverse connections. Only available on standard (80%) rated 3P unit-mount circuit breakers. Not available in R interrupting rating. Not available with I-Line or Plug-In constructions.

<sup>&</sup>lt;sup>3</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>&</sup>lt;sup>2</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>3</sup> Standard Lug Kit: AL175JD Terminal Wire Range: 4–4/0 AWG Al or Cu.

<sup>&</sup>lt;sup>4</sup> Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu.

#### PowerPact™ H-, J-, and L-Frame Circuit Breakers **Circuit Breakers**

H-Frame 150 A and J-Frame 250 A 3P Circuit Breakers with Lugs and Field-Interchangeable Electronic Trip Table 24: Units<sup>1</sup>, <sup>2</sup> (Standard (80%) Rated, 600 Vac, 50/60 Hz)

Elec	Electronic Trip Unit			Interrupting Rating				
Туре	Function	Trip Unit	Size	D	G	J <sup>3</sup>	L <sup>3</sup>	
			60 A <sup>4</sup>	HDL36060TU31X	HGL36060TU31X	HJL36060TU31X	HLL36060TU31X	
Ctondord	LI	3.2	100 A <sup>4</sup>	HDL36100TU31X	HGL36100TU31X	HJL36100TU31X	HLL36100TU31X	
Standard	LI	3.2	150 A <sup>4</sup>	HDL36150TU31X	HGL36150TU31X	HJL36150TU31X	HLL36150TU31X	
			250 A <sup>5</sup>	JDL36250TU31X	JGL36250TU31X	JJL36250TU31X	JLL36250TU31X	
			60 A <sup>4</sup>	HDL36060TU33X	HGL36060TU33X	HJL36060TU33X	HLL36060TU33X	
Standard	LSI	0.00	100 A <sup>4</sup>	HDL36100TU33X	HGL36100TU33X	HJL36100TU33X	HLL36100TU33X	
Standard	LSI	3.2S	150 A <sup>4</sup>	HDL36150TU33X	HGL36150TU33X	HJL36150TU33X	HLL36150TU33X	
			250 A <sup>5</sup>	JDL36250TU33X	JGL36250TU33X	JJL36250TU33X	JLL36250TU33X	
	LSI	5.2A	60 A <sup>4</sup>	HDL36060TU43X	HGL36060TU43X	HJL36060TU43X	HLL36060TU43X	
A t			5 O A	100 A <sup>4</sup>	HDL36100TU43X	HGL36100TU43X	HJL36100TU43X	HLL36100TU43X
Ammeter			150 A <sup>4</sup>	HDL36150TU43X	HGL36150TU43X	HJL36150TU43X	HLL36150TU43X	
			250 A <sup>5</sup>	JDL36250TU43X	JGL36250TU43X	JJL36250TU43X	JLL36250TU43X	
	LSI	5.2E	60 A <sup>4</sup>	HDL36060TU53X	HGL36060TU53X	HJL36060TU53X	HLL36060TU53X	
F			100 A <sup>4</sup>	HDL36100TU53X	HGL36100TU53X	HJL36100TU53X	HLL36100TU53X	
Energy			150 A <sup>4</sup>	HDL36150TU53X	HGL36150TU53X	HJL36150TU53X	HLL36150TU53X	
			250 A <sup>5</sup>	JDL36250TU53X	JGL36250TU53X	JJL36250TU53X	JLL36250TU53X	
			60 A <sup>4</sup>	HDL36060TU44X	HGL36060TU44X	HJL36060TU44X	HLL36060TU44X	
Ammeter	LSIG	6.2A	100 A <sup>4</sup>	HDL36100TU44X	HGL36100TU44X	HJL36100TU44X	HLL36100TU44X	
Ammeter	LSIG	0.2A	150 A <sup>4</sup>	HDL36150TU44X	HGL36150TU44X	HJL36150TU44X	HLL36150TU44X	
			250 A <sup>5</sup>	JDL36250TU44X	JGL36250TU44X	JJL36250TU44X	JLL36250TU44X	
			60 A <sup>4</sup>	HDL36060TU54X	HGL36060TU54X	HJL36060TU54X	HLL36060TU54X	
Гоо <i>на</i> :	LSIG	6.05	100 A <sup>4</sup>	HDL36100TU54X	HGL36100TU54X	HJL36100TU54X	HLL36100TU54X	
Energy	LSIG	6.2E	150 A <sup>4</sup>	HDL36150TU54X	HGL36150TU54X	HJL36150TU54X	HLL36150TU54X	
			250 A <sup>5</sup>	JDL36250TU54X	JGL36250TU54X	JJL36250TU54X	JLL36250TU54X	

<sup>&</sup>lt;sup>1</sup> Circuit breakers will be labeled with Line and Load markings and are not suitable for reverse connections.

<sup>&</sup>lt;sup>5</sup> Standard Lug Kit: AL250JD Terminal Wire Range: 3/0 AWG-350 kcmil Al or Cu. For smaller wire range (4-4/0 AWG AI or Cu), replace the lug's wire binding screws with the larger binding screws provided.







H-Frame

01/2014

Trip	Unit

15–60 A H-Frame		70–150 A H-Fr	70-150 A H-Frame		150-250 A J-Frame	
Amperage	Cat. No.	Amperage	Cat. No.	Amperage	Cat. No.	
15 A	HT3015	70 A	HT3070	150 A	JT3150	
20 A	HT3020	80 A	HT3080	175 A	JT3175	
25 A	HT3025	90 A	HT3090	200 A	JT3200	
30 A	HT3030	100 A	HT3100	225 A	JT3225	
35 A	HT3035	110 A	HT3110	250 A	JT3250	
40 A	HT3040	125 A	HT3125	_	_	
45 A	HT3045	150 A	HT3150	_	_	
50 A	HT3050	_	_	_	_	
60 A	HT3060	_	_	_	_	

<sup>2</sup> Only available on 3P unit-mount circuit breakers. Not available in R interrupting rating. Not available with I-Line or Plug-in constructions.

<sup>&</sup>lt;sup>3</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>&</sup>lt;sup>4</sup> Standard Lug Kit: AL150HD Terminal Wire Range: 14–3/0 AWG Al or C.

#### PowerPact™ H-, J-, and L-Frame Circuit Breakers **Circuit Breakers**

H-Frame and J-Frame 3P Field-Installable Micrologic Electronic Trip Units1 Table 26:

Electronic Trip Unit			Ammana Cattings	Trip Unit
Туре	Function	Trip Unit	- Ampere Settings	Cat. No.
			15-20-25-30-35-40-45-50-60	HE3060U31X
			35-40-45-50-60-70-80-90-100	HE3100U31X
	LI	3.2	50-60-70-80-90-100-110-125-150	HE3150U31X
Standard			70-80-100-125-150-175-200-225-250	JE3250U31X
Sianuaru			15-20-25-30-35-40-45-50-60	HE3060U33X
	LSI	3.2S	35-40-45-50-60-70-80-90-100	HE3100U33X
	LSI	3.28	50-60-70-80-90-100-110-125-150	HE3150U33X
			70-80-100-125-150-175-200-225-250	JE3250U33X
	LSI	5.2A	15–60	HE3060U43X
			35–100	HE3100U43X
			50–150	HE3150U43X
Ammeter			70–250	JE3250U43X
Ammeter		6.2A	15–60	HE3060U44X
	LSIG		35–100	HE3100U44X
	LSIG		50–150	HE3150U44X
			70–250	JE3250U44X
			15–60	HE3060U53X
	LSI	5.2E	35–100	HE3100U53X
	LSI		50-150	HE3150U53X
_			70–250	JE3250U53X
Energy			15–60	HE3060U54X
	LSIG	6.05	35–100	HE3100U54X
	LSIG	6.2E	50–150	HE3150U54X
			70–250	JE3250U54X

<sup>&</sup>lt;sup>1</sup> Electronic trip units cannot be used for DC applications.

H-Frame 150A and J-Frame 250 A 3P Basic Circuit Breaker Frame Without Table 27: Terminations or Trip Unit (600 Vac, 250 Vdc<sup>1</sup>)

Circuit		Interrupting Rating					
Breaker	Ampere Rating	D	G	J <sup>2</sup>	L <sup>2</sup>		
Frame	3	Cat. No.	Cat. No.	Cat. No.	Cat. No.		
H-Frame <sup>3</sup>	15–60 A	HDF36000F06	HGF36000F06	HJF36000F06	HLF36000F06		
n-riames	70–150 A	HDF36000F15	HGF36000F15	HJF36000F15	HLF36000F15		
J-Frame	150–250 A	JDF36000F25	JGF36000F25	JJF36000F25	JLF36000F25		

<sup>&</sup>lt;sup>1</sup> Not suitable for reverse connection.

<sup>&</sup>lt;sup>2</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>&</sup>lt;sup>3</sup> Field-installable trip units must match frame ampere rating.

# **L-Frame Circuit Breaker Catalog Numbers**

# **Unit-Mount Circuit Breaker Catalog Numbers**

Table 28: L-Frame 600 A Electronic Trip UL Rated 3P Circuit Breakers (600 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

	•	-		1	•					
Elec	tronic Trip	Unit	Sensor	Interrupting Rating (2nd Letter of Catalog Number)						
Туре	Function	Trip Unit	Rating	D	G	J1	L1	R <sup>1</sup>		
Standard (8	Standard (80%) Rated, 600 Vac, 50/60 Hz									
			250 A <sup>3</sup>	LDL36250U31X	LGL36250U31X	LJL36250U31X	LLL36250U31X	LRL36250U31X		
Standard	LI	3.32	400 A <sup>4</sup>	LDL36400U31X	LGL36400U31X	LJL36400U31X	LLL36400U31X	LRL36400U31X		
			600 A <sup>4</sup>	LDL36600U31X	LGL36600U31X	LJL36600U31X	LLL36600U31X	LRL36600U31X		
			250 A <sup>3</sup>	LDL36250U33X	LGL36250U33X	LJL36250U33X	LLL36250U33X	LRL36250U33X		
Standard	LSI	3.3S <sup>2</sup>	400 A <sup>4</sup>	LDL36400U33X	LGL36400U33X	LJL36400U33X	LLL36400U33X	LRL36400U33X		
			600 A <sup>4</sup>	LDL36600U33X	LGL36600U33X	LJL36600U33X	LLL36600U33X	LRL36600U33X		
Ammeter	LSI	5.3A	400 A <sup>4</sup>	LDL36400U43X	LGL36400U43X	LJL36400U43X	LLL36400U43X	LRL36400U43X		
Ammeter	LOI	5.3A	600 A <sup>4</sup>	LDL36600U43X	LGL36600U43X	LJL36600U43X	LLL36600U43X	LRL36600U43X		
Energy	LSI	5.3E	400 A <sup>4</sup>	LDL36400U53X	LGL36400U53X	LJL36400U53X	LLL36400U53X	LRL36400U53X		
Lifelgy	LOI	5.5L	600 A <sup>4</sup>	LDL36600U53X	LGL36600U53X	LJL36600U53X	LLL36600U53X	LRL36600U53X		
Ammeter	LSIG	6.3A	400 A <sup>4</sup>	LDL36400U44X	LGL36400U44X	LJL36400U44X	LLL36400U44X	LRL36400U44X		
Animeter	LSIG	0.3A	600 A <sup>4</sup>	LDL36600U44X	LGL36600U44X	LJL36600U44X	LLL36600U44X	LRL36600U44X		
Energy	LSIG	6.3E	400 A <sup>4</sup>	LDL36400U54X	LGL36400U54X	LJL36400U54X	LLL36400U54X	LRL36400U54X		
Lifelgy	LSIG		600 A <sup>4</sup>	LDL36600U54X	LGL36600U54X	LJL36600U54X	LLL36600U54X	LRL36600U54X		
100% Rated	, 600 Vac, 50	/60 Hz								
Standard	LI	3.32	250 A <sup>3</sup>	LDL36250CU31X	LGL36250CU31X	LJL36250CU31X	LLL36250CU31X	LRL36250CU31X		
Statiuatu	LI	3.32	400 A <sup>4</sup>	LDL36400CU31X	LGL36400CU31X	LJL36400CU31X	LLL36400CU31X	LRL36400CU31X		
Ctondord	LSI	0.002	250 A <sup>3</sup>	LDL36250CU33X	LGL36250CU33X	LJL36250CU33X	LLL36250CU33X	LRL36250CU33X		
Standard	LSI	3.3S <sup>2</sup>	400 A <sup>4</sup>	LDL36400CU33X	LGL36400CU33X	LJL3640C0U33X	LLL36400CU33X	LRL36400CU33X		
Ammeter	LSI	5.3A	400 A <sup>4</sup>	LDL36400CU43X	LGL36400CU43X	LJL36400CU43X	LLL36400CU43X	LRL36400CU43X		
Energy	LSI	5.3E	400 A <sup>4</sup>	LDL36400CU53X	LGL36400CU53X	LJL36400CU53X	LLL36400CU53X	LRL36400CU53X		
Ammeter	LSIG	6.3A	400 A <sup>4</sup>	LDL36400CU44X	LGL36400CU44X	LJL36400CU44X	LLL36400CU44X	LRL36400CU44X		
Energy	LSIG	6.3E	400 A <sup>4</sup>	LDL36400CU54X	LGL36400CU54X	LJL36400CU54X	LLL36400CU54X	LRL36400CU54X		

UL Listed/CSA Certified as current limiting circuit breakers.

01/2014

<sup>&</sup>lt;sup>2</sup> 3P circuit breakers with this trip unit can be used for 2P applications.

<sup>3</sup> Standard Lug Kit: AL400L61K3 Terminal Wire Range: (1) 2 AWG-600 kcmil Cu or (1) 2 AWG-500 kcmil Al. Type of Terminal Shield: Short.

<sup>&</sup>lt;sup>4</sup> Standard Lug Kit: AL600LS52K3 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 29: L-Frame 600 A Mission Critical Standard (80%) Rated Electronic Trip UL Rated 3P Circuit Breakers (480Y/277 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

El	ectronic Trip	Unit	Sensor	Interrupting Rating (2nd Letter of Catalog Number)					
Туре	Function	Trip Unit	Rating	D	G	J	L		
			250 A <sup>1</sup>	LDL34250WU31X	LGL34250WU31X	LJL34250WU31X	LLL34250WU31X		
Standard	LI	3.3-W	400 A <sup>2</sup>	LDL34400WU31X	LGL34400WU31X	LJL34400WU31X	LLL34400WU31X		
			600 A <sup>2</sup>	LDL34600WU31X	LGL34600WU31X	LJL34600WU31X	LLL34600WU31X		
			250 A <sup>1</sup>	LDL34250WU33X	LGL34250WU33X	LJL34250WU33X	LLL34250WU33X		
Standard	LSI	3.3S-W	400 A <sup>2</sup>	LDL34400WU33X	LGL34400WU33X	LJL34400WU33X	LLL34400WU33X		
			600 A <sup>2</sup>	LDL34600WU33X	LGL34600WU33X	LJL34600WU33X	LLL34600WU33X		
A t	1.01	5.3A-W	400 A <sup>2</sup>	LDL34400WU43X	LGL34400WU43X	LJL34400WU43X	LLL34400WU43X		
Ammeter	LSI		600 A <sup>2</sup>	LDL34600WU43X	LGL34600WU43X	LJL34600WU43X	LLL34600WU43X		
F	1.01	5 OF W	400 A <sup>2</sup>	LDL34400WU53X	LGL34400WU53X	LJL34400WU53X	LLL34400WU53X		
Energy	LSI	5.3E-W	600 A <sup>2</sup>	LDL34600WU53X	LGL34600WU53X	LJL34600WU53X	LLL34600WU53X		
A 4	1.010	0.04.14	400 A <sup>2</sup>	LDL34400WU44X	LGL34400WU44X	LJL34400WU44X	LLL34400WU44X		
Ammeter	LSIG	6.3A-W	600 A <sup>2</sup>	LDL34600WU44X	LGL34600WU44X	LJL34600WU44X	LLL34600WU44X		
	1.010	6 2F W	400 A <sup>2</sup>	LDL34400WU54X	LGL34400WU54X	LJL34400WU54X	LLL34400WU54X		
Energy	LSIG	6.3E-W	600 A <sup>2</sup>	LDL34600WU54X	LGL34600WU54X	LJL34600WU54X	LLL34600WU54X		

<sup>1</sup> Standard Lug Kit: AL400L61K3 Terminal Wire Range: (1) 2 AWG-600 kcmil Cu or (1) 2 AWG-500 kcmil Al. Type of Terminal Shield: Short.

<sup>&</sup>lt;sup>2</sup> Standard Lug Kit: AL600LS52K3 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 30: L-Frame 600 A Electronic Trip UL Rated 4P Circuit Breakers
(600 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Elec	tronic Trip	Unit	Sensor	Interrupting Ratin	g (2nd Letter of Ca	atalog Number)		
Туре	Function	Trip Unit	Rating	D	G	J <sup>1</sup>	L1	R1
Standard (8	0%) Rated, (	600 Vac, 50/6	60 Hz	•	•	•	•	•
			250 A <sup>2</sup>	LDL46250U31X	LGL46250U31X	LJL46250U31X	LLL46250U31X	LRL46250U31X
Standard	LI	3.3	400 A <sup>3</sup>	LDL46400U31X	LGL46400U31X	LJL46400U31X	LLL46400U31X	LRL46400U31X
			600 A <sup>3</sup>	LDL46600U31X	LGL46600U31X	LJL46600U31X	LLL46600U31X	LRL46600U31X
			250 A <sup>2</sup>	LDL46250U33X	LGL46250U33X	LJL46250U33X	LLL46250U33X	LRL46250U33X
Standard	LSI	3.3S	400 A <sup>3</sup>	LDL46400U33X	LGL46400U33X	LJL46400U33X	LLL46400U33X	LRL46400U33X
			600 A <sup>3</sup>	LDL46600U33X	LGL46600U33X	LJL46600U33X	LLL46600U33X	LRL46600U33X
Ammotor	1.01	5.3A	400 A <sup>3</sup>	LDL46400U43X	LGL46400U43X	LJL46400U43X	LLL46400U43X	LRL46400U43X
Anmeter	Ammeter LSI	5.3A	600 A <sup>3</sup>	LDL46600U43X	LGL46600U43X	LJL46600U43X	LLL46600U43X	LRL46600U43X
Energy	1.01	5.3E	400 A <sup>3</sup>	LDL46400U53X	LGL46400U53X	LJL46400U53X	LLL46400U53X	LRL46400U53X
Energy	LSI	5.3⊑	600 A <sup>3</sup>	LDL46600U53X	LGL46600U53X	LJL46600U53X	LLL46600U53X	LRL46600U53X
Ammeter	LSIG	6.3A	400 A <sup>3</sup>	LDL46400U44X	LGL46400U44X	LJL46400U44X	LLL46400U44X	LRL46400U44X
Anmeter	LSIG		600 A <sup>3</sup>	LDL46600U44X	LGL46600U44X	LJL46600U44X	LLL46600U44X	LRL46600U44X
Energy	LSIG	6.3E	400 A <sup>3</sup>	LDL46400U54X	LGL46400U54X	LJL46400U54X	LLL46400U54X	LRL46400U54X
Lifelgy	LSIG	0.3L	600 A <sup>3</sup>	LDL46600U54X	LGL46600U54X	LJL46600U54X	LLL46600U54X	LRL46600U54X
100% Rated	l, 600 Vac, 5	0/60 Hz						
Standard	LI	3.3	250 A <sup>2</sup>	LDL46250CU31X	LGL46250CU31X	LJL46250CU31X	LLL46250CU31X	LRL46250CU31X
Statiuatu	Li	5.5	400 A <sup>3</sup>	LDL46400CU31X	LGL46400CU31X	LJL46400CU31X	LLL46400CU31X	LRL46400CU31X
Ctandard	LSI	3.3S	250 A <sup>2</sup>	LDL46250CU33X	LGL46250CU33X	LJL46250CU33X	LLL46250CU33X	LRL46250CU33X
Standard	LOI	ა.აა	400 A <sup>3</sup>	LDL46400CU33X	LGL46400CU33X	LJL46400CU33X	LLL46400CU33X	LRL46400CU33X
Ammeter	LSI	5.3A	400 A <sup>3</sup>	LDL46400CU43X	LGL46400CU43X	LJL46400CU43X	LLL46400CU43X	LRL46400CU43X
Energy	LSI	5.3E	400 A <sup>3</sup>	LDL46400CU53X	LGL46400CU53X	LJL46400CU53X	LLL46400CU53X	LRL46400CU53X
Ammeter	LSIG	6.3A	400 A <sup>3</sup>	LDL46400CU44X	LGL46400CU44X	LJL46400CU44X	LLL46400CU44X	LRL46400CU44X
Energy	LSIG	6.3E	400 A <sup>3</sup>	LDL46400CU54X	LGL46400CU54X	LJL46400CU54X	LLL46400CU54X	LRL46400CU54X

<sup>&</sup>lt;sup>1</sup> UL Listed/CSA Certified as current limiting circuit breakers.

Table 31: L-Frame 600 A Mission Critical Standard (80%) Rated Electronic Trip UL Rated 4P Circuit Breakers (480Y/277 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Elec	Electronic Trip Unit		Sensor	Interrupting Rating (2nd Letter of Catalog Number)					
Туре	Function	Trip Unit	Rating	D	G	J	L		
			250 A <sup>1</sup>	LDL44250WU31X	LGL44250WU31X	LJL44250WU31X	LLL44250WU31X		
Standard	LI	3.3-W	400 A <sup>2</sup>	LDL44400WU31X	LGL44400WU31X	LJL44400WU31X	LLL44400WU31X		
			600 A <sup>2</sup>	LDL44600WU31X	LGL44600WU31X	LJL44600WU31X	LLL44600WU31X		
			250 A <sup>1</sup>	LDL44250WU33X	LGL44250WU33X	LJL44250WU33X	LLL44250WU33X		
Standard	LSI	3.3S-W	400 A <sup>2</sup>	LDL44400WU33X	LGL44400WU33X	LJL44400WU33X	LLL44400WU33X		
			600 A <sup>2</sup>	LDL44600WU33X	LGL44600WU33X	LJL44600WU33X	LLL44600WU33X		
A t	1.01	5.3A-W	400 A <sup>2</sup>	LDL44400WU43X	LGL44400WU43X	LJL44400WU43X	LLL44400WU43X		
Ammeter	LSI		600 A <sup>2</sup>	LDL44600WU43X	LGL44600WU43X	LJL44600WU43X	LLL44600WU43X		
F	1.01	5 OF W	400 A <sup>2</sup>	LDL44400WU53X	LGL44400WU53X	LJL44400WU53X	LLL44400WU53X		
Energy	LSI	5.3E-W	600 A <sup>2</sup>	LDL44600WU53X	LGL44600WU53X	LJL44600WU53X	LLL44600WU53X		
A t	1.010	0.04.14/	400 A <sup>2</sup>	LDL44400WU44X	LGL44400WU44X	LJL44400WU44X	LLL44400WU44X		
Ammeter	LSIG	6.3A-W	600 A <sup>2</sup>	LDL44600WU44X	LGL44600WU44X	LJL44600WU44X	LLL44600WU44X		
F	1.010	0 0E W	400 A <sup>2</sup>	LDL44400WU54X	LGL44400WU54X	LJL44400WU54X	LLL44400WU54X		
Energy LSIG	LSIG	6.3E-W	600 A <sup>2</sup>	LDL44600WU54X	LGL44600WU54X	LJL44600WU54X	LLL44600WU54X		

<sup>1</sup> Standard Lug Kit: AL400L61K4 Terminal Wire Range: (1) 2 AWG-600 kcmil Cu or (1) 2 AWG-500 kcmil Al. Type of Terminal Shield: Short.

<sup>&</sup>lt;sup>2</sup> Standard Lug Kit: AL400L61K4 Terminal Wire Range: (1) 2 AWG-600 kcmil Cu or (1) 2 AWG-500 kcmil Al. Type of Terminal Shield: Short.

<sup>3</sup> Standard Lug Kit: AL600LS52K4 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.

<sup>&</sup>lt;sup>2</sup> Standard Lug Kit: AL600LS52K4 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.

## **I-Line Circuit Breaker Catalog Numbers**

Table 32: L-Frame 600 A I-Line Standard (80%) Rated Electronic Trip UL Rated Circuit Breakers (600 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Elec	Electronic Trip Unit		Sensor	Interrupting Rating							
Туре	Function	Trip Unit	Rating	D	G	J 1	L <sup>3</sup>	R <sup>3</sup>			
			250 A <sup>3</sup>	LDA36250U31X	LGA36250U31X	LJA36250U31X	LLA36250U31X	LRA36250U31X			
Standard	LI	3.32	400 A <sup>4</sup>	LDA36400U31X	LGA36400U31X	LJA36400U31X	LLA36400U31X	LRA36400U31X			
			600 A <sup>4</sup>	LDA36600U31X	LGA36600U31X	LJA36600U31X	LLA36600U31X	LRA36600U31X			
		3.3S <sup>2</sup>	250 A <sup>3</sup>	LDA36250U33X	LGA36250U33X	LJA36250U33X	LLA36250U33X	LRA36250U33X			
Standard	LSI		400 A <sup>4</sup>	LDA36400U33X	LGA36400U33X	LJA36400U33X	LLA36400U33X	LRA36400U33X			
			600 A <sup>4</sup>	LDA36600U33X	LGA36600U33X	LJA36600U33X	LLA36600U33X	LRA36600U33X			
A t	1.01	5.3A	400 A <sup>44</sup>	LDA36400U43X	LGA36400U43X	LJA36400U43X	LLA36400U43X	LRA36400U43X			
Ammeter	LSI		600 A <sup>4</sup>	LDA36600U43X	LGA36600U43X	LJA36600U43X	LLA36600U43X	LRA36600U43X			
	1.01	5.05	400 A <sup>4</sup>	LDA36400U53X	LGA36400U53X	LJA36400U53X	LLA36400U53X	LRA36400U53X			
Energy	LSI	5.3E	600 A <sup>4</sup>	LDA36600U53X	LGA36600U53X	LJA36600U53X	LLA36600U53X	LRA36600U53X			
A t	1.010	6.3A	2.24		0.04	400 A <sup>4</sup>	LDA36400U44X	LGA36400U44X	LJA36400U44X	LLA36400U44X	LRA36400U44X
Ammeter	LSIG		600 A <sup>4</sup>	LDA36600U44X	LGA36600U44X	LJA36600U44X	LLA36600U44X	LRA36600U44X			
	1 010	6.05	400 A <sup>4</sup>	LDA36400U54X	LGA36400U54X	LJA36400U54X	LLA36400U54X	LRA36400U54X			
Energy	LSIG	6.3E	600 A <sup>4</sup>	LDA36600U54X	LGA36600U54X	LJA36600U54X	LLA36600U54X	LRA36600U54X			

<sup>1</sup> UL Listed/CSA Certified as current limiting circuit breakers.

Table 33: L-Frame 600 A Mission Critical I-Line Standard (80%) Rated Electronic Trip UL Rated Circuit Breakers (480/277 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Ele	ctronic Trip	Unit	Sensor	Interrupting Rating	Interrupting Rating					
Туре	Function	Trip Unit	Rating	D	G	J	L			
			250 A <sup>1</sup>	LDA34250WU31X	LGA34250WU31X	LJA34250WU31X	LLA34250WU31X			
Standard	LI	3.3-W	400 A <sup>2</sup>	LDA34400WU31X	LGA34400WU31X	LJA34400WU31X	LLA34400WU31X			
			600 A <sup>2</sup>	LDA34600WU31X	LGA34600WU31X	LJA34600WU31X	LLA34600WU31X			
			250 A <sup>1</sup>	LDA34250WU33X	LGA34250WU33X	LJA34250WU33X	LLA34250WU33X			
Standard	Standard LSI	3.3S-W	400 A <sup>2</sup>	LDA34400WU33X	LGA34400WU33X	LJA34400WU33X	LLA34400WU33X			
			600 A <sup>2</sup>	LDA34600WU33X	LGA34600WU33X	LJA34600WU33X	LLA34600WU33X			
A t	1.01	5.3A-W	5 0 A M	400 A <sup>2</sup>	LDA34400WU43X	LGA34400WU43X	LJA34400WU43X	LLA34400WU43X		
Ammeter	LSI		600 A <sup>2</sup>	LDA34600WU43X	LGA34600WU43X	LJA34600WU43X	LLA34600WU43X			
	1.01	5.05.144	400 A <sup>2</sup>	LDA34400WU53X	LGA34400WU53X	LJA34400WU53X	LLA34400WU53X			
Energy	LSI	5.3E-W	600 A <sup>2</sup>	LDA34600WU53X	LGA34600WU53X	LJA34600WU53X	LLA34600WU53X			
Ammotor	1 010	C 2A W	400 A <sup>2</sup>	LDA34400WU44X	LGA34400WU44X	LJA34400WU44X	LLA34400WU44X			
Ammeter	LSIG	6.3A-W	600 A <sup>2</sup>	LDA34600WU44X	LGA34600WU44X	LJA34600WU44X	LLA34600WU44X			
	LSIG	C OF W	400 A <sup>2</sup>	LDA34400WU54X	LGA34400WU54X	LJA34400WU54X	LLA34400WU54X			
Energy	LoiG	6.3E-W	600 A <sup>2</sup>	LDA34600WU54X	LGA34600WU54X	LJA34600WU54X	LLA34600WU54X			

Standard Lug Kit: AL400L61K3 Terminal Wire Range: (1) 2 AWG–600 kcmil Cu or (1) 2 AWG–500 kcmil Al. Type of Terminal Shield: Short.

<sup>&</sup>lt;sup>2</sup> 3P circuit breakers with this trip unit can be used for 2P applications.

<sup>3</sup> Standard Lug Kit: AL400L61K3 Terminal Wire Range: (1) 2 AWG-600 kcmil Cu or (1) 2 AWG-500 kcmil Al. Type of Terminal Shield: Short.

<sup>4</sup> Standard Lug Kit: AL600LS52K3 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.

Standard Lug Kit: AL600LS52K3 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 34: L-Frame 250 A and 400 A I-Line 100% Rated Electronic Trip UL Rated Circuit Breakers (600 Vac, 50/60 Hz) With Factory Sealed Trip Unit Suitable for Reverse Connection

Electronic Trip Unit		Sensor	Interrupting Rating						
Туре	Function	Trip Unit	Rating	D	G	J 1	L3	R <sup>3</sup>	
Ctondord	- 11	3.32	250 A <sup>3</sup>	LDA36250CU31X	LGA36250CU31X	LJA36250CU31X	LLA36250CU31X	LRA36250CU31X	
Standard	Standard LI	3.32	400 A <sup>4</sup>	LDA36400CU31X	LGA36400CU31X	LJA36400CU31X	LLA36400CU31X	LRA36400CU31X	
Standard	LSI	3.3S <sup>2</sup>	250 A <sup>3</sup>	LDA36250CU33X	LGA36250CU33X	LJA36250CU33X	LLA36250CU33X	LRA36250CU33X	
Stanuaru	LOI	3.33-	400 A <sup>4</sup>	LDA36400CU33X	LGA36400CU33X	LJA36400CU33X	LLA36400CU33X	LRA36400CU33X	
Ammeter	LSI	5.3A	400 A <sup>4</sup>	LDA36400CU43X	LGA36400CU43X	LJA36400CU43X	LLA36400CU43X	LRA36400CU43X	
Energy	LSI	5.3E	400 A <sup>4</sup>	LDA36400CU53X	LGA36400CU53X	LJA36400CU53X	LLA36400CU53X	LRA36400CU53X	
Ammeter	LSIG	6.3A	400 A <sup>4</sup>	LDA36400CU44X	LGA36400CU44X	LJA36400CU44X	LLA36400CU44X	LRA36400CU44X	
Energy	LSIG	6.3E	400 A <sup>4</sup>	LDA36400CU54X	LGA36400CU54X	LJA36400CU54X	LLA36400CU54X	LRA36400CU54X	

<sup>&</sup>lt;sup>1</sup> UL Listed/CSA Certified as current limiting circuit breakers.

## Circuit Breakers with Field-Interchangeable Trip Units Catalog Numbers

Table 35: L-Frame 3 Pole, 600 A Circuit Breakers with Lugs and Field-Interchangeable Electronic Trip Units (600 Vac, 50/60 Hz)<sup>1</sup>, <sup>2</sup>

Ele	ectronic Trip U	Jnit	Sensor	Interrupting Rating			
Туре	Function	Trip Unit	Rating	D	G	J 3	L <sup>3</sup>
Standard (80°	% Rated), 600 Va	ac, 50/60 Hz					
			250 A <sup>4</sup>	LDL36250TU31X	LGL36250TU31X	LJL36250TU31X	LLL36250TU31X
Standard	LI	3.3	400 A <sup>5</sup>	LDL36400TU31X	LGL36400TU31X	LJL36400TU31X	LLL36400TU31X
			600 A <sup>5</sup>	LDL36600TU31X	LGL36600TU31X	LJL36600TU31X	LLL36600TU31X
			250 A <sup>4</sup>	LDL36250TU33X	LGL36250TU33X	LJL36250TU33X	LLL36250TU33X
Standard	LSI	3.3S	400 A <sup>5</sup>	LDL36400TU33X	LGL36400TU33X	LJL36400TU33X	LLL36400TU33X
			600 A <sup>5</sup>	LDL36600TU33X	LGL36600TU33X	LJL36600TU33X	LLL36600TU33X
			400 A <sup>5</sup>	LDL36400TU43X	LGL36400TU43X	LJL36400TU43X	LLL36400TU43X
Ammeter	LSI	5.3A	600 A <sup>5</sup>	LDL36600TU43X	LGL36600TU43X	LJL36600TU43X	LLL36600TU43X
	1.01	5.05	400 A <sup>5</sup>	LDL36400TU53X	LGL36400TU53X	LJL36400TU53X	LLL36400TU53X
Energy	LSI	5.3E	600 A <sup>5</sup>	LDL36600TU53X	LGL36600TU53X	LJL36600TU53X	LLL36600TU53X
	1.010	6.3A	400 A <sup>5</sup>	LDL36400TU44X	LGL36400TU44X	LJL36400TU44X	LLL36400TU44X
Ammeter	LSIG		600 A <sup>5</sup>	LDL36600TU44X	LGL36600TU44X	LJL36600TU44X	LLL36600TU44X
	1.010	6.3E	400 A <sup>5</sup>	LDL36400TU54X	LGL36400TU54X	LJL36400TU54X	LLL36400TU54X
Energy	LSIG		600 A <sup>5</sup>	LDL36600TU54X	LGL36600TU54X	LJL36600TU54X	LLL36600TU54X
100% Rated, (	600 Vac, 50/60 H	lz				•	•
Ote ded	LI	3.3	250 A <sup>4</sup>	LDL36250RU31X	LGL36250RU31X	LJL36250RU31X	LLL36250RU31X
Standard	LI	3.3	400 A <sup>5</sup>	LDL36400RU31X	LGL36400RU31X	LJL36400RU31X	LLL36400RU31X
Ctondord	1.01	2.20	250 A <sup>4</sup>	LDL36250RU33X	LGL36250RU33X	LJL36250RU33X	LLL36250RU33X
Standard	LSI	3.3S	400 A <sup>5</sup>	LDL36400RU33X	LGL36400RU33X	LJL36400RU33X	LLL36400RU33X
Ammeter	LSI	5.3A	400 A <sup>5</sup>	LDL36400RU43X	LGL36400RU43X	LJL36400RU43X	LLL36400RU43X
Energy	LSI	5.3E	400 A <sup>5</sup>	LDL36400RU53X	LGL36400RU53X	LJL36400RU53X	LLL36400RU53X
Ammeter	LSIG	6.3A	400 A <sup>5</sup>	LDL36400RU44X	LGL36400RU44X	LJL36400RU44X	LLL36400RU44X
Energy	LSIG	6.3E	400 A <sup>5</sup>	LDL36400RU54X	LGL36400RU54X	LJL36400RU54X	LLL36400RU54X

<sup>1</sup> Circuit breakers will be labeled with Line and Load markings and are not suitable for reverse connections.

<sup>5</sup> Standard Lug Kit: AL600LS52K3 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.



<sup>&</sup>lt;sup>2</sup> 3P circuit breakers with this trip unit can be used for 2P applications.

<sup>3</sup> Standard Lug Kit: AL400L61K3 Terminal Wire Range: (1) 2 AWG-600 kcmil Cu or (1) 2 AWG-500 kcmil Al. Type of Terminal Shield: Short.

<sup>&</sup>lt;sup>4</sup> Standard Lug Kit: AL600LS52K3 Terminal Wire Range: (2) 2/0 AWG-500 kcmil Al/Cu. Type of Terminal Shield: Medium.

<sup>&</sup>lt;sup>2</sup> Only available on 3P unit-mount circuit breakers. Not available in R interrupting rating. Not available with I-Line or Plug-in constructions.

<sup>&</sup>lt;sup>3</sup> UL Listed/CSA Certified as current limiting circuit breakers.

<sup>4</sup> Standard Lug Kit: AL400L61K3 Terminal Wire Range: (1) 2 AWG-600 kcmil Cu or (1) 2 AWG-500 kcmil Al. Type of Terminal Shield: Short.

## PowerPact™ H-, J-, and L-Frame Circuit Breakers Circuit Breakers

Table 36: L-Frame 600 A, 3 Pole, Basic Circuit Breaker Frame Without Terminations or Trip Units (600 Vac, 50/60 Hz)<sup>1</sup>

Ampere	Interrupting Rati	Interrupting Rating								
Rating	D	G	J 2	L <sup>2</sup>						
250 A (70–250 A)	LDF36000F25	LGF36000F25	LJF36000F25	LLF36000F25						
400 A (125–400 A)	LDF36000F40	LGF36000F40	LJF36000F40	LLF36000F40						
600 A (200–600 A)	LDF36000F60	LGF36000F60	LJF36000F60	LLF36000F60						

<sup>&</sup>lt;sup>1</sup> Not suitable for reverse connection.

Table 37: L-Frame 3P Field-Installable Micrologic Electronic Trip Units

Ele	ectronic Trip U	nit	Ammana Catting	Trip Unit
Туре	Function	Trip Unit	Ampere Setting	Cat. No.
			70-80-100-125-150-175-200-225-250	LE3250U31X
	LI	3.3	125-150-175-200-225-250-300-350-400	LE3400U31X
Standard			200-225-250-300-350-400-450-500-600	LE3600U31X
Sianuaru			70-80-100-125-150-175-200-225-250	LE3250U33X
	LSI	3.3S	125-150-175-200-225-250-300-350-400	LE3400U33X
			200-225-250-300-350-400-450-500-600	LE3600U33X
	LSI	5.3A	125–400	LE3400U43X
Ammeter	LSI	5.3A	200–600	LE3600U43X
Ammeter	LSIG	6.3A	125–400	LE3400U44X
	LSIG	6.3A	200–600	LE3600U44X
	LSI	5.3E	125–400	LE3400U53X
Гоогон	LSI	5.3E	200–600	LE3600U53X
Energy	1.010	6.05	125–400	LE3400U54X
	LSIG	6.3E	200–600	LE3600U54X

<sup>&</sup>lt;sup>2</sup> UL Listed/CSA Certified as current limiting

## Section 4—Automatic Switches

## **Automatic Switch Functions**

An automatic switch can be used to open and close a circuit under normal operating conditions. They are similar in construction to circuit breakers, except that the switches open instantaneously at a factory-set, non-adjustable trip point calibrated to protect only the molded case switch.

Molded case switches are intended for use as disconnect devices only. UL489 requires molded case switches to be protected by a circuit breaker or fuse of equivalent rating. Molded case switches are labeled with their appropriate withstand ratings. The withstand rating of a switch is defined as the maximum current at rated voltage that the molded case switch will withstand without damage when protected by a circuit breaker with an equal continuous current rating.

PowerPact™ H-, J-, and L-frame automatic switches are available in unit mount, I-Line™, plug-in and drawout versions. They use the same accessories and offer the same connection possibilities as the circuit-breaker versions. They may be interlocked with another switch or circuit breaker to form a source-changeover system.

Switches are Listed under UL file E103740 and Certified under CSA file LR88980.

## **Motor Operator**

PowerPact H-, J-, and L-frame switches equipped with a motor operator module allow remote closing and opening.

## Ground Fault Protection (H- and J-Frame Circuit Breakers Only)

An ELM or GFM module may be added to an automatic switch to monitor all leakage currents in the outgoing circuits of the equipment on which the automatic switch is installed. When the ELM or GFM module detects an earth-leakage current, the automatic switch interrupts the load current.

#### **Automatic Switch Protection**

The automatic switch can make and break its rated current. For an overload or a short-circuit, it must be protected by an upstream device, in compliance with installation standards. Due to their high-set instantaneous release PowerPact H-, J- and L-frame automatic switches are self-protected.

## **Specifications**

Table 38: H-Frame Automatic Molded Case Switch Specifications

	Frame			H-F	rame	
	Withstand Rating		"G	"	"L"	
	Poles		2P	3P	2P <sup>1</sup>	3P
	Catalog Number	150 A	HGL26000S15	HGL3600S15	HLL26000S15	HLL36000S15
		175 A	_	_	_	_
		250 A	_	_	_	_
UL 489		240 Vac	65 kA	65 kA	125 kA	125 kA
	Withstand Ratings	480 Vac	35 kA	35 kA	100 kA	100 kA
	Willistatiu hatiings	600 Vac	18 kA	18 kA	50 kA	50 kA
		250 Vdc	20 kA	20 kA	20 kA	20 kA
	AC Trip Point		2250 A	2250 A	2250 A	2250 A
	Rated Insulation Voltage		750 Vac	750 Vac	750 Vac	750 Vac
IEC 60947-3	Rated Impulse Withstand Voltage		8 kV	8 kV	8 kV	8 kV
IEC 00947-3	Rated Operational Voltage	ac	525 Vac	525 Vac	525 Vac	690 Vac
	nated Operational Voltage	dc	_	_	_	_

<sup>1 2</sup>P devices use a 3P switch frame with the center pole inoperative.

Table 39: J-Frame Automatic Molded Case Switch Specifications

	Frame		J-Frame				
	Withstand Rating		"(	"G"		"L"	
	Poles		2P1	3P	2P1	3P	3P
	Catalog Number	150 A	_	_	_	_	
		175 A	JGL26000S17	JGL36000S17	JLL26000S17	JLL36000S17	JRL36000S17
		250 A	JGL26000S25	JGL36000S25	JLL26000S25	JLL36000S25	JRL36000S25
UL 489		240 Vac	65 kA	65 kA	125 kA	125 kA	200 kA
	Withstand Ratings	480 Vac	35 kA	35 kA	100 kA	100 kA	200 kA
	Willistatiu hattiigs	600 Vac	18 kA	18 kA	50 kA	50 kA	100 kA
		250 Vdc	20 kA				
	AC Trip Point	•	3125 A				
	Rated Insulation Voltage		750 Vac				
IEC 60947-3	Rated Impulse Withstand Voltage		8 kV				
IEC 00947-3	Dated Operational V-11	ac	525 Vac	525 Vac	525 Vac	525 Vac	690 Vac
	Rated Operational Voltage dc		500 Vdc				

<sup>&</sup>lt;sup>1</sup> 2P devices use a 3P switch frame with the center pole inoperative.

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Automatic Switches

## **Catalog Numbers**

Table 40: PowerPact H-Frame and J-Frame 250 A Unit-Mount Automatic Molded Case Switches, 600 Vac with Factory Sealed Trip Unit (Suitable for Reverse Connection)

Ampere	2-pole	3-pole	Withstan	d Rating <sup>1</sup>		Trip	Standard Lug Kit
Rating	Cat. No.	Cat. No.	240 Vac	480 Vac	600 Vac	Point	Terminal Wire Range
G Withsta	nd	•	•	•	•	•	•
150 A	HGL26000S15 <sup>2</sup>	HGL36000S15	65	35	18	2250 A	AL150HD #14–#3/0 AWG Al or Cu
175 A	JGL26000S17	JGL36000S17	C.F.	35	10	3125 A	AL250JD
250 A	JGL26000S25	JGL36000S25	<del></del> 65	33	18	3125 A	#3/0-350 kcmil Al or Cu
L Withsta	nd						
150 A	HLL26000S15	HLL36000S15	125	100	50	2250 A	AL150HD #14–#3/0 AWG Al or Cu
175 A	JLL26000S17	JLL36000S17	105	100	50	3125 A	AL250JD
250 A	JLL26000S25	JLL36000S25	125	100	50	3125 A	#3/0-350 kcmil Al or Cu
R Withsta	nd						
175 A	_	JRL36000S17	200	200	100	3125 A	AL250JD
250 A	_	JRL36000S25	200	200	100	0123 A	#3/0-350 kcmil Al or Cu

<sup>1</sup> The withstand rating is the fault current, at rated voltage, that the molded case switch will withstand without damage when protected by a circuit breaker or fuse with an equal continuous current rating.

Table 41: PowerPact H-Frame and J-Frame I-Line Automatic Molded Case Switches, 600 Vac with Factory Sealed Trip Unit (Suitable for Reverse Connection)

Ampere	2-pole	3-pole	Withstan	d Rating <sup>1</sup>		Trip	Standard Lug Kit
Rating	Cat. No.	Cat. No.	240 Vac	480 Vac	600 Vac	Point	Terminal Wire Range
G Withsta	nd						<u>.</u>
150 A	HGA26000S15() <sup>2</sup>	HGA36000S15	65	35	18	1300 A	AL150HD
150 A	11GA20000315( )-	11GA30000313	03	33	10	1300 A	#14-#3/0 AWG AI or Cu
175 A	JGA26000S17()	JGA36000S17	65	35	18	2500 A	AL250JD
250 A	JGA26000S25()	JGA36000S25	00	35 16		2500 A	#3/0-350 kcmil Al or Cu
L Withsta	nd						
150 A	HLA26000S15()	HLA36000S15	125	100	50	1300 A	AL150HD
150 A	TILA20000313()	11LA30000313	125	100	30	1300 A	#14-#3/0 AWG AI or Cu
175 A	JLA26000S17()	JLA36000S17	125	100	50	1300 A	AL250JD
250 A	JLA26000S25()	JLA36000S25	125	100	50	2500 A	#3/0-350 kcmil Al or Cu
R Withsta	nd						
175 A	JRA26000S17()	JRA36000S17	200	200	100	3125A	AL250JD
250 A	JRA26000S25()	JRA36000S25	200	200	100	3123A	#3/0-350 kcmil Al or Cu

<sup>1</sup> The withstand rating is the fault current, at rated voltage, that the molded case switch will withstand without damage when protected by a circuit breaker or fuse with an equal continuous current rating.

<sup>2 2-</sup>pole device with 3 in. (76 mm) mounting height, all other 2-pole circuit breakers use 3-pole switch 4.5 in. (114 mm) mounting height.

<sup>&</sup>lt;sup>2</sup> 2-pole device with 3 in. (76 mm) mounting height, all other 2-pole circuit breakers use 3-pole 4.5 in. (114 mm) mounting height.

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Automatic Switches

Table 42: PowerPact L-Frame 600 A Unit-Mount Automatic Molded Case Switches, 600 Vac

Ampere	Poles <sup>1</sup>	Cat. No.	Withstan	d Rating <sup>2</sup>		Trip	Standard Lug Terminal
Rating	Poles		240 Vac	480 Vac	600 Vac	Point	Wire Range
Unit-Mou	nt Autom	atic Molded Case S	Switches,	•	-	•	•
G Withstan	d						
400 A	3P	LGL36000S40X	65 kA	35 kA	18 kA	4800 A	AL600LS52K3
600 A	3P	LGL36000S60X	65 kA	35 kA	18 kA	6600 A	(2) 2 AWG-500 kcmil Al/Cu
400 A	4P	LGL46000S40X	65 kA	35 kA	18 kA	4800 A	AL600LS52K4
600 A	4P	LGL46000S60X	65 kA	35 kA	18 kA	6600 A	(2) 2 AWG-500 kcmil Al/Cu
L Withstand	b		•	•	•		
400 A	3P	LLL36000S40X	125 kA	100 kA	50 kA	4800 A	AL600LS52K3
600 A	3P	LLL36000S60X	125 kA	100 kA	50 kA	6600 A	(2) 2 AWG-500 kcmil Al/Cu
400 A	4P	LLL46000S40X	125 kA	100 kA	50 kA	4800 A	AL600LS52K4
600 A	4P	LLL46000S60X	125 kA	100 kA	50 kA	6600 A	(2) 2 AWG-500 kcmil Al/Cu
R Withstan	d		•	•	•		
400 A	3P	LRL36000S40X	200 kA	200 kA	100 kA	4800 A	AL600LS52K3
600 A	3P	LRL36000S60X	200 kA	200 kA	100 kA	6600 A	(2) 2 AWG-500 kcmil Al/Cu
400 A	4P	LRL46000S40X	200 kA	200 kA	100 kA	4800 A	AL600LS52K4
600 A	4P	LRL46000S60X	200 kA	200 kA	100 kA	6600 A	(2) 2 AWG-500 kcmil Al/Cu
I-Line Cir	cuit Brea	kers Automatic Mo	Ided Case	Switches			
G Withstan	d						
400 A	3P	LGA36000S40X	65 kA	35 kA	18 kA	4800 A	AL600LF52K3
600 A	3P	LGA36000S60X	65 kA	35 kA	18 kA	6600 A	(2) 3/0 AWG-500 kcmil Al/Cu
L Withstand	L	•		•	•	•	•
400 A	ap.	LLA36000S40X	125 kA	100 kA	50 kA	4800 A	AL600LF52K3
600 A	- 3P	LLA36000S60X	125 kA	100 kA	50 kA	6600 A	(2) 3/0 AWG-500 kcmil Al/Cu
R Withstan	d	•		•	•	•	•
400 A	op.	LRA36000S40X	200 kA	200 kA	100 kA	4800 A	AL600LF52K3
600 A	3P	LRA36000S60X	200 kA	200 kA	100 kA	6600 A	(2) 3/0 AWG-500 kcmil Al/Cu

<sup>&</sup>lt;sup>1</sup> 4P circuit breaker available as bus connected, with lug configurations, and in plug-in, draw-out and rear-connected configurations.

Table 43: L-Frame Ratings and Withstand Ratings

Circuit Breaker			400 A	600 A					
Number of Poles			3, 4	3, 4					
Ampere Rating (A)	400	600							
UL 489 Ratings									
Rated Voltage (V)		600	600						
IEC 60947-3 ratings									
Rated Insulation Voltage (V)			750	750					
Rated Impulse Withstand Voltage (kV)			8	8					
Rated Operational Voltage	Ue	AC 50/60 Hz	690	690					
Rated Operational Current	le	AC 525 V	400	600					
Making Capacity (kA peak)			7.1	8.5					
Short Time Withstand Current (kA rms)	low	Icw (kA ms)	5	6					
Short-Time Withstand Current (kA rms)	lcw	Duration (s)	1	1					

The withstand rating is the fault current, at rated voltage, that the molded case switch will withstand without damage when protected by a circuit breaker or fuse with an equal continuous current rating.

### Section 5—Motor Circuit Protection

## **General Information**

The parameters to be considered for motor-feeder protection depend on:

- the application (type of machine driven, operating safety, frequency of operation, etc.)
- · the level of continuity of service required by the load or the application
- the applicable standards for the protection of equipment.

The required electrical functions are:

- isolation
- switching, generally at high endurance levels
- protection against overloads and short-circuits, adapted to the motor
- additional special protection.

A motor branch circuit must comply with the requirements of standard UL508 concerning contactors and their protection:

- · coordination of feeder components
- overload relay trip classes.

#### **Motor Branch Circuit Protection Function**

A motor branch circuit comprises a set of devices for motor protection and control, as well as for protection of the branch circuit itself.

## Switching

The purpose is to control the motor (ON / OFF), either manually, automatically or remotely, taking into account overloads upon start-up and the long service life required. This function is provided by a contactor. When the coil of the contactor's electromagnet is energized, the contactor closes and establishes, through the poles, the circuit between the upstream supply and the motor, through the circuit breaker.

#### **Basic Protection**

- Short-circuit protection
  - Detection and breaking, as quickly as possible, of high short-circuit currents to avoid damage to the installation. This function is provided by a circuit breaker.
- Overload protection
  - Detection of overload currents and motor shutdown before temperature rise in the motor and conductors damages insulation. This function is provided by a circuit breaker or a separate motor overload relay.
- Phase unbalance or phase loss protection
  - Phase unbalance or phase loss can cause temperature rise and braking torques that can lead to premature ageing of the motor. These effects are even greater during starting, therefore protection must be virtually immediate.



#### **Additional Electronic Protection**

- Locked rotor
- Under-load
- · Long starts and stalled rotor
- Insulation faults

## **Trip Class of a Overload Relay Device**

The motor branch circuit includes thermal protection that may be built into the circuit breaker. The protection must have a trip class suited to motor starting. Depending on the application, the motor starting time varies from a few seconds (no-load start) to a few dozen seconds (high-inertia load).

Table 44: Trip Class of Overload Relays as a Function of Their FLA Setting

Class	1.05 FLA <sup>1</sup>	1.2 FLA <sup>1</sup>	1.5 FLA <sup>2</sup>	6.0 FLA <sup>1</sup>	
5	t > 2 h	t < 2h	t < 2 mn	2 s < t ≤ 5 s	
10	t > 2 h	t < 2h	t < 4 mn	4 s < t ≤ 10 s	
20	t > 2 h	t < 2h	t < 8 mn	6 s < t ≤ 20 s	

<sup>1</sup> Time for a cold start (motor off and cold).

Example: In class 20, the motor must have finished starting within 20 seconds (6 to 20 s) for a starting current of 6 x FLA.

## **Asynchronous-Motor Starting Parameters**

The main parameters of direct on-line starting of three-phase asynchronous motors (90% of all applications) are listed below.


- FLA: Full load amperes
   This is the current drawn by the motor at full rated load.
- Id: locked rotor current
   This is the current drawn by the motor during starting, on average 6.0 x In for a duration of 5 to 30 seconds depending on the application. These values determine the trip class and any additional "long-start" protection devices that may be needed.
- Id: peak starting current This is the subtransient current during the first two half-waves when the system is energized, on the average 14 I<sub>n</sub> for 10 to 15 ms (e.g. 1840 A peak).

The protection settings must effectively protect the motor, notably through a suitable overload relay trip class, but let the peak starting current through.

## **Motor-Feeder Solutions**

PowerPact™ H-, J-, and L-frame circuit breakers motor circuit breakers are designed for motor-feeder solutions using:

- three devices, including an electronic MCP or 1.3 M instantaneous-only trip unit
- · two devices including a 2 M electronic trip unit.



<sup>&</sup>lt;sup>2</sup> Time for warm start (motor running under normal conditions).

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Motor Circuit Protection

#### PowerPact H-, J-, and L-Frame with Micrologic™ Trip Units Motor-Protection Range

PowerPact H-, J-, and L-frame circuit breakers with Micrologic trip units can be used to create motor-feeder solutions comprising two or three devices. The protection devices are designed for continuous duty at 104°F (40°C).

#### Three-device solutions

- 1 PowerPact circuit breaker with Micrologic 1.3 M trip unit
- 1 contactor
- overload relay

#### Two-device solutions

- 1 PowerPact circuit breaker with a Micrologic 2 M electronic trip unit.
- 1 contactor

**Table 45: Motor Protection Specifications** 

Type of Motor Protec	tion		3 Devices (Circuit Breaker + Contactor + Overload Relay)	2 Devices (Circuit Breaker + Contactor)		
PowerPact H-, J-, or L-fra	me circuit breaker		PowerPact L-frame 400/600 A	PowerPact H-, J-, and L-Frame 100–600 A		
	Type 2 coordinat	ion with	Contactor + overload relay	Contactor		
Trip Unit	Туре		Micrologic 1.3 M Electronic Trip Unit	Micrologic 2 M Electronic Trip Unit		
	Separate		X			
Overload Relay		5		X		
Overload helay	Built-in, Class	10		Х		
		20		Х		
Protection functions of Po	werPact H-, J-, and	L-frame	circuit breaker	•		
Short-circuits			X	Х		
Overloads				X		
Special motor functions Phase unbalance				X		

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Motor Circuit Protection

## **Electronic Motor Circuit Protectors (AC Only)**




PowerPact H- and J-frame Electronic Motor Circuit Protectors (MCP) are instantaneous-trip circuit breakers. They are designed to offer short circuit protection and are National Electrical Code® (NEC®) compliant when installed as part of a combination controller having motor overload protection. MCP circuit breakers accept the same accessories and terminals as the equivalent thermal-magnetic circuit breakers. (See Section 3 for Accessories.)

The unique design of the PowerPact MCPs includes two rotary switches to allow quick setting adjustments based on the characteristics of the motor.

The first rotary switch allows for Full Load Amperes (FLA) adjustment across the range of the frame size.

The second rotary switch selects the type of motor protection based on Automatic 1 for Standard Efficiency or Automatic 2 for High Energy Efficient. When using the automatic settings the MCP microprocessor automatically adjusts the trip settings for both current and time to align with the start-up characteristic for the motor type, whether it is a standard or energy-efficient motor. This includes a dampening means to accommodate a transient motor in-rush current without nuisance tripping of the circuit breaker. Rotary switch 2 also allows for traditional motor protection from 8 to 13 times the selected FLA.

The MCP rotary switches are detented and allow the device to be set to specific trip values within a typical accuracy range of +/-5%.



## **Full Load Amp Settings**

- 1. Determine the motor's full-load current by referring to the nameplate on the motor.
- Set the trip range by turning the FLA rotary switch to the setting closest to the motor's full load current.


#### **Automatic Protection Settings**

The MCP microprocessor automatically adjusts the trip settings for both current and time to align with the start-up characteristics for the motor type selected. This includes a dampening means to accommodate a transient motor in-rush current without nuisance tripping of the circuit breaker.



## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Motor Circuit Protection**


Figure 3: **Automatic Protection Settings** 



## **Manual Protection Settings**

The manual settings may be adjusted to multiples of current based on the rotary switch setting for motor Full Load Amps (FLA).

For example, if FLA rotary switch is set to 20 and I<sub>m</sub> rotary switch is set to 9x, then the instantaneous trip point will be 180 A.



See Tables 51 thru 53 for more information.

Table 46: H- and J-Frame Electronic Motor Circuit Protectors (MCP)

Frame	Current	Full Load Amperes	Adjustable Instantaneous	Suffix	J Interrupting L Interrupting (See SCCR Table Below)		R Interrupting	
		Range	Trip Range		Cat. No.	Cat. No.	Cat. No.	
	30 A	1.5–25 A	9–325 A	M71	HJL36030M71	HLL36030M71	HRL36030M71	
H-Frame	50 A	14–42 A	84–546 A	M72	HJL36050M72	HLL36050M72	HRL36050M72	
п-гіапіе	100 A	30–80 A	180–1040 A	M73	HJL36100M73	HLL36100M73	HRL36100M73	
	150 A	58–130 A	348–1690 A	M74	HJL36150M74	HLL36150M74	HRL36150M74	
J-Frame	250 A	114–217 A	684–2500 A	M75	JJL36250M75	JLL36250M75	JRL36250M75	

High Short Circuit Current Ratings (SCCR)

The PowerPact MCP helps achieve the high UL508A Short Circuit Current Rating (SCCR) needed to meet NEC Article 409 requirements for industrial control panels. They deliver up to 100 kA at 480 Vac SCCR when used in combination with approved Square D™ NEMA or Schneider Electric™ IEC motor starters.

Table 47: **Short Circuit Current Ratings (SCCR)** 

Contactor/Starter	J Interrupting			L Interrupting			R Interrupting		
	200-240 Vac	480 Vac	600 Vac	200-240 Vac	480 Vac	600 Vac	200-240 Vac	480 Vac	600 Vac
Tesys D-line and F-line	100 kA	65 kA	25 kA	100 kA	100 kA	50 kA	200 kA	200 kA	100 kA
NEMA Type S	100 kA	65 kA	25 kA	100 kA	100 kA	50 kA	200 kA	200 kA	100 kA

01/2014

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Motor Circuit Protection

Table 48: MCP Selection by HP Ratings of Induction-Type Squirrel-Cage and Wound-Rotor Motors


				otor Motors 3Ø 60 Hz		PowerPact H	
Starter Size	200 Vac	230 Vac	480 Vac	575 Vac	Amperes	J-Frame Elec	tronic MCP
				1/2	0.9 A		
			1/2	0/4	1.1 A		
			3/4	3/4 1	1.3 A 1.7 A		
			1	'	2.1 A		
		1/2			2.2 A		
				1-1/2	2.4 A		
	1/2			2	2.5 A 2.7 A		
			1-1/2		3 A		
00		3/4			3.2 A		
			2		3.4 A		
	3/4			0	3.7 A		
		1		3	3.9 A 4.2 A	HJL36030M71	
	1	'			4.8 A	and	
			3		4.8 A	HLL36030M71	
		1-1/2		_	6 A		
		2		5	6.1 A 6.8 A	1/2-10 hp	
	1-1/2				6.9 A		
			5		7.6 A		
	2				7.8 A		
0				7-1/2	9 A 9.6 A		
	3	3	7-1/2	10	9.6 A 11 A		
	Ü		10	10	14 A		
		5			15.2 A		
4	-			15	17 A		
1	5		15		17.5 A 21 A		1111 000501470
		7-1/2	15	20	22 A		HJL36050M72
	7-1/2	, =			25.3 A		and
			20	25	27 A		HLL36050M72
2		10		30	28 A 32 A		1
	10			30	32.2 A		10–25 hp
	10		25		34 A		
			30		40 A		
		46		40	41 A	HJL36100M73	
	15	15			42 A 48.3 A	and	
	13		40	50	52 A	HLL36100M73	
3		20			54 A		
	20			60	62 A	15–50 hp	
		25	50		65 A 68 A	·r	
		20	60	75	77 A		
	25				78.2 A		HJL36150M74
	0.5	30			80 A		and
	30		75		92 A 96 A		HLL36150M74
4			/5	100	96 A 99 A		
		40		. 55	104 A		30-100 hp
	40				120 A		
			100	105	124 A		
		50		125	125 A 130 A	JJL36250M75	
			1	150	144 A	and	
[	50				150 A	JLL36250M75	
5		60	105		154 A		
	60		125		156 A 177.1 A	50-150 hp	
	50		150		180 A		
		75		200	192 A		J
	75		000		221 A		
		100	200		240 A 248 A		
Chadad area		100	<u> </u>		240 A		

Shaded area is not covered by J-frame electronic motor circuit protector.



## Micrologic 1.3 M Electronic Trip Units for Instantaneous **Protection Only (L-Frame Circuit Breakers Only)**

Micrologic 1.3 M trip units are used in 3-device motor-feeder solutions on PowerPact L-frame circuit breakers with performance levels G/J/L. They provide short-circuit protection for motors up to 250 kW at 400 V.



Micrologic 1.3 M trip units provide instantaneous protection only, using electronic technology. They are dedicated to 600 A 3-pole (3P 3D) circuit breakers or 4-pole circuit breakers with detection on three poles (4P, 3D). They are especially used in 3-pole versions for motor protection.

Circuit breakers equipped with Micrologic 1.3 M trip units, without thermal protection, are used in certain applications to replace automatic switches. Micrologic 1.3 M trip units are available on PowerPact L-frame circuit breakers only.

NOTE: All Micrologic trip units have a transparent, sealable cover that protects access to the adjustment rotary switches.

They also provide the benefits of electronic technology:

- accurate settings
- tests
- "Ready" LED.

Circuit breakers with a Micrologic 1.3 M trip unit are combined with a overload relay and a contactor.

Protection settings are made using a rotary switch.

#### **Protection Version**

Three pole (3P): three pole frame circuit breakers equipped with detection on all three poles.

## **Indications**

The green "Ready" LED blinks slowly when the electronic trip unit is ready to provide protection. It indicates the trip unit is operating correctly.

NOTE: All the trip units have a transparent sealable cover that protects access to the adjustment rotary switches.

01/2014

Table 49: Micrologic 1.3 M Electronic Trip Unit


Rating: In at 104	°F (40°C) <sup>1</sup>	400 A	600 A				
Circuit Breaker	PowerPact L-frame	x x					
Short-time protection	n						
Pick-up (A)	I <sub>sd</sub>	Adjustable directly in amps					
accuracy ±15%	There is a very short delay to let through motor starting currents	9 settings: 2000-2400-2800- 3200-3600-4000-4800 A	9 settings: 3000-3600-4200- 4800-5400-6000-6600-7200 A				
	t <sub>sd</sub>	Non-adjustable					
Time delay (ms)	Non-tripping time Maximum break time	20 60					
Instantaneous prote	ection	•					
Pick-up (A)	l <sub>i</sub> non-adjustable	4800	7200				
accuracy ±15%	Non-tripping time Maximum break time	0 30 ms					

<sup>1</sup> Motor standards require operation at 104°F (40°C). Circuit-breaker ratings are derated to take this requirement into account

## Micrologic 2.2 M and 2.3 M Electronic Trip Units

Micrologic 2.2 M and 2.3 M trip units provide built-in thermal and instantaneous protection. They are used in 2-device motor-feeder solutions on PowerPact H-, J-, and L-frame circuit breakers with performance levels J/L. They provide protection for motors up to 315 kW at 400 V against:

- short-circuits
- overloads with selection of a trip class (5, 10 or 20)
- phase unbalance.



Circuit breakers with a Micrologic 2.2 M/ 2.3 M trip unit include protection similar to an inverse-time overload relay. They are combined with a contactor.

Protection settings are made using a rotary switch.

#### **Overloads (or Thermal Protection)**

Long-time protection and trip class (FLA)

- Inverse-time thermal protection
- against overloads with adjustable pick-up FLA.
- Settings are made in amperes. The tripping curve for the long-time protection, which indicates the time delay tr before tripping, is defined by the selected trip class.



## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Motor Circuit Protection

### **Trip Class**

- The class is selected as a function of the normal motor starting time.
  - Class 5: starting time less than 5 s
  - Class 10: starting time less than 10 s
  - Class 20: starting time less than 20 s
- For a given class, it is necessary to check that all motor-feeder components are sized to carry the 6 x FLA starting current without excessive temperature rise during the time corresponding to the class.

#### **Short-Circuits**

Short-time protection (I<sub>sd</sub>)

- Provides protection with an adjustable pick-up I<sub>sd</sub>.
- There is a very short delay to let through motor starting currents.

Non-adjustable instantaneous protection (I<sub>i</sub>)

Instantaneous protection with non-adjustable pick-up l<sub>i</sub>.

## Phase Unbalance or Phase Loss (I<sub>unbal</sub>)

- This function opens the circuit breaker if a phase unbalance occurs:
  - that is greater than the 30% fixed pick-up I<sub>unbal</sub>
  - following the non-adjustable time delay t<sub>unbal</sub> equal to:
    - 0.7 s during starting
    - 4 s during normal operation
- Phase loss is an extreme case of phase unbalance and leads to tripping under the same conditions

## **Indications**

#### Front indications

- The green "Ready" LED blinks slowly when the electronic trip unit is ready to provide protection. It
  indicates the trip unit is operating correctly.
- Red alarm LED for motor operation goes ON when the thermal image of the rotor and stator is greater than 95% of the permissible temperature rise.

Remote indications using SDTAM module

- PowerPact H-, J-, and L-frame devices with a Micrologic 2 M trip unit can be equipped with an SDTAM module dedicated to motor applications for:
  - a contact to indicate circuit-breaker overload
  - a contact to open the contactor. In the event of a phase unbalance or overload, this output is activated 400 ms before circuit-breaker tripping to open the contactor and avoid circuit breaker tripping
- This module takes the place of the shunt trip (MN)/undervoltage trip (MX) coils and an auxiliary switch (OF) contact

SDTAM remote indication relay module with its terminal block.

Note: All the trip units have a transparent sealable cover that protects access to the adjustment rotary switches.



Table 50: Micrologic 2.2 M and 2.3 M Electronic Trip Unit

Rating: I <sub>n</sub> at 104°	F (40°C) <sup>1</sup>		30 A	50 A	100 A	150 A	250 A	400 A	600 A			
	PowerPact H-fra	ame	Х	Х	Х	Х	_	_	_			
Circuit Breaker	PowerPact J-fra	ıme	_	_	_	_	Х	_	_	_		
	PowerPact L-fra	ıme	_	_	_	_	_	Х	Х			
Overloads (or Th	ermal Protection	on): Long-	Time Pro	tection a	nd Trip C	lass	•	•	•			
	FLA		Value depending on trip unit rating (In) and setting on rotary switch									
	I <sub>n</sub> = 30 A	FLA =	14	16	18	20	21	22	23	24	25	
	I <sub>n</sub> = 50 A	FLA =	14	17	21	24	27	29	32	36	42	
Pick-Up (A)	I <sub>n</sub> = 100 A	FLA =	30	35	41	45	51	56	63	71	80	
Tripping between 1.05 and 1.20 FLA	I <sub>n</sub> = 150 A	FLA =	58	71	78	86	91	97	110	119	130	
	I <sub>n</sub> = 250 A	FLA =	114	137	145	155	163	172	181	210	217	
	I <sub>n</sub> = 400 A	FLA =	190	210	230	250	270	290	310	330	348	
	I <sub>n</sub> = 600 A	FLA =	312	338	364	390	416	442	468	484	520	
Time Delay												
Trip Class	5	10	20									
Time Delay (s)		1.5 x FLA	120	240	480	For warm start						
Depending on	t <sub>r</sub>	6 x FLA	6.5	13.5	26	For cold start						
selected trip class		7.2 x FLA	5	10	20	For cold start						
S Short Circuits:	Short-time pro	tection wit	th fixed t	ime dela	/							
Pick-up (A) accuracy ±15%	I <sub>sd</sub> = FLA x		5	6	7	8	9	10	11	12	13	
	t <sub>sd</sub>		Non-adjustable									
Time delay (ms)	Non-tripping tim	е	20									
	Maximum break	time	60									
I Short Circuit: N	on-adjustable i	nstantane	ous prote	ection								
Pick-up (A) accuracy ±15%	I <sub>i</sub> non-adjustable	9	450	750	1500	2250	3750	4800	7200			
T: 11 ( )	Non-tripping tim	е	0				•	•				
Time delay (ms)	Maximum break	time	30 ms									
Phase unbalance	or phase loss		•									
Pick-up (A) accuracy ±20%	I <sub>unbal</sub> in % aver	age current <sup>2</sup>	30%									
Time delay (ms)	Non-adjustable	0.7 s during starting 4 s during normal operation										

<sup>&</sup>lt;sup>1</sup> Motor standards require operation at 104°F (40°C). Circuit-breaker ratings are derated to take this requirement into account.

 $<sup>^{2}</sup>$  The unbalance measurement takes into account the most unbalanced phase with respect to the average current.

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Motor Circuit Protection

#### **Additional Technical Characteristics**

Table 51: Additional Technical Characteristics




Table 52: L-Frame Electronic Trip Unit Magnetic Only 3 Pole, 600 Vac, 50/60 Hz—Three Device Solutions<sup>1</sup>

Sensor Rating		Trip Unit	Adjustable <sup>2</sup> Trip Range (A)	G-Interrupting Cat. No.	J-Interrupting Cat. No.	L-Interrupting Cat. No.	R-Interrupting Cat. No.
PowerPact	400	1.3 M	500-1200%	LGL36400M37X	LJL36400M37X	LLL36400M37X	LRL36400M37X
L-Frame	600	1.3 1/1	500-1200%	LGL36600M37X	LJL36600M37X	LLL36600M37X	LRL36600M37X

<sup>1</sup> Three-device solutions are the traditional solutions: motor circuit protector plus motor starter plus overload relay.

 $<sup>^2</sup>$   $\,$  UL magnetic trip tolerances are -20%/+30% from the nominal values shown.

## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Motor Circuit Protection**

H-Frame (150 A), J-Frame (250 A) and L-Frame (600 A) Electronic Motor Protector Circuit Breakers Table 53: (UL Ratings)—Two Device Solutions<sup>1</sup>

Electronic Trip Unit Type	Frame	Sensor Rating	Hnit	Full Load Amperes Range (FLA)	I <sub>sd</sub> (x FLA)	G Interrupting Cat. No.	J Interrupting Cat. No.	L Interrupting Cat. No.	R Interrupting Cat. No.				
		30	2.2 M	14–25	5-13 x FLA	HGL36030M38X	HJL36030M38X	HLL36030M38X	HRL36030M38X				
II Frame	H-Frame	50		14–42	5-13 x FLA	HGL36050M38X	HJL36050M38X	HLL36050M38X	HRL36050M38X				
	i i-i iailie	100		30–80	5-13 x FLA	HGL36100M38X	HJL36100M38X	HLL36100M38X	HRL36100M38X				
Standard <sup>2</sup>		150		58–130	5-13 x FLA	HGL36150M38X	HJL36150M38X	HLL36150M38X	HRL36150M38X				
	J-Frame	250		114–217	5-13 x FLA	JGL36250M38X	JJL36250M38X	JLL36250M38X	JRL36250M38X				
L-Fram	I Eramo	L-Frame 400 2.3	2 2 M	190–348	5-13 x FLA	LGL36400M38X	LJL36400M38X	LLL36400M38X	LRL36400M38X				
	L-Frame		600	600	600	600			2.3 101	312–520	5-13 x FLA	LGL36600M38X	LJL36600M38X

Two-device solutions (these electronic motor protector circuit breakers include short circuit and overload protection)

<sup>—1</sup> electronic motor circuit protector with a Micrologic 2.2 M electronic trip unit, plus
—1 contactor

 $<sup>^{2}</sup>$  The standard trip unit offers Class 5, 10 and 20 and phase unbalance or phase loss protection.

## **Section 6—Trip Units**

## **Available Trip Units**

- PowerPact™ H-, J-, and L-Frame circuit breakers offer a range of thermal-magnetic and Micrologic™ electronic trip units in interchangeable cases. Thermal-magnetic trip units are designed to open automatically under overload or short circuit. H-frame and J-frame thermalmagnetic circuit breakers contain individual thermal (overload) and instantaneous (short circuit) sensing elements in each pole.
- Micrologic electronic trip units provide intelligent operation, with wide setting ranges make
  installation upgrades easier. Designed with processing capabilities, Micrologic trip units can
  provide measurement information and device operating assistance to supply all of the information
  required to manage the electrical installation and optimize energy use.

Micrologic trip units offer excellent measurement accuracy, using a new generation of current transformers combining "iron-core" sensors for self-powered electronics and "air-core" sensors (Rogowski coils) for measurements. The protection functions are managed by an ASIC component that is independent of the measurement functions. This independence ensures immunity to conducted and radiated disturbances and a high level of reliability.

An LED on the front of the electronic trip units indicates the result of the self-test running continuously on the measurement system and the tripping release. When the green LED is flashing, the links between the CTs, the processing electronics and the Mitop release are operational. The circuit breaker is ready to protect. A minimum current of 15 to 50 A, depending on the device, is required for this function.


The dual adjustment for protection functions on Micrologic 5 / 6 consists of:

- an adjustment using rotary switches sets the maximum value
- an adjustment, made using the keypad or remotely, fine-tunes the setting. This setting may not
  exceed the first one. It can be read directly on the Micrologic screen, to within one ampere and
  a fraction of a second.

**NOTE:** All the trip units have a transparent sealable cover that protects access to the adjustment rotary switches.

01/2014


Table 54: Understanding the Names of Micrologic Electronic Trip Units



For Micrologic trip unit features, see table 9 on page 20.

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

Table 55: Trip Unit Availability




NOTE: W = mission critical trip unit.


01/2014

## **Protection of Distribution Systems**

## **Thermal-Magnetic Trip Units**

TM thermal-magnetic trip units can be used on PowerPact H and J-frame circuit breakers with interrupting levels D/G/J/L. Thermal-magnetic trip units are available in factory sealed or field-interchangeable constructions.





**H-Frame Trip Curve** 

- (I<sub>n</sub>) Fixed threshold thermal protection against overload
- (I<sub>i</sub>) **Fixed** threshold instantaneous protection against short circuits






Table 56: H-Frame and J-Frame 3P Field-Installable Thermal-Magnetic Trip Unit

15-60 A H-Fr	15-60 A H-Frame		ame	150–250 A J-Fra	150-250 A J-Frame			
Amperage	Cat. No.	Amperage	Cat. No.	Amperage	Cat. No.			
15 A	HT3015	70 A	HT3070	150 A	JT3150			
20 A	HT3020	80 A	HT3080	175 A	JT3175			
25 A	HT3025	90 A	HT3090	200 A	JT3200			
30 A	HT3030	100 A	HT3100	225 A	JT3225			
35 A	HT3035	110 A	HT3110	250 A	JT3250			
40 A	HT3040	125 A	HT3125	_	_			
45 A	HT3045	150 A	HT3150	_	_			
50 A	HT3050	_	_	_	_			
60 A	HT3060	_	_	_	_			

## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Trip Units**

## **Micrologic 3 Trip Units**

Micrologic 3 trip units can be used on PowerPact H-, J-, and L-Frame circuit breakers with performance levels D/G/J/L.



#### They provide:

- standard protection of distribution cables
- indication of:
  - overloads (using LEDs)
  - overload tripping (using the SDx relay module).

Circuit breakers equipped with Micrologic 3 trip units can be used to protect distribution systems supplied by transformers.

#### Protection

Settings are made using the adjustment rotary switches.

Overloads: Long time protection (I<sub>r</sub>)

Inverse time protection against overloads with an adjustable current pick-up I, set using a rotary switch and an adjustable time delay tr.

#### Neutral protection


- On 3-pole L-frame circuit breakers, neutral protection is not possible.
- On four-pole L-frame circuit breakers, neutral protection may be set using a three-position switch:
  - switch position 4P 3D: neutral unprotected
  - switch position 4P 3D + N/2: neutral protection at half the value of the phase pick-up, (0.5 x I<sub>r</sub>)
  - switch position 4P 4D: neutral fully protected at I<sub>r</sub>



#### **Indicators**



Front Indicators



#### Front indicators

- The green "Ready" LED blinks slowly when the electronic trip unit is ready to provide protection. It indicates the trip unit is operating correctly.
- Orange overload pre-alarm LED: steady on when I > 90% I<sub>r</sub>
- Red overload LED: steady on when I > 105% I<sub>r</sub>

#### Remote indicators

An overload trip signal can be remotely checked by installing an SDx relay module inside the circuit breaker. This module receives the signal from the Micrologic electronic trip unit through an optical link and makes it available on the terminal block. The signal is cleared when the circuit breaker is reclosed. See page 98.

Table 57: Micrologic 3 Trip Unit

Ratings	I <sub>n</sub> at 104°F (40°C) <sup>1</sup>	60 A	100 A	150 A	250 A	400 A	600 A
Circuit Breaker	H-frame	Х	Χ	Х			
	J-frame				Х		
	L-frame				Χ	Χ	X

#### Micrologic 3.2 / 3.3 trip units<sup>2</sup>

L Long-time protect	tion											
	I <sub>r</sub>		Value	Value depending on sensor rating (I <sub>n</sub> ) and setting on rotary switch								
	I <sub>n</sub> =60 A	I <sub>r</sub> =	15	20	25	30	35	40	45	50	60	
Pick-Up (A)	I <sub>n</sub> = 100 A	I <sub>r</sub> =	35	40	45	50	60	70	80	90	100	
Tripping between	I <sub>n</sub> = 150 A	I <sub>r</sub> =	50	60	70	80	90	100	110	125	150	
ripping between .05 and 1.20 I <sub>r</sub> ime Delay (s) .ccuracy 0 to -20%	I <sub>n</sub> = 250 A	I <sub>r</sub> =	70	80	100	125	150	175	200	225	250	
	I <sub>n</sub> = 400 A	I <sub>r</sub> =	125	150	175	200	225	250	300	350	400	
	I <sub>n</sub> = 600 A	I <sub>r</sub> =	200	225	250	300	350	400	450	500	600	
	t <sub>r</sub>		0.5	1	2	4	8	16				
Time Delay (s)		1.5 x l <sub>r</sub>	15	25	50	100	200	400				
Accuracy 0 to -20%	6 x I <sub>r</sub>		0.5	1	2	4	8	16				
		7.2 x l <sub>r</sub>	0.35	0.7	1.4	2.8	5.5	11				
Thermal memory			20 min	utes bef	ore and	after trip	ping					
I Instantaneous												
		60 A	1.5	2	3	4	6	8	10	12	15	
		100 A	1.5	2	3	4	6	8	10	12	15	
	Lw	150 A	1.5	2	3	4	6	8	10	12	15	
Pick-up (A)	l <sub>i</sub> x	250 A	1.5	2	3	4	5	6	8	10	12	
accuracy ± 15%		400 A	1.5	2	3	4	5	6	8	10	12	
		600 A	1.5	2	3	4	5	6	8	10	11	
	Non-tripping time Maximum break time		10 ms 50 ms	for I > 1.	5 li			_				

#### Micrologic 3.2S / 3.3S trip units<sup>2</sup>

			_							
ion										
l <sub>r</sub>		Value depending on sensor rating $(I_n)$ and setting on rotary switch								
I <sub>n</sub> =60 A	I <sub>r</sub> =	15	20	25	30	35	40	45	50	60
I <sub>n</sub> = 100 A	I <sub>r</sub> =	35	40	45	50	60	70	80	90	100
I <sub>n</sub> = 150 A	I <sub>r</sub> =	50	60	70	80	90	100	110	125	150
I <sub>n</sub> = 250 A	I <sub>r</sub> =	70	80	100	125	150	175	200	225	250
I <sub>n</sub> = 400 A	I <sub>r</sub> =	125	150	175	200	225	250	300	350	400
I <sub>n</sub> = 600 A	I <sub>r</sub> =	200	225	250	300	350	400	450	500	600
t <sub>r</sub>		non-adjustable								
	1.5 x I <sub>r</sub>	400								
	6 x I <sub>r</sub>	16								
	7.2 x I <sub>r</sub>	11								
		20 minutes before and after tripping								
tion										
I <sub>sd</sub> - I <sub>r</sub> x		1.5	2	3	4	5	6	7	8	10
t <sub>sd</sub>		non-adjustable								
Non-tripping time Maximum break time		20 80								
l <sub>i</sub> x l <sub>n</sub>		1.5	2	3	4	6	8	10	12	15
Non-tripping time Maximum break time		10 ms 50 ms for I > 1.5 li								
	I <sub>r</sub> I <sub>n</sub> =60 A I <sub>n</sub> = 100 A I <sub>n</sub> = 150 A I <sub>n</sub> = 250 A I <sub>n</sub> = 400 A I <sub>n</sub> = 600 A I <sub>r</sub> = 600 A	$ \begin{aligned} &\frac{\textbf{I}_{\textbf{r}}}{\textbf{I}_{\textbf{n}}} = & \textbf{60 A} & \textbf{I}_{\textbf{r}} = \\ &\textbf{I}_{\textbf{n}} = & \textbf{100 A} & \textbf{I}_{\textbf{r}} = \\ &\textbf{I}_{\textbf{n}} = & \textbf{150 A} & \textbf{I}_{\textbf{r}} = \\ &\textbf{I}_{\textbf{n}} = & \textbf{150 A} & \textbf{I}_{\textbf{r}} = \\ &\textbf{I}_{\textbf{n}} = & \textbf{250 A} & \textbf{I}_{\textbf{r}} = \\ &\textbf{I}_{\textbf{n}} = & \textbf{400 A} & \textbf{I}_{\textbf{r}} = \\ &\textbf{I}_{\textbf{n}} = & \textbf{600 A} & \textbf{I}_{\textbf{r}} = \\ &\textbf{t}_{\textbf{r}} = & \\ &\textbf{1.5 x I_{\textbf{r}}} \\ && & \textbf{6 x I_{\textbf{r}}} \\ && & & \textbf{7.2 x I_{\textbf{r}}} \end{aligned} $	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Value depending on sensor rating (In) and set     In = 60 A	Value depending on sensor rating (I <sub>n</sub> ) and setting of I <sub>n</sub> = 60 A	Value depending on sensor rating (In) and setting on rotary     In = 60 A				

<sup>1</sup> If the trip units are used in high-temperature environments, the Micrologic trip unit setting must take into account the thermal limitations of the circuit breaker. See the temperature derating information on page 129.


<sup>2</sup> Mission Critical trip units have a "-W" at the end of the number (for example 3.2-W). All other protections are the same and have the same trip curves.



## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

## Micrologic 5 / 6 A or E Trip Units

Micrologic 5 / 6 A (Ammeter) or E (Energy) trip units can be used on PowerPact H-, J-, and L-frame circuit breakers with performance levels D, G, J, or L. They all have a front display module. They offer basic LSI protection (Micrologic 5 trip unit) or LSI and ground-fault protection G (Micrologic 6 trip unit). They also offer measurement, alarm and energy values.



The capabilities of Micrologic 5 / 6 A and E trip units come into full play with the front display module. When the two are connected using a simple cable with RJ45 connectors, the combination offers full Power Meter capabilities and all the measurements required to monitor the electrical installation.

	Measurements	Operating and Maintenance Assistance	Communication Network
Ammeter (Micrologic A Trip Unit)	Current measurements  Phase and neutral currents I <sub>A</sub> , I <sub>B</sub> , I <sub>C</sub> , I <sub>N</sub> Average current of the 3 phases I <sub>avg</sub> Highest current of the three phases I <sub>max</sub> Ground-fault current Ig (Micrologic 6.2 / 6.3 A) trip units  Maximum and minimum current measured	Indicators, alarms and histories  Fault types  Alarms for high/low alarm thresholds linked to I measurements  Trip, alarm and operating histories  Time-stamped tables for settings and maximum current  Maintenance indicators  Operation, trip and alarm counters  Operating hours counter  Contact wear  Load profile and thermal image	Modbus with add-on module
Energy (Micrologic E Trip Unit)	Current measurements  Phase and neutral currents I <sub>A</sub> , I <sub>B</sub> , I <sub>C</sub> , I <sub>N</sub> Average current of the 3 phases I <sub>avg</sub> Highest current of the three phases I <sub>max</sub> Ground-fault current I <sub>g</sub> (Micrologic 6.2 / 6.3 A trip units) Maximum and minimum current measured Current unbalance between phases Voltage measurements Phase-to-phase (V) and phase-to-neutral (U) voltages Average voltages V <sub>avg</sub> , U <sub>avg</sub> Ph-Ph (V) and Ph-N (U) voltage unbalance Frequency measurements Frequency (f) Power-quality indicators Total harmonic distortion (THD) for current and voltage Power measurements Active, reactive and apparent power, total and per phase Power factor and cos φ Maximum and minimum For all I, V, f, P, E measurements Demand current and power measurements Demand values, total and per phase Maximum demand Energy metering Active, reactive and apparent energy, total and per phase	Indicators, alarms and histories  Fault types Alarms for high/low thresholds linked to I, V, f, P, E measurements Trip, alarm and operating histories Time-stamped tables for settings and I, V, f, P, E maximum values Maintenance indicators Operation, trip and alarm counters Operating hours counter Contact wear Load profile and thermal image	Modbus with add-on module

01/2014

#### **Power Requirements**

The amount of current needed to power the trip unit is printed in the upper left hand corner of the trip unit by the Ready LED.

Table 58: Trip Unit Power Requirements

Frame		Power-Up Requirement
	60 A	> 15 A
H-Frame, 60 A	100 A	> 15 A
	150 A	> 30 A
J-Frame, 250A	250A	> 30 A
L-Frame, 600 A	400 A	> 50 A
L-I fame, 600 A	600 A	> 50 A

#### **Protection**

Settings can be adjusted in two ways, using the rotary switches and/or the keypad.

- The keypad can be used to make fine adjustments in 1 A steps below the maximum value defined by the setting on the rotary switch.
- Access to setting modifications using the keypad is protected by a locking function displayed on the screen and controlled by a microswitch.
- The lock is activated automatically if the keypad is not used for 5 minutes.
- Access to the microswitch is protected by a transparent, sealable cover.
- With the cover closed, it is still possible to display the various settings and measurements using the keypad.

#### Overloads: Long-Time Protection (I<sub>r</sub>)

Inverse time protection against overloads with an adjustable current pick-up  $I_r$  is set using a rotary switch or the keypad for fine adjustments. The time delay  $t_r$  is set using the keypad.

#### Short-Circuits: Short-Time Protection (I<sub>sd</sub>)

Short-circuit protection with an adjustable pick-up  $I_{sd}$  and adjustable time delay  $t_{sd}$ , with the possibility of including a portion of an inverse time curve ( $I^2t$  On).

#### Short-Circuits: Instantaneous Protection (I<sub>i</sub>)

Instantaneous protection with adjustable pick-up Ii.

#### Additional Ground Fault Protection (I<sub>a</sub>) on Micrologic 6 Trip Units

Residual type ground-fault protection with an adjustable pick-up I<sub>g</sub> and adjustable time delay t<sub>g</sub>. Possibility of including a portion of an inverse time curve (I<sup>2</sup>t On).

#### **Neutral Protection**

- On 4-pole circuit breakers, this protection can be set using the keypad:
  - Off: neutral unprotected
  - 0.5: neutral protection at half the value of the phase pick-up (0.5 x l<sub>r</sub>)
  - 1.0: neutral fully protected at I<sub>r</sub>
  - OSN: Oversized neutral protection at 1.6 times the value of the phase pick-up. Used when there is a high level of 3rd order harmonics (or orders that are multiples of 3) that accumulate in the neutral and create a high current. In this case, the device must be limited to  $I_r = 0.63 \times I_n$  for the maximum neutral protection setting of 1.6 x  $I_r$ .
- With 3-pole circuit breakers, the neutral can be protected by installing an external neutral sensor with the output (T1, T2) connected to the trip unit.




## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

#### Zone Selective Interlocking (ZSI)

A ZSI terminal block may be used to interconnect a number of Micrologic trip units to provide zone selective interlocking for short-time ( $I_{sd}$ ) and ground-fault ( $I_{g}$ ) protection, without a time delay. For PowerPact H- and J-frame circuit breakers, the ZSI function is available only in relation to the upstream circuit breaker (ZSI out). For PowerPact L-frame circuit breakers, the ZSI function is available in relation to the upstream circuit breaker (ZSI out) and downstream circuit breakers (ZSI in).

#### Display of Type of Fault.




Display of Interrupted Current.

On a fault trip, the type of fault  $(I_r, I_{sd}, I_i, I_g)$ , the phase concerned and the interrupted current are displayed. An external power supply is required.

#### **Indicators**

#### Front Indicators



- The green "Ready" LED blinks slowly when the electronic trip unit is ready to provide protection. It
  indicates the trip unit is operating correctly.
- Orange overload pre-alarm LED stays on when I > 90% I<sub>r</sub>
- Red overload LED stays on when I > 105% I<sub>r</sub>

#### Remote Indicators

An SDx relay module installed inside the circuit breaker can be used to remote the following information:

- overload trip
- overload prealarm (Micrologic 5 trip units) or ground fault trip (Micrologic 6 trip units).

This module receives the signal from the Micrologic electronic trip unit through an optical link and makes it available on the terminal block. The signal is cleared when the circuit breaker is closed. Note: all the trip units have a transparent sealable cover.

These outputs can be reprogrammed to be assigned to other types of tripping or that protects access to the adjustment rotary switch. The module is described in detail in the section dealing with accessories.



SDx Module

01/2014

Table 59: Micrologic 5/6 Trip Unit<sup>1</sup>

Ratings	I <sub>n</sub> at 104°F (4	0°C) <sup>2</sup>		60 A	100 A	150 A	250 A	400 A	600 A					
	H-frame			Х	Х	Х								
Circuit Breaker	J-frame						Х							
	L-frame							Х	x x son rotary switch 40 45 50 70 80 90 100 110 125 175 200 225 250 300 350 400 450 500 on rotary switch 16 400 16 11					
L Long-time prof	tection													
	I <sub>r</sub>	rotary switch		Value dep	ending on	the trip unit	rating (I <sub>n</sub> ) a	and setting	on rotary sw	ritch				
	I <sub>n</sub> = 60 A	I <sub>r</sub> =		15	20	25	30	35	40	45	50	60		
Pick-up (A)	I <sub>n</sub> = 100 A	I <sub>r</sub> =		35	40	45	50	60	70	80	90	100		
tripping between	I <sub>n</sub> = 150 A	I <sub>r</sub> =		50	60	70	80	90	100	110	125	150		
1.05 and 1.20 I <sub>r</sub>	I <sub>n</sub> = 250 A	lr =		70	80	100	125	150	175	200	225	250		
	I <sub>n</sub> = 400 A	lr =		125	150	175	200	225	250	300	350	400		
	I <sub>n</sub> = 600 A	lr =		200	225	250	300	350	400	450	500	600		
		keypad settin	keypad setting		Fine adjustment in 1 A steps below maximum value set on rotary switch									
	tr =	keypad settin	g	0.5	1	2	4	8	16					
Time Delay (s)		1.5 x lr		15	25	50	100	200	400					
Accuracy 0 to -20%		6 x Ir		0.5	1	2	4	8	16					
		7.2 x lr		0.35	0.7	1.4	2.8	5.5	11					
Thermal memory	·			20 minute	inutes before and after tripping									
S Short-time pro	tection													
Pick-up (A)	I <sub>sd</sub>	keypad settin	g	1.5 2	2.5 3	3.5 4	4.5 5	5.5 6	6.5 7	7.5 8	8.5 9	9.5 10		
accuracy ± 10%			Tion orr			<del>- ' '</del>	using the k	· ·						
1	t <sub>sd</sub> =	Keypad setting	I <sup>2</sup> t Off	0	0.1 s	0.2 s	0.3 s 0.3 s	0.4 s						
Time delay	Non trinning tin		12t On	20 ms	0.1 S 80 ms	0.2 s 140 ms	230 ms	0.4 s 350 ms						
	Maximum brea	Non-tripping time			140 ms	200 ms	320 ms	500 ms						
Instantaneous	Iviaximum brea	K time		80 ms	140 1113	200 1113	020 1113	300 1113						
Tillstalitarieous				1		Т.	1.	I <sub>o</sub>	I o	140	140	15		
			00 4											
			60 A	1.5	2	.3	4	6						
			100 A	1.5	2	.3	4	6	8	10	12	15		
Pick-up (A)	$I_i = I_n x$	Rotary Switch	100 A 150 A	1.5 1.5	2	.3	4	6	8	10 10	12 12	15 15		
Pick-up (A)	$I_i = I_n x$	Rotary Switch	100 A 150 A 250 A	1.5 1.5 1.5	2 2 2	.3 .3	4 4 4	6 6 5	8 8 6	10 10 8	12 12 10	15 15 12		
Pick-up (A) accuracy ± 15%	$I_i = I_n x$		100 A 150 A 250 A 400 A	1.5 1.5 1.5 1.5	2 2 2 2	.3 .3 .3	4 4 4 4	6 6 5 5	8 8 6 6	10 10 8 8	12 12 10 10	15 15 12 12		
	Non-tripping tin	Switch	100 A 150 A 250 A	1.5 1.5 1.5 1.5 1.5 1.0 ms	2 2 2 2 2	.3 .3	4 4 4	6 6 5	8 8 6 6	10 10 8 8	12 12 10 10	15 15 12		
accuracy ± 15%	Non-tripping tin	Switch ne k time	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 1.5 0 ms for	2 2 2 2 2 2	.3 .3 .3	4 4 4 4	6 6 5 5	8 8 6 6	10 10 8 8	12 12 10 10	15 15 12 12		
	Non-tripping tin Maximum brea	Switch  ne k time  Micrologic	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 1.5 0 ms for	2 2 2 2 2 2	.3 .3 .3	4 4 4 4	6 6 5 5	8 8 6 6	10 10 8 8	12 12 10 10	15 15 12 12		
accuracy ± 15%  G Ground-fault p	Non-tripping tin Maximum brea protection - for I <sub>g</sub>	ne k time  Micrologic  Keypad Settin	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 1.5 10 ms 50 ms for	2 2 2 2 2 2 1 > 1i	.3 .3 .3 .3	4 4 4 4	6 6 5 5 5	8 8 6 6 6	10 10 8 8 8	12 12 10 10 10	15 15 12 12		
accuracy ± 15%	Non-tripping tin Maximum brea protection - for I <sub>g</sub> I <sub>n</sub> = 60 A	ne k time  * Micrologic  Keypad Settin	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 10 ms 50 ms for Trip Units	2 2 2 2 2 2 1 > 1i	.3 .3 .3 .3 .3	4 4 4 4 4	6 6 5 5 5 5	8 8 6 6 6 6	10 10 8 8 8 8	12 12 10 10 10	15 15 12 12 11		
accuracy ± 15%  G Ground-fault p  Pick-up (A)	Non-tripping tin Maximum brea protection - for I <sub>g</sub>	ne k time  Micrologic  Keypad Settin  I <sub>g</sub> =  I <sub>g</sub> =	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 10 ms 50 ms for  Trip Units 0.3 0.35 0.2 2.5	2 2 2 2 2 2 1 > 1i 3	.3 .3 .3 .3 .3 .3	4 4 4 4 4 4 4 5 0.6 0.65 5 0.5 0.55	6 6 5 5 5 5 0.7 0.75 0.6 0.65	8 8 6 6 6 6	10 10 8 8 8 8	12 12 10 10 10	15 15 12 12		
accuracy ± 15%  G Ground-fault p  Pick-up (A)	Non-tripping tin Maximum brea protection - for I <sub>g</sub> I <sub>n</sub> = 60 A	ne k time  Micrologic  Keypad Settii  Ig = Ig = Keypad	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 10 ms 50 ms for  Trip Units 0.3 0.35 0.2 2.5	2 2 2 2 2 2 1 > 1i 3 0.4 0.45 0.3 0.35 0.1	.3 .3 .3 .3 .3 .3 .3 .4 .0.5 .0.5 .0.4 .0.4 .0.2	4 4 4 4 4 4 4 5 0.6 0.65 0.5 0.5 0.3	6 6 5 5 5 5 5 5 0.7 0.75 0.6 0.65 0.4	8 8 6 6 6 6	10 10 8 8 8 8	12 12 10 10 10	15 15 12 12 11		
accuracy ± 15%  G Ground-fault p  Pick-up (A)	Non-tripping tin Maximum brea protection - for $\frac{I_g}{I_n=60 \text{ A}}$ $\frac{I_n=100-600 \text{ A}}{t_g=100-600 \text{ A}}$	switch  ne k time  Micrologic  Keypad Settin  Ig =  Ig =  Keypad  setting	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 10 ms 50 ms for  Trip Units 0.3 0.35 0.2 2.5	2 2 2 2 2 2 1 > 1i 3 0.4 0.45 0.3 0.35 0.1 0.1	.3 .3 .3 .3 .3 .3 .3 .0.5 0.4 0.4 0.2	4 4 4 4 4 4 4 5 0.6 0.65 5 0.5 0.55 0.3 0.3	6 6 5 5 5 5 5 0.7 0.75 0.6 0.65 0.4 0.4	8 8 6 6 6 6	10 10 8 8 8 8	12 12 10 10 10	15 15 12 12 11		
G Ground-fault p Pick-up (A) accuracy ± 10%	Non-tripping tin Maximum brea protection - for I <sub>g</sub> I <sub>n</sub> = 60 A I <sub>n</sub> = 100–600 A	Switch  ne k time  Micrologic  Keypad Settin  I <sub>g</sub> =  I <sub>g</sub> =  Keypad  setting  ne	100 A 150 A 250 A 400 A 600 A	1.5 1.5 1.5 1.5 1.5 10 ms 50 ms for  Trip Units 0.3 0.35 0.2 2.5	2 2 2 2 2 2 1 > 1i 3 0.4 0.45 0.3 0.35 0.1	.3 .3 .3 .3 .3 .3 .3 .4 .0.5 .0.5 .0.4 .0.4 .0.2	4 4 4 4 4 4 4 5 0.6 0.65 0.5 0.5 0.3	6 6 5 5 5 5 5 5 0.7 0.75 0.6 0.65 0.4	8 8 6 6 6 6	10 10 8 8 8 8	12 12 10 10 10	15 15 12 12 11		

<sup>1</sup> Mission Critical trip units have a "-W" at the end of the number (for example 3.2-W). All other protections are the same and have the same trip curves.



<sup>&</sup>lt;sup>2</sup> If the trip units are used in high-temperature environments, the Micrologic trip unit setting must take into account the thermal limitations of the circuit breaker. See the temperature derating information on page 129.

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Units

Table 60: Micrologic 3 Field-Installable Trip Units<sup>1</sup>

Circuit Bro	eaker				
Frame	Standard	Poles	Rating	Trip Unit Type	Catalog No.
		3P	60 A	Micrologic 3.2	HE3060U31X
		3P	60 A	Micrologic 3.2S	HE3060U33X
H-frame	UL/CSA/NOM	3P	100 A	Micrologic 3.2	HE3100U31X
H-Trame	UL/CSA/NOM	3P	100 A	Micrologic 3.2S	HE3100U33X
		3P	150 A	Micrologic 3.2	HE3150U31X
		3P	150 A	Micrologic 3.2S	HE3150U33X
J-Frame UL/CSA/NO	LIL /OCA/NOM	3P	250 A	Micrologic 3.2	JE3250U31X
	UL/CSA/NOM	3P	250 A	Micrologic 3.2S	JE3250U33X
			250 A	Micrologic 3.3	LE3250U31X
				Micrologic 3.3S	LE3250U33X
		o.D.	400 A	Micrologic 3.3	LE3400U31X
		3P		Micrologic 3.3S	LE3400U33X
			600.4	Micrologic 3.3	LE3600U31X
L-Frame	UL/CSA/NOM		600 A	Micrologic 3.3S	LE3600U33X
∟-rame	UL/CSA/NOM		050 A	Micrologic 3.3	LE4250U31X
			250 A	Micrologic 3.3S	LE4250U33X
		4P	400 A	Micrologic 3.3	LE4400U31X
		45	400 A	Micrologic 3.3S	LE4400U33X
			600 A	Micrologic 3.3	LE4600U31X
			600 A	Micrologic 3.3S	LE4600U33X

<sup>1</sup> Mission Critical trip units that end in "W" are factory sealed and are not available as field installable units.

## PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Units

Table 61: Micrologic 5 and 6 Field-Installable Trip Units<sup>1</sup>

Circuit Bro	eaker				
Frame	Standard	Poles	Rating	Trip Unit Type	Catalog No.
				Micrologic 5.2 A	HE3060U43X
				Micrologic 6.2 A	HE3060U44X
			60 A	Micrologic 5.2 E	HE3060U53X
				Micrologic 6.2 E	HE3060U54X
				Micrologic 5.2 A	HE3060U43X
1 6	LU /00A /NOM	o.D.		Micrologic 6.2 A	HE3100U44X
H-frame	UL/CSA/NOM	3P	100 A	Micrologic 5.2 E	HE3100U53X
				Micrologic 6.2 E	HE3100U54X
				Micrologic 5.2 A	HE3150U43X
			150 A	Micrologic 6.2 A	HE3150U44X
				Micrologic 5.2 E	HE3150U53X
				Micrologic 6.2 E	HE3150U54X
J-Frame I		3Р	250 A	Micrologic 5.2 A	JE3250U43X
	UL/CSA/NOM			Micrologic 6.2 A	JE3250U44X
-rrame	UL/CSA/NOM			Micrologic 5.2 E	JE3250U53X
				Micrologic 6.2 E	JE3250U54X
			400 A	Micrologic 5.3 A	LE3400U43X
				Micrologic 6.3 A	LE3400U44X
				Micrologic 5.3 E	LE3400U53X
	UL/CSA/NOM	3P		Micrologic 6.3 E	LE3400U54X
	OL/CSA/NOW	35		Micrologic 5.3 A	LE3600U43X
			600 A	Micrologic 6.3 A	LE3600U44X
			000 A	Micrologic 5.3 E	LE3600U53X
-Frame				Micrologic 6.3 E	LE3600U54X
-i raine				Micrologic 5.3 A	LE4400U43X
			400 A	Micrologic 6.3 A	LE4400U44X
			400 A	Micrologic 5.3 E	LE4400U53X
	UL/CSA/NOM	4P		Micrologic 6.3 E	LE4400U54X
	OL/OSA/NOW	45		Micrologic 5.3 A	LE4600U43X
			600 A	Micrologic 6.3 A	LE4600U44X
			000 A	Micrologic 5.3 E	LE4600U53X
				Micrologic 6.3 E	LE4600U54X

<sup>1</sup> Mission Critical trip units that end in "W" are factory sealed and are not available as field installable units.

**Table 62: Micrologic Spare Parts** 

Description	Frame	Trip Unit	Catalog No.
LOD District	11/1/1	Micrologic 5	S429483
LCD Display	H/J/L	Micrologic 6	S429484
T: 11:10	H/J	Micrologia	S429481
	L	Micrologic 3	S432461
Trip Unit Cover-Transparent	H/J	Micrologia F/G	S429478
	L	Micrologic 5/6	S432459
Trip Unit Wire Seal	Н	Micrologic 3/5/6	MICROTUSEA

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

#### **Power Meter Functions**

In addition to protection functions, Micrologic 5 / 6 trip units offer all the functions of Power Meter products as well as operating-assistance for the circuit breaker.

- display of settings
- measurement functions:
  - Ammeter (A)
  - Energy (E)
- alarms
- · time-stamped histories and event tables
- maintenance indicator
- communication network.

Micrologic A and E trip unit measurement functions are made possible by the trip unit intelligence and the accuracy of the sensors. They are handled by a microprocessor that operates independent of protection functions.

#### **Display**

#### Micrologic Trip Unit LCD

The user can display all the protection settings and the main measurements on the LCD screen of the trip unit.

- Micrologic A trip unit: instantaneous rms current measurements
- Micrologic E trip unit: voltage, frequency and power measurements and energy metering, in addition to the measurements offered by Micrologic A

To make the display available under all conditions and increase operating comfort, an external power supply is recommended for Micrologic A trip unit. It is indispensable to:

- display faults and interrupted current measurements
- use all the functions of Micrologic E trip unit (such as metering of low power and energy values)
- · ensure operation of the communication network.

The external power supply can be shared by several devices. For description, see page 83.

#### Front Display Module (FDM121)

An FDM121 can be connected to a Micrologic trip unit using a prefabricated cable to display all measurements on a screen. The result is a veritable  $96 \times 96$  mm Power Meter.

In addition to the information displayed on the Micrologic trip unit LCD, the FDM121 screen shows demand, power quality and maximum/minimum values along with alarms, histories and maintenance indicators.

The FDM121 requires a 24 Vdc power supply. The Micrologic trip unit is supplied by the same power supply through the cable connecting it to the FDM.

#### **PC Screen**

When the Micrologic trip unit, with or without a front display module, is connected to a communication network, all information can be accessed using a PC with the appropriate software installed.






FDM121 Display

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

#### Measurements

# IA 431 A IB 385 A IC 426 A IN 2 A ESC 888




100 120


Y

ESC ▼ Voltage

IN E



Power



#### **Instantaneous RMS Measurements**

The Micrologic A and E trip units continuously display the RMS value of the highest current of the three phases and neutral (Imax). The navigation buttons can be used to scroll through the main measurements.

In the event of a fault trip, the current interrupted is memorized.

The Micrologic A trip unit measures phase, neutral, ground fault currents. The Micrologic E trip unit offers voltage, frequency and power measurements in addition to the measurements provided by Micrologic A trip unit.

#### **Maximum / Minimum Values**

Every instantaneous measurement provided by Micrologic A or E trip unit can be associated with a maximum/minimum. The maximum for the highest current of the three phases and neutral, the demand current and power can be reset using the trip unit keypad, the front display module or the communication network.

#### **Energy Metering**

The Micrologic E trip units also measures the energy consumed since the last reset of the meter. The active energy meter can be reset using the keypad and the front display module or the communication network.

#### **Demand and Maximum Demand Values**

Micrologic E trip units also calculates demand current and power values. These calculations can be made using a block or sliding interval that can be set from 5 to 60 minutes in steps of 1 minute. The window can be synchronized with a signal sent through the communication network. Whatever the calculation method, the calculated values can be recovered on a PC using the Modbus™ communication network.

Ordinary spreadsheet software can be used to provide trend curves and forecasts based on this data. They will provide a basis for load shedding and reconnection operations used to adjust consumption to the subscribed power.

#### **Power Quality**

Micrologic E trip units calculate power quality indicators taking into account the presence of up to the 15th order, including the total harmonic distortion (THD) of unit, current and voltage.

NOTE: The front display module will display voltage and current phases as A/B/C instead of 1/2/3.

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Units

Table 63: Micrologic 5/6 Trip Units Integrated Power Meter Functions

			Тур	е	Display	
			A	E	Trip Unit LCD	Front Display Module  Man manu (C) Duck vee  Materia A Marria A Services
Display of Protection S	ettings					
Pick-ups (A) and delays	All settings can be displayed	$I_r$ , $t_r$ , $I_{sd}$ , $t_{sd}$ , $I_i$ , $I_g$ , $t_g$	Χ	Х	Х	
Measurements						
Instantaneous rms	measurements					
	Phase and neutral	I <sub>A</sub> , I <sub>B</sub> , I <sub>C</sub> , I <sub>N</sub>	Χ	Х	Х	Х
	Average of phases	$lavg = (l_A + l_B + l_C) / 3$	Х	Х	_	X
Currents (A)	Highest current of the 3 phases and neutral	Imax of I <sub>A</sub> , I <sub>B</sub> , I <sub>C</sub> , I <sub>N</sub>	Х	Х	x	X
	Ground fault (Micrologic 6 trip unit)	% Ig (pick-up setting)	Х	Х	x	X
	Current unbalance between phases	% lavg	_	Х	_	X
	Phase-to-phase	V <sub>AB</sub> , V <sub>BC</sub> , V <sub>CA</sub>	_	Х	х	Х
	Phase-to-neutral	U <sub>AN</sub> , U <sub>B</sub> N, U <sub>CN</sub>	_	Х	x	X
	Average of phase-to-phase voltages	$Vavg = (V_{AB} + V_{AC} + V_{BC}) / 3$	_	Х	_	X
Voltage (V)	Average of phase-to-neutral voltages	Uavg = $(U_{AN} + U_{BN} + U_{CN}) / 3$	_	Х	_	X
	Ph-Ph and Ph-N voltage unbalance	% Vavg and% Uavg	_	Х	_	X
	Phase sequence	1-2-3, 1-3-2	_	Х	x	X
Frequency (Hz)	Power System	f	_	Х	Х	Х
	Active (kW)	P, total/per phase	_	Х	х	Х
	Reactive (kVAR)	Q, total/per phase	_	Х	x	X
Power	Apparent (kVA)	S, total/per phase	_	Х	x	X
	Power factor and cos φ (fundamental)	PF and cos φ, total and per phase	_	Х	_	X
Maximum, minimui			1	1	1	1
	Associated with instantaneous rms	Reset with Micrologic trip unit or front display	1	1		1
	measurements	module	Х	Х		X
Energy metering						
	Active (kWh), reactive (kVAR), apparent	Total since last reset		I		1
Energy	(kVA)	Absolute or signed mode <sup>1</sup>	_	Х	X	X
Demand and maxir	mum demand values	,		1	ı	
D		Present value on the selected window	_	Х	_	Х
Demand current (A)	Phases and neutral	Maximum demand since last reset	_	Х	_	Х
-	Active (kWh), reactive (kVAR), apparent	Present value on the selected window	_	Х	_	Х
Demand power	(kVA)	Maximum demand since last reset	_	х	_	Х
Calculation window		Adjustable from 5 to 60 minutes in 1 minute steps	_	Х	_	2
Power quality						
Total harmonic	Of voltage with respect to rms value	THDU, THDV of the Ph-Ph and Ph-N voltage	<u> </u>	Х	_	Х

<sup>&</sup>lt;sup>1</sup> Absolute mode: E absolute = E out + E in; Signed mode: E signed = E out - E in.

<sup>&</sup>lt;sup>2</sup> Available through the communication network only.

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

#### Additional technical characteristics

Measurement accuracy of the entire measurement system, including the sensors:

Current: +/- 1%Voltage: +/- 0.5%

Power and energy: +/- 2%

Frequency: +/- 0.1%.

## **Operating-Assistance Functions Characteristics**

### Micrologic Trip Unit Alarms with Time-Stamping

#### **Alarm Types**

The user can assign an alarm to all Micrologic A or E trip unit measurements or events:

- up to 12 alarms can be used together:
  - two alarms are predefined and activated automatically:
     Micrologic 5 trip unit: overload (I<sub>r</sub>)
     Micrologic 6 trip unit: overload (I<sub>r</sub>) and ground fault (I<sub>g</sub>)
  - thresholds, priorities and time delays can be set for ten other alarms.
- the same measurement can be used for different alarms to precisely monitor certain values, e.g. the frequency or the voltage
- alarms can also be assigned to various states: phase lead/lag, four quadrants,
- phase sequence selection of display priorities, with screen displaying a window showing high priority alarm
- · alarm time-stamping.

#### **Alarm Settings**

Alarms cannot be set using the keypad or the front display module. They are set through the communication network with the PC. Set-up includes the threshold, priority, activation delay before display and deactivation delay. It is also possible to reprogram the standard assignment for the two SDx relay outputs to user-selected alarms.

#### Alarm Reading

Remote alarm indicators

- · reading on the front display module or on a PC through the communication network
- system remote indicators using SDx relay with two output contacts for alarms.
- Micrologic trip unit built-in LCD display.

#### **Histories and Event Tables**

Micrologic A and E trip unit have histories and event tables that are always active.

#### Three types of time-stamped histories

- Tripping due to overruns of I<sub>r</sub>, I<sub>sd</sub>, I<sub>i</sub>, I<sub>g</sub>: last 17 trips
- Alarms: last 10 alarms
- Operating events: last 10 events

Each history record is stored with:

- indicators in clear text in a number of user-selectable languages
- · time-stamping: date and time of event
- status: pick-up / drop-out



## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

#### Two types of time-stamped event tables

- Protection settings
- Minimums / maximums

#### Display of alarms and tables

The time-stamped history and event tables may be displayed on a PC through the communication network.

#### **Embedded memory**

Micrologic A and E trip units have a non-volatile memory that saves all data on alarms, histories, event tables, counters and maintenance indicators even if power is lost.

#### Maintenance Indicators

Micrologic A and E trip units have indicators for, among others, the number of operating cycles, contact wear and operating times (operating hours counter) of the PowerPact H-, J-, and L-frame circuit breakers.

It is possible to assign an alarm to the operating cycle counter to plan maintenance. The various indicators can be used together with the trip histories to analyze the level of stresses the device has been subjected to. The information provided by the indicators cannot be displayed on the Micrologic trip unit LCD. It is displayed on the PC through the communication network.

#### **Management of Installed Devices**

Each circuit breaker equipped with a Micrologic 5 or 6 trip unit can be identified using the communication network:

- serial number
- firmware version
- hardware version
- · device name assigned by the user.

This information together with that previously described provides a clear view of the state of the installed devices.

**NOTE:** Please refer to page 77 for more details on display formats.

Table 64: Micrologic 5/6 Trip Units Operating Assistance Functions

									Туре	9	Display	
									A	E	Trip Unit LCD	Front Display Module  Moreone  Obligation  Alarms  Services
Operating Assistance										1	1	I.
Personalized Alarms												
Cottingo	Up to 10 alarms assigned to all A and	E measi	urements	3					Х	Х	_	1
Settings	Phase lead/lag, four quadrants, phase	e sequen	ce, displ	ay prior	ity selec	tion			_	Х	_	1
Display	Alarms and tripping								Х	Х	_	1
Remote Indicators	Activation of two dedicated contacts of	n SDx m	odule						Х	Х	_	1
Time-Stamped Histories												
Trips (last 17)	Cause of tripping (time-stamping with ms)	1	I <sub>i</sub> (Micro			Jnit)			X X	X X		1
Alarms (last 10)	1	y \	3 -						Х	Х	_	1
		Modif	cation o	f protec	tion sett	ina by	rotary s	witch	1_	Х	_	1
			Modification of protection setting by rotary switch Opening of keypad lock			_	X	_	1			
	Test using keypad				_	X	_	1				
Operating events (last 10)	Event types	Test using external tool			_	Х	_	1				
			Time setting (date and time) Reset for maximum, minimum and energy meter			_	Х	_	1			
						X	Х	x	Х			
Time Stamping	Presentation	Date and time, text, status			Х	Х	_	1				
Time-Stamped Event	Tables										1	1
	Setting modified (value displayed)	I <sub>r</sub>	t <sub>r</sub>	I <sub>sd</sub>	t <sub>sd</sub>	li	Iq	t <sub>q</sub>	Х	Х	_	1
Protection settings	Time-stamping		and time			L :	ı 'y	1.9	Х	Х	_	1
<b>3</b> .	Previous value		before r						X	X	_	1
	Values monitored	I <sub>A</sub>	I <sub>B</sub>	I <sub>C</sub>	I <sub>N</sub>	Iį			х	Х	_	1
Min/Max	Time-stamping		and time	of min/	may rec	ord						
	Previous value		ax value		max roc	ora			X X	Х	_	1
Maintenance Indicato			iast variat	<u> </u>						<u> </u>	-	
	Mechanical cycles <sup>2</sup>	Assig	nable to	an alar	m				T			
	Electrical cycles <sup>2</sup>	Assignable to an alarm Assignable to an alarm										
Counter	Trips	"	One per type of trip			x x	Х	_	1			
	Alarms	1	One for each type of alarm									
	Hours	Total operating time (hours)										
In all and an	0	0/			Х	Х		1				
Indicator	Contact wear %		6			Х	Х					
Lood profile	Llaura at different la al laura	% of h	% of hours in four current ranges: 0–49% I <sub>n</sub> ,		Х	Х		1				
Load profile	Hours at different load levels		50–79% I <sub>n</sub> , 80–89% I <sub>n</sub> and ≥ 90% I <sub>n</sub>			Х	Х		[ '			

<sup>&</sup>lt;sup>1</sup> Available through the communication network only.

<sup>&</sup>lt;sup>2</sup> The BSCM (page 82) is required for these functions.

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Units

#### Additional technical characteristics:

Contact wear

Each time PowerPact H-, J-, and L-frame circuit breakers open, the Micrologic 5 / 6 trip unit measures the interrupted current and increments the contact-wear indicator as a function of the interrupted current, according to test results stored in memory. Breaking under normal load conditions results in a very slight increment. The indicator value may be read on the front display module. It provides an estimation of contact wear calculated on the basis of the cumulative forces affecting the circuit breaker. When the indicator reaches 80%, it is advised to replace the circuit breaker to ensure the availability of the protected equipment.

Circuit breaker load profile

Micrologic 5 / 6 trip units calculate the load profile of the circuit breaker protecting a load circuit. The profile indicates the percentage of the total operating time at four current levels (% of I<sub>n</sub>):

- 0 to 49%  $I_n$
- 50 to 79%  $I_n$
- 80 to 89%  $I_n$
- ≥ 90%  $I_n$ .
- This information can be used to optimize use of the protected devices or to plan ahead for expansion.

## **Motor Circuit Protectors (AC Only)**

See Section 5 for information about PowerPact H-, J- and L-frame electronic motor circuit protectors (MCP) with trip units:

- Micrologic 1.3 M
- Micrologic 2 M



01/2014

## Section 7—Accessories for Micrologic™ Trip Units

## **Display Options**

## Front Display Module Functions (FDM121) (Micrologic 5 / 6 A or E Trip Units Only)

The front display module (FDM121) can be integrated in the PowerPact™ H-, J-, and L-frame circuit breaker system. It uses the sensors and processing capacity of the Micrologic trip unit to display measurements, demand, power quality and maximum/minimum values along with alarms, histories, and maintenance indicators.

It is easy to use and requires no special software or settings and is immediately operational when connected to the PowerPact H-, J-, and L-frame circuit breakers by a simple cable.

The FDM121 is a large display, but requires very little depth. The anti-glare graphic display screen is backlit for easy reading even under poor ambient lighting and at sharp angles.



∴ Metering

A Alarms

Services

FDM121 Display

## Table 65: Characteristics

	Size	96 x 96 x 30 mm	
	Installation	Requires 10 mm behind the door (or 20 mm when the 24 Vdc power supply connector is used).	
Screen	Backlighting	White	
	Viewing Angle	Vertical ±60°, horizontal ±30°	
	Resolution	High: excellent reading of graphic symbols.	
Alarm LED	Flashing orange	Alarm pick-up	
Alami LED	Steady orange after operator reset	Alarm condition persists.	
Operating temperature	14°F to 131°F (-10 °C to +55 °C).	°C).	
Certifications	UL, CSA, CE		
24 Vdc power supply	Tolerances 24 V -20% +10% (19.2 V to 26.4 V)	When the FDM121 is connected to the communication network, the 24 Vdc is supplied by the communication network wiring.	
Power Requirements	40 mA, 24 Vdc		
Mounting	Standard door cut-out 92 x 92 mm. Attached using clips.	To avoid a cut-out in the door, a surface-mount accessory is available for surface mounting by drilling two 22 mm diameter holes.	
Degree of protection	NEMA12 / IP54 in front.	NEMA12 / IP54 is maintained after mounting by using the supplied gasket during installation.	



Surface Mount Accessory

#### Mounting

The FDM121 is easily installed in equipment.

- Standard door cut-out 3.62 x 3.62 in. (92 x 92 mm).
- Attached using clips.

To avoid a cut-out in the door, an accessory is available for surface mounting by drilling only two 0.87 in. (22 mm) diameter holes.

The FDM121 degree of protection is NEMA12 / IP54 in front. NEMA12 / IP54 is maintained after mounting by using the supplied gasket during installation.



#### Display of Micrologic Trip Unit Measurements and Alarms

The FDM121 is intended to display Micrologic 5 / 6 trip unit measurements, alarms and operating information. It cannot be used to modify the protection settings. Measurements may be easily accessed through a menu.

All user-defined alarms are automatically displayed. The display mode depends on the priority level selected during alarm set-up:

- high priority: a pop-up window displays the time-stamped description of the alarm and the orange LED flashes
- medium priority: the orange Alarm LED goes steady on I
- low priority: no display on the screen.

All faults resulting in a trip automatically produce a high-priority alarm, without any special settings required. In all cases, the alarm history is updated.

If power to the FDM121 fails, all information is stored in the Micrologic trip unit non-volatile memory. The data can be consulted using the communication network when power is restored.

#### Status Indications and Remote Control

When the circuit breaker is equipped with the BSCM module (page 82), the FDM121 display can also be used to view circuit breaker status conditions:

- Auxiliary switch (OF): ON/OFF
- Alarm switch (SD): trip indication
- Overcurrent trip switch (SDE): fault-trip indication (overload, short-circuit, ground fault)

#### **Electrical Connection**

The FDM121 is equipped with:

- a 24 Vdc terminal block:
  - plug-in type with 2 wire inputs per point for easy daisy-chaining
  - power supply range of 24 V -20% (19.2 V) to 24 V +10% (26.4 V)
- · two RJ45 jacks.

The Micrologic trip unit connects to the internal communication network terminal block on the PowerPact H-, J-, and L-frame circuit breakers using the pre-wired NSX cord. Connection to one of the RJ45 connectors on the FDM121 automatically establishes communication between the Micrologic trip unit and the FDM121 and supplies power to the Micrologic trip unit measurement functions.

When the second connector is not used, it must be fitted with a line terminator TRV00880.

#### **Navigation**

Five buttons are used for intuitive and fast navigation.

The "Context" button may be used to select the type of display (digital [text], bargraph, analog).


The user can select the display language (Chinese, English, French, German, Italian, Portuguese, Spanish, etc.) Other languages can be downloaded.

#### Screens

Main menu

When powered up, the FDM121 screen automatically displays the ON/OFF status of the device.

When not in use, the screen is not backlit. Backlighting can be activated by pressing one of the buttons. It goes off after three minutes.



Orange LED \


Main menu

Quick view

C Services









#### Fast access to essential information:


• "Quick view" provides access to five screens that display a summary of essential operating information (I, V, f, P, E, THD, circuit breaker On / Off).

#### Access to detailed information

- "Metering" can be used to display the measurement data (I, U-V, f, P, Q, S, E, THD, PF) with the corresponding min/max values.
- · Alarms displays active alarms and the alarm history
- Services provides access to the operation counters, energy and maximum reset function, maintenance indicators, identification of modules connected to the internal bus and FDM121 internal settings (language, contrast, etc.)







Quick View

Metering Sub-Menu

Services

#### **Catalog Numbers**

**Table 66:** Front Display Module Catalog Numbers


Description	Catalog No.
FDM121	STRV00121
FDM121 Mounting Accessory	TRV00128

## **Circuit Breaker Communication Network Options**

All PowerPact H-, J-, and L-frame circuit breakers devices can be equipped with the communication function using a pre-wired connection system and a Modbus<sup>™</sup> communication interface module. The interface module can be connected directly or through the front display module (FDM121).

The PowerPact H-, J-, and L-frame circuit breakers can be integrated in a Modbus communication network. Four functional levels can be used separately or combined to adapt to all supervision requirements.

Level	Function		
Communication of status indications	Compatible with PowerPact H-, J- and L-frame circuit breakers and automatic switches. Use the BSCM module to access the following information:		
Communication or status indications	<ul> <li>ON/OFF position</li> <li>trip indication</li> <li>fault-trip indication</li> </ul>		
	Available on all circuit breakers and automatic switches with communicating motor operators, the remote control can be used to:		
Communication of commands	<ul><li>open</li><li>closed</li><li>reset</li></ul>		
	This level provides access to:		
Communication of measurements with Micrologic 5 / 6 A or E trip unit	<ul> <li>instantaneous and demand values</li> <li>maximums/minimums</li> <li>energy metering</li> <li>demand current and power</li> <li>power quality</li> </ul>		
	This level also provides access to:		
Communication of operating assistance with Micrologic 5 / 6 A or E trip unit	<ul> <li>protection and alarm settings</li> <li>time-stamped histories and event tables</li> <li>maintenance indicators</li> </ul>		




PowerPact H-, J-, or L-frame circuit breaker is connected to the Modbus communication interface module (IFM) or front display module (FDM121) through the internal terminal block for the NSX cord.

The front display module is connected to the Modbus communication interface module by a communication cable with RJ45 connectors on both ends.

- 1. Modbus network
- 2. Modbus communication interface module
- 3. NSX cord
- Internal terminal block for communication using the NSX cord
- 5. BSCM module
- 6. Prefabricated wiring
- 7. Micrologic trip unit
- 8. FDM121 display
- 9. RJ45 cable
- 10. Line terminator (for unused connectors, if applicable)

01/2014

## **Modbus Communication Interface Module (IFM)**



- Five-point Modbus and 24 Vdc connector
- 2. Two Modbus address rotary switches (1 to 99)
- 3. Modbus traffic LED
- Lock-out to disable writing to the trip unit
- 5. Test LED
- 6. Test button
- Two connectors for RJ45 cable

#### **Functions**


This module, required for connection to the network, contains the Modbus address (1 to 99) declared by the user using the two rotary switches in front. It automatically adapts (baud rate, parity) to the Modbus network in which it is installed.


It is equipped with a lock-out switch to enable or disable operations involving writing to Micrologic trip unit, (such as reset, counter reset, setting modifications, device opening and closing commands).

There is a built-in test function to check the connections of the Modbus communication interface module with the Micrologic trip unit and front display module.

#### Mounting

The module is mounted on a DIN rail. A number of modules may be clipped one next to the other. For this, a stacking accessory (shown below) is available for fast clip-connection of both the Modbus link and the 24 Vdc supply.





The Modbus communication interface module supplies 24 Vdc to the corresponding Micrologic trip unit, front display module, and BSCM module. Module power requirements is 60 mA / 24 Vdc.

#### **Catalog Numbers**

Table 67: IFM Catalog Numbers

Description	Catalog No.
Modbus Communication Interface Module (IFM)	STRV00210
Stacking Connectors for IFM (10)	TRV00217

## **Isolated Modus Repeater Module**

Since Modbus interface modules (part number STRV00210) are not isolated, an isolated Modbus Repeater Module needs to be inserted between the Modbus network inside the equipment and the Modbus network outside the equipment.

Table 68: Catalog Number

Description	Catalog No.
Isolated Modbus Repeater Module	STRV00211



## PowerPact™ H-, J-, and L-Frame Circuit Breakers Accessories for Micrologic™ Trip Units

### **NSX Cord**

Micrologic trip units are connected to the Modbus communication interface module (IFM) or front display module through the internal terminal block for the NSX cord equipped with an RJ45 connector.

The NSX cord is available in two cable lengths:


- 4.27 ft (1.3 m)
- 9.84 ft (3 m)

Lengths up to 32.8 ft (10 m) are possible using extensions.


- For voltage V ≤ 480 V, available in 3 prefabricated lengths: 0.35 m, 1.3 m and 3 m.
- For voltages V > 480 V, a special 1.3 m cable with an insulation accessory is required.
- A set of cables with RJ45 connectors is available to adapt to different distances between devices.

Table 69: **NSX Cord Catalog Numbers** 

Description	Catalog No.
NSX Cord 4.27 ft (1.3 m), V ≤ 480 V	S434201
NSX Cord 9.84 ft (3 m), V ≤ 480 V	S434202
NSX Cord 4.27 ft (1.3 m), V > 480 V	S434204
NSX Cord 9.84 ft (3 m), V > 480 V	S434303



Lenath



with V > 480 V

## **Breaker Status and Control Module (BSCM)**

#### **Functions**

The optional BSCM Breaker Status & Control Module is used to acquire device status indications and control the communicating remote-control function. It includes a memory used to manage the maintenance indicators.

#### Status indications

Indication of device status:

Auxiliary switch (OF), alarm switch (SD), and overcurrent trip switch (SDE).

#### **Maintenance indicators**

The BSCM manages the following indicators:

- mechanical operation counter
- electrical operation counter
- history of status indications.

It is possible to assign an alarm to the operation counters.

#### **Controls**

The BSCM can be used to carry out communicating remote control operations using the communicating motor operator (open, close and reset) in different modes (manual, auto).

The BSCM can be installed on all PowerPact H-, J-, and L-frame circuit breakers and automatic switches with Micrologic trip units. It simply clips into the auxiliary contact slots. It occupies the slots of one auxiliary switch (OF) and one overcurrent trip switch (SDE). The BSCM is supplied with 24 Vdc power automatically through the NSX cord when the communication network is installed.




01/2014

### **Catalog Numbers**

Table 70: BSCM Catalog Numbers

Description	Catalog No.
Replacement BSCM	S434205
BSCM with NSX Cord 1.3 m, V ≤ 480 V	S434201BS
BSCM with NSX Cord 3 m, V ≤ 480 V	S434202BS
BSCM with NSX Cord 1.3 m, V > 480 V	S434204BS
BSCM with NSX Cord 3 m, V > 480 V	S434303BS

## 24 Vdc Power-Supply Terminal Block



24 Vdc Terminal Block

The Micrologic 5/6 trip unit display is operational when current is flowing through the circuit breaker. To power the Micrologic 5/6 trip unit when the trip unit is not connected to an FDM121 or to the communication network, a 24 Vdc power-supply terminal block can be installed only on Micrologic 5/6 trip units. When used, it excludes connection of an NSX cord.

Table 71: 24 Vdc Catalog Number

Description	Catalog No.
24 Vdc Terminal Block Unit Mount	S434210

## **External 24 Vdc Power-Supply Module**

An external 24 Vdc power supply is required for installation in a communication network, whatever the type of trip unit.

On installations without a communication network, the power supply is available as an option for Micrologic 5/6 trip units in order to:

- modify settings when the circuit breaker is open
- display measurements when the current flowing through the circuit breaker is low (15 to 50 A depending on the rating)
- maintain the display of the cause of tripping and interrupted current.


A single external 24 Vdc supply may be used for the entire network, depending on the number of devices in the communication network. The required characteristics are:

- output voltage: 24 Vdc ± 5%
- ripple: ± 1%

Table 72: Available External Power-Supply Modules (1 A)

Available External Power-Supply Modules		Input Voltage	Output Power	Cat. No.
Power supply		24–30		685823
	Vdc (±5%)	48–60		685824
		100–125	5 VA/5W	685825
	Vac (+10%, -15%)	110–130	5 VA/5VV	685826
		200–240		685827
		380-415		685829

To determine the required output current of the 24 Vdc power supply, it is necessary to sum up the currents consumed by the different loads supplied.



External 24 Vdc Power-Supply Module

**Table 73:** Power Requirements

Module	Typical Consumption 24 Vdc @ 68°F (20°C)	Maximum Consumption 19.2 Vdc @ 140°F (60°C)	
Micrologic 5/6 trip units	30 mA	55 mA	
BSCM	9 mA	15 mA	
FDM121	21 mA	30 mA	
IFM	21 mA	30 mA	
Isolated Modbus Repeater Module	15 mA	19 mA	

For installation recommendations, see page page 136



**Battery Module** 

## **Battery Module**

The battery module is a back-up supply for the external power-supply module. The input/output voltages are 24 Vdc and it can supply power for approximately three hours (100 mA).

Table 74: Battery Module

Description	Catalog No.
Battery Module	685831

## **Pocket Tester**



Pocket Tester

The pocket tester connects to the Micrologic trip unit test connector. It powers up the Micrologic trip unit and the Ready LED. It supplies the screen, allows settings to be made using the keypad, and provides thermal imaging inhibit functions.


Table 75: Pocket Tester

Description	Catalog No.
Pocket Tester	S434206

The pocket tester runs off of two Alkaline AA batteries.

## **UST Test Adapter (UTA) Tester for Test and Maintenance**





- power supply (110–220 Vac / 50-60 Hz 24 Vdc 1 A)
- special Micrologic cable for connection to the trip-unit test connector
- standard USB cable
- standard RJ45 cable
- user manual

**UTA Tester Module** 

Table 76: UTA Tester Catalog Numbers

Description	Catalog No.
UTA Tester (complete)	STRV00910
Spare 110-240 V power supply	TRV00915
Spare Micrologic cable	TRV00917
Spare UTA Tester Module	STRV00911
Bluetooth/Modbus Option for UTA Tester	TCSWAAC13FB


Included in the UTA Tester, the UTA Tester module tests Micrologic trip unit operation and provides access to all parameters and settings. It connects to the Micrologic trip unit test connector and can operate in two modes.

- Stand-alone mode to:
  - supply the Micrologic trip unit with power and check operation using the Ready LED
  - Provides ground-fault inhibit and thermal memory inhibit
- PC mode, connected to a PC with a USB or Bluetooth link. This mode provides access to
  protection settings, alarm settings and readings of all indicators. Using the associated RSU
  software utility, it is possible to store, in a dedicated file for each device, all the data that can
  transferred to another device.

This mode also offers operating-test functions:

- check on trip time delay (trip curve)
- check on non-tripping time (coordination)
- check on ZSI (Zone Selective Interlocking) function
- alarm simulation
- display of setting curves
- display of currents
- printing of test reports
- optional Bluetooth link (to PC).





## **Universal Logic Plug System**



The Universal Logic Plug (ULP) system allows the PowerPact H-, J- and L-frame circuit breakers to become metering and supervision tools to assist for energy efficiency. For easy connection of the different modules, the prefabricated cables are identified by a ULP symbol. The connection points on compatible modules are marked in the same manner.

Table 77: ULP Accessories Catalog Numbers

Description	Qty	Catalog No.
RJ45 connectors, female/female	10	TRV00870
ULP Line termination	10	TRV00880
RJ45/RJ45 male cord L= 0.3 m	10	TRV00803
RJ45/RJ45 male cord L= 0.6 m	10	TRV00806
RJ45/RJ45 male cord L = 1 m	5	TRV00810
RJ45/RJ45 male cord L = 2 m	5	TRV00820
RJ45/RJ45 male cord L = 3 m	5	TRV00830
RJ45/RJ45 male cord L = 5 m	1	TRV00850
Modbus Line Terminations	2	VW3A8306DRC

For more information about the ULP System, see page 136 or bulletin 48940-329-01, *ULP (Universal Logic Plug) Connection System—User Guide.* 

### **Circuit Breaker Communication Networks and Software**


### Modbus™ Communication Network

Modbus is the most widely used communication protocol in industrial networks. It operates in masterslave mode. The devices (slaves) communicate one after the other with a gateway (master).

Masterpact™ and PowerPact™ circuit breakers with Micrologic trip units, PowerLogic™ and Sepam™ products all operate with this protocol. A Modbus network is generally implemented on an LV or MV system. Micrologic trip units use the Modbus communication protocol, compatible with ION-Enterprise PowerLogic supervision systems.

Depending on the data monitored and the desired refresh rate, a Modbus network connected to a gateway can serve 4 to 16 devices. For larger installations, a number of Modbus networks can be connected to an Ethernet® network (TCP/IP/Modbus protocol) through their gateways.

The downloadable RSUsoftware application facilitates implementation of communication network functions.



## **Supervision Software**

Schneider Electric<sup>™</sup> electrical installation supervision, management and expert system software integrates PowerPact H-, J-, and L-frame electronic circuit breakers identification modules.

#### **Types of Software**

Micrologic trip unit communication network functions are designed to interface with software dedicated to electrical installations:

- installation supervision
- · electrical installation supervision
- power system management: electrical engineering expert systems
- process control
- SCADA (Supervisory Control & Data Acquisition), EMS (Enterprise Management System) or BMS (Building Management System) type software.

## Remote Setting Utility (RSU)

The downloadable Micrologic Trip Unit Utility, RSU, facilitates the implementation of communication network functions.

- The RSU is available to assist in starting up a communicating installation. The software can be downloaded from the Schneider Electric internet site.
- The "Live update" function enables immediate updating to obtain the most recent upgrades. These
  easy-to-use utilities include starting assistance and online help. They are compatible with Microsoft
  Windows 2000, XP, Vista and Windows 7.



RSU mini-supervision screen for current measurements.

The RSU can be used to set the protection functions and alarms for each Masterpact™ and PowerPact device.

After connection to the network and entry of the circuit-breaker Modbus address, the software automatically detects the type of trip unit installed.

There are two possible operating modes. For each selected circuit breaker, the user can do the following.

Operating Mode	Operation	Description		
Off-Line with the Software Disconnected from the	Determine the protection settings	The settings are carried out on a screen that shows the front of the trip unit. The Micrologic trip unit setting rotary switches, keypad and screen are simulated for easy use of all Micrologic trip unit setting functions.		
Communication Network	Save and duplicate the protection settings	Each configuration created can be saved for subsequent device programming. It can also be duplicated and used as the basis for programming another circuit breaker.		
	Display the current settings The software displays the trip unit and provides access to all settings.	The software displays the trip unit and provides access to all settings.		
	View the corresponding protection curves	A graphic curve module in the software displays the protection curve corresponding to the settings.		
On-Line with the Software Connected to the Network	Display the current settings Modify settings in a secure manner	There are different levels of security:  — password: by default, it is the same for all devices, but can be differentiated for each device  — locking of the Modbus communication interface module which must be unlocked before the corresponding device can be set remotely  — maximum settings limited by the positions of the two rotary switches on the trip unit. These rotary switches, set by the user, determine the maximum settings that can be made using the communication network.  Settings are modified by:  — either direct, on-line setting of the protection settings on the screen		
		or by loading the settings prepared in off-line mode. This is possible only if the positions of the rotary switches allow the new settings.  All manual settings made subsequently on the device have priority.		
		Up to 12 alarms can be linked to measurements or events.		
	Program alarms	two alarms are predefined and activated automatically:  — Micrologic 5 trip unit: overload $(I_r)$ — Micrologic 6 trip unit: overload $(I_r)$ and ground fault $(I_g)$		
		thresholds, priorities and time delays can be set for 10 other alarms. They may be selected from a list of 91 alarms		
	Set the outputs of the SDx relays	This is required when the user wants to change the standard configuration and assign different signals to the 2 outputs of the SDx relay.		

To download the RSU software (LV4ST100):

- go to www.schneider-electric.com and do a search for LV4ST100.
- Click on LV4ST100, then click Software/Firmware under Downloads menu, then download.

#### Gateway

The gateway has two functions:

- access to the company intranet (Ethernet) by converting Modbus frames to the TCP/IP/Modbus protocol
- optional web page server for the information from the devices.


Examples include EGX300 and EGX100.



### Integration of PowerPact H-, J-, and L-frame Circuit Breakers

Micrologic trip unit communication network functions are designed to interface with software dedicated to electrical installations. PowerPact H-, J-, and L-frame circuit breakers are integrated using Modbus communication interface modules connected through FDM121 front display modules or NSX cords.

For easy connection of the different modules, the prefabricated cables are identified by ULP (Universal Logic Plug) symbols. The connection points on compatible modules are marked in the same manner.



### Schneider Electric™ Solutions

#### Electrical Equipment Supervision using Gateways such as the EGX300 Web Servers

- A simple solution for customers who want to consult the main electrical parameters of installed devices without dedicated software.
- Up to 16 devices are connected using Modbus communication interface modules to an MPS100 or EGX300 Ethernet gateway integrating the functions of a web page server. The embedded Web pages can be easily configured with just a few mouse clicks. The information they provide is updated in real time.
- The Web pages can be consulted using a standard Web browser on a PC connected through Ethernet to the company Intranet or remotely using a modem. Automatic notification of alarms and threshold overruns is possible using e-mail or SMS (Short Message Service).

#### **SMS Electrical Engineering Expert System Software**

PowerLogic™ SMS is a family of web-enabled software products for high-end power-monitoring applications. It is designed for large power systems.


SMS products offer detailed analysis of electrical events, long-duration data logging and extensive, economical report-building capabilities (such as power usage monitoring and tariff management).

A wide variety of screens can be displayed in real time, including more than 50 tables, analogue meters, bargraphs, alarms logs with links to display waveforms and predefined reports on energy quality and service costs.

01/2014

#### **Electrical Installation Supervision using ION-Enterprise Software**

- PowerLogic<sup>™</sup> ION-Enterprise software is ideally suited to the supervision needs of small system
  applications, monitoring up to 32 devices.
- Installed on a PC under Windows, it represents a cost-effective and easy-to-implement powermonitoring solution that offers:
  - automatic detection of compatible devices
  - real-time monitoring of data including power requirements
  - a report generator with a number of pre-defined reports that can be exported to
  - Excel
  - cost allocation
  - time-stamped data-logging possibilities
  - Modbus serial and Modbus TCP/IP compatible communication.



### Other Software

PowerPact H-, J-, and L-frame devices can forward their measurement and operating information to special software integrating the electrical installation and other technical facilities:

- SCADA process control software: Vijeo CITECT
- · BMS Building Management System software: Vista.

For more information, contact your local field office.

## **External Neutral Current Transformer (ENCT)**

The external neutral current transformer is a sensor required for a three-pole circuit breaker in a system with a distributed neutral to measure the neutral current in order to:

- protect the neutral conductor
- · protect against ground faults.

This current transformer can be connected to Micrologic 5 / 6 trip units. The transformer rating must be compatible with that of the circuit breaker.



Circuit Breaker	Rating	Catalog No.
H-Frame	60-100 A	S429521
n-rrame	150 A	S430562
J-Frame	250 A	S430563
L-Frame	400–600 A	S432575

For installation recommendations, see page 135.



External neutral current transformer


# External Neutral Voltage Tap

## **External Neutral Voltage Tap (ENVT)**

The external neutral voltage tap is required for Micrologic E power metering with a three-pole circuit breaker in a system with a distributed neutral. It is used to connect the neutral to the Micrologic trip unit to measure phase-to-neutral (Ph-N) voltages.

The ENVT is included with the Micrologic 5/6 electronic trip unit.

## Zone Selective Interlock (ZSI) Module



A ZSI terminal block may be used to interconnect a number of Micrologic trip units to provide zone selective interlocking for short-time ( $I_{sd}$ ) and ground-fault ( $I_{g}$ ) protection, without a time delay. For PowerPact H- and J-frame circuit breakers, the ZSI function is available only in relation to the upstream circuit breaker (ZSI out). For PowerPact L-frame circuit breakers, the ZSI function is available in relation to the upstream circuit breaker (ZSI out) and downstream circuit breakers (ZSI in)

Table 79: ZSI Catalog Number

Description	Catalog No.
ZSI Module	S434212

### I-Line™ Wiring Harness

Accessories installed in I-Line circuit breakers require the use of optional wiring harnesses (not provided). The wiring harness allows the accessory wiring to exit the circuit breaker through wiring channels in the side of the circuit breakers. Wire harnesses may also be used for unit-mount applications.




Table 80: Wiring Harness Catalog Numbers

Description	Catalog No.
Auxiliary Switch (OF) I-Line Wire Harness	S434500
Alarm Switch (SD)/Overcurrent Trip Switch (SDE) I-Line Wire Harness	S434501
SDx/SDTAM I-Line Wire Harness	S434502
Undervoltage Trip (MN) I-Line Wire Harness	S434503
Shunt Trip (MX) I-Line Wire Harness	S434504
24 Vdc Power Supply Terminal Block I-Line Wire Harness	S434505
Motor Operator (MT) I-Line Wire Harness	S434506
Communicating Motor Operator (MTc) I-Line Wire Harness	S434507
NSX Cord I-Line Wire Harness	S434508
ZSI (H/J-Frame, Out Only) I-Line Wire Harness	S434300
ZSI (L-Frame, In and Out) I-Line Wire Harness	S434301
ENCT I-Line Wire Harness	S434302

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

## Section 8—Accessories and Auxiliaries

All PowerPact<sup>TM</sup> H-, J-, and L-frame circuit breakers and automatic switches have slots for the electrical auxiliaries

#### H- and J-Frame

- 4 indication contacts
  - 2 ON/OFF (auxiliary switches [OF1 and OF2])
  - 1 trip indication (alarm switch [SD])
  - 1 fault-trip indication (overcurrent trip switch [SDE])
- one remote-tripping release
  - either 1 undervoltage trip (MN)
  - or 1 shunt trip (MX)

#### L-Frame

- 5 indication contacts
  - 3 ON/OFF auxiliary switches (OF1, OF2, and OF3)
  - 1 trip indication (alarm switch [SD])
  - 1 fault-trip indication (overcurrent trip switch [SDE])
- one remote-tripping release
  - either 1 undervoltage trip (MN)
  - or 1 shunt trip (MX)

Circuit breakers equipped with Micrologic<sup>™</sup> trip units may be equipped with a fault-trip indication to identify the type of fault by installing

- one indication module with two outputs (see page 98)
  - either an SDx module with Micrologic 3.x / 5.x A or E / 6.x A or E
  - or an SDTAM module with Micrologic 2.x M.

This module occupies the slots of one auxiliary switch (OF) contact and an undervoltage trip (MN)/shunt trip (MX).

All these auxiliaries may be installed with a motor operator.

### **Communication Network**

Communication networks require specific auxiliaries.

Communication of status indications

- 1 BSCM module
- 1 NSX cord (internal terminal block) for both communication and 24 Vdc supply to the BSCM.

Communication of status conditions is compatible with a standard motor operator.

Communication of status indications and controls requires, in addition to the previous auxiliaries:

1 communicating motor operator connected to the BSCM.

Communication of measurements is available on Micrologic 5 / 6. The system consists of:

1 NSX cord (internal terminal block) for both communication and 24 Vdc supply to the Micrologic.

Communication of measurements is compatible with a standard or communicating motor operator.


Communication of status indications, controls and measurements is available on Micrologic 5 / 6. The system consists of:

- 1 BSCM module
- 1 NSX cord (internal terminal block) for both communication and 24 Vdc supply to the BSCM and the Micrologic
- 1 communicating motor operator connected to the BSCM.

Installation of SDx or SDTAM is compatible with communication network.



Table 81: Standard Auxiliary Possibilities Based on Trip Unit



## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

Table 82: Communication Network Auxiliary Possibilities Based on Trip Unit

Туре	Trip Unit	Auxiliary Possibilities		
H-Frame J-Frame	Micrologic 3	Communication of status indications and controls  Communicating Motor Operator  NSX Cord  BSCM		
H-Frame J-Frame	Micrologic 5 Micrologic 6	Communication of measurements with or without FDM121 display  Motor Operator  Or NSX Cord		
L-Frame	Micrologic 1.3 M Micrologic 3	Communication of status indications and controls  Communicating Motor Operator  NSX Cord  BSCM  BSCM		
L-Frame	Micrologic 5 Micrologic 6	Communication of status indications  Communication of status indications, controls and measurements with or without FDM121 display  Communicating Motor Operator  NSX Cord  NSX Cord  BSCM		

## **Accessory Connections**

Electrical accessories are fitted with numbered terminal blocks for wires with the following maximum size:

- 16 AWG (1.5 mm<sup>2</sup>) for auxiliary switches (OF1 or OF2), and shunt trip (MX) or undervoltage trip (MN)
- 14 AWG (2.5 mm<sup>2</sup>) for the motor operator

Auxiliary switch wiring exits fixed mounted devices through a knock-out in the front cover.

NOTE: See page 119 for plug-in and page 121 for drawout options.

## **Auxiliary and Alarm Indication Contacts**

Auxiliary indication contacts provide remote information of the circuit breaker status and can thus be used for indications, electrical locking, relays, etc.

#### Table 83: Auxiliary and Alarm Indication Contacts



Overcurrent Trip

Switch Actuator (SDE)

Auxiliary Switch (OF)/ Alarm Switch (SD)

### Open/Closed—Auxiliary Switches (OF)

· Indicates the position of the circuit breaker contacts

#### Trip Indication—Alarm Switch (SD)

- Indicates that the circuit breaker has tripped due to an overload, short circuit or ground fault, the operation of a shunt trip or undervoltage trip or the "push-to-trip" button
- Resets when the circuit breaker is reset

#### **Applications**

#### Overcurrent Trip Switch (SDE)

- · Indicates that the circuit breaker has tripped due to an overload, short circuit or ground fault
- Resets when the circuit breaker is reset

The above switches are also available in low-level versions (with gold flash plating) capable of switching very low loads (e.g., for controlling PLCs or electronic circuits)

#### Rotary Handle Indicator: CAO (early-break) and CAF (early-make)

Fitted in the rotary handle module (see page 106)

## Installation & Connection

- The auxiliary switch (OF), alarm switch (SD), and overcurrent trip switch (SDE) indication contacts snap into cavities behind the front accessory cover of the circuit breaker.
- One model serves for all indication functions depending on where it is fitted in the circuit breaker.
   The overcurrent trip switch (SDE) in a circuit breaker equipped with a thermal-magnetic or Micrologic 1/2/3 trip unit requires the SDE actuator.

## Standards

- The internal accessories comply with requirements of Underwriters Laboratories<sup>®</sup> Inc. (UL<sup>®</sup>).
- UL 489 and Canadian Standard Association C22.2 No. 5-02 Standards.
- All internal accessories are Listed for field installation per UL file E103955 and Certified under CSA file LR 69561. Auxiliary indicator contacts comply with UL 489, CSA C22.2 No. 5-02 and IEC 60947-5 Standards. "Low-level" indicator contacts are not UL Recognized.

#### Table 84: Electrical Characteristics

Characteristic	Standard		Low-Level	Low-Level <sup>1</sup>	
Supplied as Standard (Form C)	4		4	4	
Maximum Number of Contacts	4		4	4	
Rated Thermal Current	6 A		5 A	5 A	
Minimum Load	100 mA at 24 V 1 mA at 4 V				
Operational Current	AC	DC	AC	DC	
24 V	6 A	6 A	5 A	5 A	
48 V	6 A	2.5 A	5 A	2.5 A	
110 V	6 A	0.6 A	5 A	0.6	
220/240 V	6 A	_	5 A	_	
250 V	_	0.6 A	5 A	0.3 A	
380/440 V	6 A	_	5 A	_	
480 V	6 A	<u> </u>	5 A	_	
660/690 V	6 A	_	_	_	

<sup>1</sup> If the maximum voltage and current is exceeded, the low-level function of the switch will be lost but the switch will continue to function as a standard switch.



## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

Table 85: Auxiliary Switch Catalog Numbers

Contacts	Factory-Installed Suffix	Field-Installable Kit No.	Kit Qty.
1A/1B Standard	AA	S29450	1
2A/2B Standard	AB	S29450	2
1A/1B Low-Level (Gold)	AE	S29452	1
2A/2B Low-Level (Gold)	AF	S29452	2

Table 86: Alarm/Overcurrent Trip Switch Catalog Numbers

Suffix	Switch	Kit No.	Kit Qty.
PowerPac PowerPac	t L-Frame tt H/J-Frame with Micrologic 5/6 trip units		
ВС	Alarm Switch	S29450	1
ВН	Alarm Switch Low-Level	S29452	1
BD	Overcurrent Trip Switch Standard	S29450	1
BJ	Overcurrent Trip Switch Low-Level	S29452	1
BE	Alarm Switch and Overcurrent Trip Switch, Standard	S29450	2
BK	Alarm Switch and Overcurrent Trip Switch, Low-Level	S29452	2
	t H/J-Frame with Thermal-Magnetic or 1/2/3 trip units		
ВС	Alarm Switch	S29450	1
ВН	Alarm Switch, Low-Level	S29452	1
BD	Overcurrent Trip Switch, Standard SDE Actuator	S29450 S29451	1 1
BJ Overcurrent Trip Switch, Low-Level SDE Actuator		S29452 S29451	1 1
BE	Alarm Switch and Overcurrent Trip Switch, Standard SDE Actuators	S29450 S29451	2 2
ВК	Alarm Switch and Overcurrent Trip Switch, Low-Level SDE Actuators	S29452 S29451	2 2

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

## **SDx and SDTAM Modules for Micrologic**

SDx and SDTAM are relay modules with two outputs. They send different signals depending on the type of fault. They may not be used together.

#### SDx Module

The SDx module remotely monitors the trip or alarm conditions of PowerPact H-, J-, and L-frame circuit breakers equipped with electronic protection.

An SDx relay module installed inside the circuit breaker can be used to remote the overload trip signal.

This module receives the signal from the Micrologic electronic trip unit through an optical link and makes it available on the terminal block. The signal is cleared when the circuit breaker is closed. These outputs can be reprogrammed to be assigned to other types of tripping or alarm (see page 98).

The SDx module may be used in 400 Hz systems for voltages from 24 to 440V.

The SD2 output, available on all Micrologic trip units, corresponds to the overload-trip indication.

The SD4 output, available on Micrologic 5 / 6, is assigned to:

- overload pre-alarm (Micrologic 5)
- ground-fault trip indication (Micrologic 6)

These two outputs automatically reset when the device is closed (turned ON).

For Micrologic 5 / 6, the SD2 and SD4 outputs can be reprogrammed to be assigned to other types of tripping or alarm.

It is possible to assign a function output characteristics:

- latching with a time delay. Return to the initial state occurs at the end of the time delay
- permanent latching. Return to the initial state takes place through the communication function.

Static outputs: 24-415 V AC / Vdc; 80 mA max.

#### **SDTAM Module**

The SDTAM module, linked to the contactor controller, opens the contactor when an overload or other motor fault occurs, thus avoiding opening of the circuit breaker. The SDTAM module is specifically for the motor-protection Micrologic trip units 2 M (2.2 M and 2.3 M).

#### Micrologic 2 M

The SD4 output opens the contactor 400 ms before normal circuit-breaker opening in the following cases:

- · overload (long-time protection for the trip class)
- phase unbalance or phase loss

The SD2 output serves to memorize contactor opening by SDTAM.

#### **Output characteristics**

Output reset can be:

- manual by a pushbutton included in the wiring diagram
- automatic after an adjustable time delay (1 to 15 minutes) to take into account the motor-cooling time


Static outputs: 24-415 Vac / Vdc; 80 mA max. a (+) 24-415 V.



SDx module with terminal block.



## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Accessories and Auxiliaries**



Schematic of the communicating motor operator .


Table 87: **SDx and SDTAM Catalog Numbers** 

Contacts	Factory-Installed Suffix	Field-Installable Kit No.
SDx	V	S429532
SDTAM (motor trip units only)	V	S429424

01/2014

## **Shunt Trip (MX) and Undervoltage Trip (MN)**

A voltage release can be used to trip the circuit breaker using a control signal.





	Shunt Trip (MX)
	<ul> <li>Trips the circuit breaker when the control voltage rises above 70% of its rated voltage</li> <li>Impulse type ≥ 20 ms or maintained control signals</li> <li>AC shunt trips are suitable for ground-fault protection when combined with a Class I ground-fault sensing element</li> <li>Continuous duty rated coil</li> </ul>
Applications	Undervoltage Trip (MN)
	<ul> <li>Trips the circuit breaker when the control voltage drops below a tripping threshold</li> <li>Drops out between 35% and 70% of the rated voltage</li> <li>Continuous duty rated coil</li> <li>Circuit breaker closing is possible only if the voltage exceeds 85% of the rated voltage. If an undervoltage condition exists, operation of the closing mechanism of the circuit breaker will not permit the main contacts to touch, even momentarily. This is commonly called "Kiss Free".</li> </ul>
Installation and Connection	<ul> <li>Accessories are common to H-, J-, and L-frame circuit breakers and snap into cavities under the front accessory cover of the circuit breaker</li> <li>Each terminal may be connected by one 18–14 AWG (1.0–2.5 mm²) stranded copper wire</li> </ul>
Operation	<ul> <li>The circuit breaker must be reset locally after being tripped by shunt trip (MX) or undervoltage trip (MN)</li> <li>Tripping by the shunt trip or undervoltage trip has priority over manual (or motor operator) closing; in the presence of a standing trip order such an action does not result in any closing, even temporarily, of the main contacts</li> <li>Endurance: 50% of the rated mechanical endurance of the circuit breaker</li> </ul>

#### Table 89: Electrical Characteristics

		AC	DC	
Rated Voltage (V)		24, 48, 120, 208/277, 380/480, 525, 600	12, 24, 30, 48, 60, 125, 250	
Power Requirements	Pickup (shunt trip)	< 10 VA	< 5 W	
rower nequirements	Seal-in (undervoltage trip)	< 5 VA	< 5 W	
Clearing Time (ms)		< 50	< 50	

Table 90: Shunt Trip and Undervoltage Trip Suffix Codes and Kit Numbers

	Shunt T	rip (MX)	Undervoltage Release (MN)		
Voltage	Factory-Installed Suffix	Field-Installable Kit No.	Factory-Installed Suffix	Field-Installable Kit No.	
24 Vac	SK	S29384	UK	S29404	
48 Vac	SL	S29385	UL	S29405	
120 Vac	SA	S29386	UA	S29406	
208/277 Vac	SD	S29387	UD	S29407	
380/480 Vac	SH	S29388	UH	S29408	
525/600 Vac	SJ	S29389	UJ	S29409	
12 Vdc	SN	S29382	UN	S29402	
24 Vdc	SO	S29390	UO	S29410	
30 Vdc	SU	S29391	UU	S29411	
48 Vdc	SP	S29392	UP	S29412	
60 Vdc	SV	S29383	UV	S29403	
125 Vdc	SR	S29393	UR	S29413	
250 Vdc	SS	S29394	US	S29414	

Table 91: Adjustable and Fixed Time Delay Units for Undervoltage Trip

Dated Valtage	Field-Installable Kit No.		
Rated Voltage	Adjustable	Fixed	
48 Vac/dc	S33680	S29426	
100/130 Vac/dc	S33681	_	
220/250 Vac/dc	S33682	S29427	




## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

## **Motor Operator**



The motor operator remotely operates the circuit breaker featuring easy and sure operation:

- All circuit breaker indications and information remain visible and accessible, including trip unit settings and circuit breaker connection
- Suitability for isolation is maintained and padlocking remains possible
- Double insulation front face



- Contact position indicator (suitability for isolation)
- Spring status indicator (charged, discharged)
- 3. Manual spring-charging handle
- Keylock device
   Locking device (off position)
   using one to three padlocks,
   diameter 0.2–0.32 in. (5–8 mm),
   not supplied
- 5. ON push button
- 6. OFF push button
- Manual/auto mode selection switch; the position of the switch can be indicated remotely
- 8. Operation counter

#### Applications:

- Local motor-driven operation, centralized operation, automatic distribution control
- · Normal/standby manual transfer or switching to a replacement source to optimize energy costs
- Load shedding and reconnection to optimize energy costs
- Less than five cycle closing time for source synchronization

#### **Installation and Connection**

- All installations are available for H- and J-frame circuit breakers.
   All installations are available for L-frame circuit breakers except I-Line
- Connections of the motor operator module are to a built-in terminal block behind its front cover
- Stranded copper wire 14 AWG (2.5 mm²)

#### **Automatic Operation**

The motor operator is connected in series with the overcurrent trip switch (SDE).


- ON and OFF by two impulse type or continuous control signals
- Depending on the wiring, resetting can be done locally, remotely or automatically
- Mandatory manual reset following tripping due to an electrical fault (with overcurrent trip switch)

#### **Manual Operation**

- Transfer to manual mode with possibility of remote mode indication
- ON and OFF by two push buttons
- Recharging of stored-energy system by pumping the lever
- Padlocking in off position



## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Accessories and Auxiliaries**



**Motor Operator Characteristics** Table 92:

Response Time (ms)	Opening		< 600
nesponse rime (ms)	Closing	< 80	
Operating Frequency	cycles/minute max.		4
	AC (VA)	Opening	≤500
Power Requirements <sup>1</sup>		Closing	≤500
i ower riequirements.	DC (W)	Opening	≤500
	DO (VV)	Closing	≤500

<sup>&</sup>lt;sup>1</sup> For H- and J-frame, the inrush current is 2x operating current for 10 ms.

Table 93: Motor Operator and Accessory Suffix Codes and Catalog Numbers

Device <sup>1</sup>	Cantral Valtage	Factory-Installed	Field-Installable Kit No.		
Device	Control Voltage	Suffix	H-Frame	J-Frame	L-Frame
Communicating Motor Operator	220/240 Vac 50/60 Hz	NC	S429441	S431549	S432652
	48/60 Vac 50/60 Hz	ML	S29440	S31548	S432639
	110/130 Vac 50/60 Hz	MA	S29433	S31540	S432640
	208/277 Vac 60 Hz	MD	S29434	S31541	S432641
	380/415 Vac 50/60 Hz	MF	_	_	S432642
Motor Operator	440/480 Vac 60 Hz	MH	S29435	S31542	S432647
	24/30 Vdc	MO	S29436	S31543	S432643
	48/60 Vdc	MV	S29437	S31544	S432644
	110/130 Vdc	MR	S29438	S31545	S432645
	250 Vdc	MS	S29439	S31546	S432646
Lock Mounting Hardware	_	_	_	_	S32649
Ronis® Lock	_	_	S41940	S41940	S41940
Profalux® Lock	_	_	S42888	S42888	S42888
Mounting Hardware with Ronis Lock	_	_	S429449	S429449	_
Operations Counter	_	_	_	_	S32648
Adapter for I-Line Circuit Breaker			S37420	S37420	_

For NSX cord (communication suffixes EA, EB, ED, and EE) any motor operator may be selected.
For BSCM + NSX cord (communication suffixes EB, EH, EK, and EL) only the communicating motor operator may be selected.



## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Accessories and Auxiliaries**

## Add-On Ground-Fault Module (GFM) (H- and J-Frame Only)

The Micrologic Ground-Fault Module (GFM) is a UL Listed/CSA Certified circuit breaker accessory which protects equipment from damage caused by ground faults. It is an add-on module which, when connected to a PowerPact H- or J-frame thermal-magnetic circuit breaker only, provides ground-fault sensing and ground-fault relay functions.

HD/JD ground-fault modules feature:


- Adjustable ground-fault pickup levels
- Adjustable ground-fault time delays
- Integral ground-fault push-to-test feature
- Ground-fault indicator (mechanical for local, contacts for remote)
- All GFMs are supplied for I-Line™ mounting as standard, easily convertible to unit mount by removing the I-Line bracket.
- Fault-powered (through the sensing current transformer) for electronics, shunt trip, and integral test feature. Meets NEC 230.95(C).
- A 12 Vdc shunt trip module (Catalog No. S29382) is required in the circuit breaker. This may be field installed or factory installed when the circuit breaker is ordered with an -SN suffix.
- UL 1053 Ground-fault Sensing and Relaying Equipment

The GFM system requires the following:

- H-frame (15-150 A) or J-frame (150-250 A) molded case circuit breaker
- Shunt trip for circuit breaker (may be factory-installed or field-installed)
- Bus bar connection (terminal nut inserts) for OFF end of circuit breaker
- Optional neutral current transformer, catalog number GFM25CT (must be ordered for 4-wire applications).

Table 94: **Ground-Fault Module** 

Catalog No.	Rating	Sensitivity	Time Delay (Approximate)
GFM150HD	150 A	20, 40, 60, 80, 100 A	0.2, 0.3, 0.4, 0.6 sec
GFM250JD	250 A	40, 80, 120, 160, 200 A	0.2, 0.3, 0.4, 0.6 sec



J-Frame Circuit Breaker with GFM Installed

01/2014

## Earth Leakage Module (ELM) (H- and J-Frame Only)

The Earth Leakage Module (ELM) is an add-on module which, when connected to a PowerPact H- or J-frame MCCB, provides low-level ground-fault sensing and ground-fault relay functions.

Because these ELMs are highly sensitive (30 mA to 3 A), they provide much greater protection than GFMs (20 Amps to 200 Amps sensitivity). The ELMs provide greater protection of control circuits and other sensitive equipment. The associated circuit breaker must have a 48 Vdc shunt trip), which may be field-installed (kit S29392) or factory-installed (suffix –SP) in the H- or J-Frame circuit breaker.

The add-on Earth Leakage Module (ELM) features:

- Adjustable ground-fault pickup levels as low as 30 mA
- Adjustable ground-fault time delays from instantaneous to 500 msec (time delay can be applied to any setting)
- Integral ground fault push-to-test feature
- Ground-fault indicator; pop-up button for local status and contacts for remote indication (to be used only with the tripping option)
- All ELMs are supplied for I-Line mounting and are easily convertible to unit-mount by removing the I-Line mounting feet
- Three poles; 240 to 600 Vac maximum: 3-phase, 3-wire (no neutral) and 1-phase, 2-wire applications
- Line-power obtained through internal bus to provide power for electronics, shunt trip, and integral test feature
- A shunt trip is required in the circuit breaker; it may be field-installed or factory-installed in the PowerPact H and J circuit breakers.
- UL 1053 Ground-fault Sensing and Relaying Equipment

Table 95: ELM Selection Chart 1

Companion Circuit Breaker		Enclosure Space		Pick-Up	Ground-Fault	
Prefix	Size	Required I-Line Equipment	Catalog No.	Adjustments	Time Delay Adjustments	
HD, HG, HJ, HL	15–150 A	LA	ELM150HD	30 mA 100 mA 300 mA	Instantaneous 60 ms	
JD, JG, JJ, JL	150–250 A	LA	ELM250JD	1A 3A	100 ms 500 msec	

<sup>&</sup>lt;sup>1</sup> At 250 A, the ELM250JD can be used with standard (80%) rated circuit breakers only.

## **Factory-Installed ELMs**

The catalog number for circuit breakers with factory-installed ELM should include the special suffixes SP and VL or VM:

H D M 3 6 150 SP VL

#### where

- H = H-fame (or J = J-frame)
- D = D interruption level (or G, J or L)
- M = Lugs on ON end and terminal nuts on OFF end (required)
- SP = Factory-installed 48 Vdc shunt trip (S29392, required)
- VL= Earth Leakage Module (ELM) <150 A (H-frame) or VM = Earth Leakage Module (ELM) <250 A (J-frame)</li>




J-Frame Circuit Breaker

with ELM Installed

## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Accessories and Auxiliaries**


## **Rotary Operating Handles**

## **Directly Mounted Rotary Operating Handles**



Installation	The directly mounted rotary operating handle replaces the circuit breaker front accessory cover (secured by screws).			
Operation	The direct rotary handle maintains:  Suitability for isolation Indication of three positions: I (ON), Tripped and O (OFF) Access to the "push-to-trip" button Visibility of, and access to, trip unit settings The circuit breaker may be locked in the OFF position by using one to three padlocks (not supplied)	I/ON (Closed) Tripped O/OFF		
Models	Standard with black handle     VDE type with red handle and yellow bezel for machine tool control	(Open)		
Variations	Accessories transform the standard direct rotary handle for the following situations:  Motor control centers (MCCs): Opening of door prevented when circuit breaker is on Closing of circuit breaker inhibited when door is open  Machine tool control; complies with CNOMO E03.81.501N; degree of protection IP54 Early make or early break contacts may be installed into direct mount rotary handle			
Standards	The directly-mounted rotary operating handle is UL Listed under file E103955 and CSA Certified under file LR 69561			

## **Door-Mounted (Extended) Rotary Operating Handle**



Operating Handle

The door-mounted (extended) rotary operating handle is made up of:		
<ul> <li>A unit that replaces the front accessory cover of the circuit breaker (secured by screws)</li> <li>An assembly (handle and front plate) on the door that is always secured in the same position, whether the circuit breaker is installed vertically or horizontally</li> <li>An adjustable extension shaft</li> <li>The handle mechanism can be used in NEMA 3R and 12 enclosure applications</li> </ul>		
The door mounted operating handle makes it possible to operate circuit breakers installed in enclosure from the front. The door mounted operating handle maintains:		
<ul> <li>Suitability for isolation</li> <li>Indication of the three positions OFF (O), ON (I) and tripped</li> <li>Visibility of and access to trip unit settings when the door is open</li> <li>Degree of protection: IP40 as per IEC 529</li> </ul>		
Defeatable interlock prevents opening of door when circuit breaker is on		
The circuit breaker may be locked in the off position by using one to three padlocks, padlock shackle diameter 0.19–0.31 in. (5–8 mm); padlocks are not supplied; locking prevents opening of the enclosure door		
The shaft length is the distance between the back of the circuit breaker and the door:		
<ul> <li>Minimum shaft length is 7.4 (185 mm)</li> <li>Maximum shaft length is 24 in. (600 mm)</li> <li>Extended shaft length must be adjusted</li> </ul>		
<ul> <li>Standard with black handle</li> <li>VDE type with red handle and yellow bezel for machine tool control</li> </ul>		
For drawout configurations, the extended rotary handle is also available with a telescopic shaft containing two stable positions		
The door-mounted rotary operating handle is UL Listed under file E103955 and CSA Certified under file LR 69561		

## PowerPact™ H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

Table 96: Rotary Operated Handles

			H- and	J-Frame	L-Frame	
	Device	Description	Factory Installed Suffix	Field Installable Kit No.	Factory Installed Suffix	Field Installable Kit No.
	Standard Handle Black	Handle only	RD10	S29337	RD10	S32597
	Standard Black Handle with	One early-break switch	RD12	S29337 + S29345	RD12	S32597 + S32605
	Standard Black Handle With	Two early-make switches	RD13	S29337 + S29346	RD13	S32597 + S29346
Direct		Handle Only	RD20	S29339	RD20	S32599
Mounted	Red handle on yellow bezel	One early-break switch	RD22	S29339 + S29345	RD22	S32599 + S32605
		Two early-make switches	RD23	S29339 + S29346	RD23	S32599 + S29346
	MCC Conversion Accessory	_	S429341	_	S32606	
	CNOMO Conversion Accessory	_	S29342	_	S32602	
	Standard black handle	Handle Only	RE10	S29338	RE10	S32598
Door Mounted	Standard Black Handle with:	Two early make switches	RE13	S29338 + S29345	RE13	S32598 + S32605
	Red handle on yellow bezel	Handle Only	RE20	S29340	RE20	S32600
Telescoping			RT10	S29343	RT10	S32603
	Key lock adapter		_	S429344	_	S32604
		Ronis 1351.500	_	S41940	_	S41940
Accessories	Vay lasks	Profalux KS5 B24 D4Z	_	S42888	_	S42888
	Key locks	2 Ronis keylocks with 1 key	_	S41950		S41950
		2 Profalux keylocks with 1 key	_	S42878	_	S42878
	Indication Auxiliary Switch	One early-break switch	_	S29345	_	S32605
	Indication Auxiliary Switch	Two early-make switches	_	S29346		S29346

## **Class 9421 NEMA Door Mounted Rotary Operating Handles**



	The extended rotary operating handle is made up of:			
Installation	<ul> <li>A mounting plate that provides a rotary actuator for a standard toggle circuit breaker</li> <li>Handle assemblies available for NEMA 3, 3R, 4, and 4X</li> <li>Available in standard or short (3 in.) handle assemblies</li> </ul>			
	The door mounted operating handle makes it possible to operate circuit breakers installed in enclosure from the front.			
Operation	Provides ON (I) and OFF (O) indication			
	The circuit breaker may be locked in the off position			
	The shaft length is the distance between the back of the circuit breaker and the door:			
Shaft Length	<ul> <li>Minimum mounting depth is 5.5 in. (138 mm)</li> <li>Maximum mounting depth is 10.75 in. (273 mm) with standard shaft</li> <li>Maximum mounting depth is 21.3 in. (543 mm) with long shaft</li> </ul>			

## H- and J-Frame Class 9421 Door-Mounted Operating Mechanism

Description	Catalog No.
Standard Shaft Kit	9421LJ1
Long Shaft Kit	9421LJ4

## PowerPact™ H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

Table 97: H- and J-Frame Component Parts

Description		Catalog No.
Standard Handle Assembly	Type 1, 3R, 12	9421LH6
	NEMA Type 3 and 4, Painted	9421LH46
	NEMA Type 3 and 4, Chrome Plated	9421LC46
Operating Mechanism	Includes Lockout	9421LJ7
Standard Shaft	Support Bracket Not Required	9421LS8
Long Shaft	Support Bracket Included	9421LS13

Table 98: L-Frame NEMA Door-Mounted Rotary Operated Handles

Handle Type	Poles	() nerating Mechanism Included in Kit	Mounting Depth Min–Max	Kit Number
Painted 6 in.	3	9421LS8 and 9421LC46	7-1/4 to 12-1/16 in. (184 to 306 mm)	9421LD1
		9421LS13 and 9421LH46	7-1/4 to 22-5/8 in. (184 to 575 mm)	9421LD4


## **Class 9422 Cable Operating Handle**

The cable operator maintains:

Flange-mounted handle cable operating mechanism is for use with Class 9422 Type A handle operators especially designed for tall, deep enclosures where placement flexibility is required.



Applications	Suitability for isolation Indication of three positions: O (OFF), I (ON) and tripped Access to push-to-test
	<ul> <li>The circuit breaker may be locked in the off position by one to three padlocks</li> <li>Door can be locked closed due to interlocking features of the handle operator</li> </ul>
Installation	<ul> <li>Handle is mounted on flange of enclosure using specified mounting dimensions while circuit breaker and operating mechanism are mounted to inside of enclosure using two screws</li> <li>Cable lengths available in 3-, 5- or 10-foot lengths to accommodate a variety of mounting locations Handles are available in painted NEMA 1, 3, 3R, 4 (sheet steel) and 12 ratings or chrome (NEMA 4, 4X)</li> </ul>



Refer to NEC Article 430-10 for minimum dimension X from circuit breaker top mounting hole to wall or barrier to ensure adequate wire bending space.

Note: Bend radius in cable must never be less than 6 in. (152 mm). Electrical clearances must be maintained between cable and live electrical parts.


in.

Table 99: Class 9422 Cable Operating Mechanisms and A1 Handles

Description		H- and J-Frame Kit Number	L-Frame Kit Number
Cable Mechanism Length	36 in. (914 mm)	9422CSF30	9422CSJ30
	60 in (1524 mm)	9422CSF50	9422CSJ50
	84 in. (2134 m)	9422CSF70	_
	120 in. (3048 mm)	9422CSF10	9422CSJ10
A1 painted flange handle		_	9422A1
Operating Mechani	sm Only		9422RSI



Threaded-rod flange-mounted variable depth operating mechanism



# Class 9422 Flange-Mounted Variable-Depth Operating Mechanism

Designed for installation in custom built control enclosures where main or branch circuit protective devices are required.

- All circuit breaker operating mechanisms are suitable for either right- or left-hand flange mounting, convertible on the job.
- H- and J-frame variable mounting depth range: 5.88–17.75 in. (149–451 mm).
- H- and J-frame operating mechanism 9422RQ1 does not include handle mechanism.

Designed for installation in custom-built control enclosures where main or branch circuit protective devices are required. All circuit breaker operating mechanisms are suitable for either right- or left-hand flange mounting, convertible in the field.

Table 100: L-Frame Flange-Mounted Operating Mechanism

Description	Depth	Kit Number
Variable Depth Mechanism	9.00–17.75 in. (229–451 mm)	9422RSI

# **Locking Systems**

Padlocking systems can receive up to three padlocks with diameters of 0.19–0.31 in. (5–8 mm); padlocks not supplied.




Table 101: Device Locking, Interlocking Options

Device	Descriptio	Field-Installed Cat. No.		
Device	Description	H- and J-Frame	L-Frame	
Handle	Removable (lock OFF only)	S29370	S29370	
Padlocking	Fixed (lock OFF or ON)	S29371	S32631	
Device <sup>1</sup>	Fixed (lock OFF only) <sup>2</sup>	S37422	NJPAF	
Key Locking	Provision and 2 locks keyed alike	Ronis	_	S41950
		Profalux	_	S42878

<sup>1</sup> Rotary handles and motor operators have integral padlocking capability.

Not available in HD or HG 2P modules.



# **Manual Mechanical Interlocking Systems**

Some installations use two power supply sources to counter any temporary loss in the main supply. A mechanical interlocking system is required to safely switch between the two sources. The replacement source can be a generator set or another network.

Managing multiple power sources can be controlled manually by mechanical interlocks.


The mechanical interlocking system is made up of:

- two H-, J-, or L-frame devices (circuit breakers or switches) controlled manually
- mechanical interlocking, which prevents handle movement from the OFF position while the other device is in the ON position.


Since it is controlled manually by a maintenance technician, switchover time from the normal source to the replacement source can vary.

Figure 4: Interlocking Systems

#### H- and J-Frame




Interlocking with Toggle Control (S29354)




Interlocking with Rotary Handles (S29369)

#### L-Frame



Interlocking with Toggle Control (S32614)



Interlocking with Rotary Handles (S32621)

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

#### Interlocking of Circuit Breakers With Toggle Control

Two devices can be interlocked using this system. Two identical interlocking systems can be used to interlock three devices installed side by side.

Authorized positions:

- one device closed (ON), the others open (OFF)
- all devices open (OFF)

The system is locked using one or two padlocks (shackle diameter 0.19–0.31 in. [5 to 8 mm]). This system can be expanded to more than three devices.

There are two interlocking-system models:

- one for PowerPact H- and J-frame circuit breakers
- one for PowerPact L-frame circuit breakers

All toggle-controlled unit-mount or plug-in PowerPact H-, J-, and L-frame circuit breakers and automatic switches of the same frame size can be interlocked. The devices must be either all unit-mount or all plug-in versions. Interlocking is not available for I-Line constructions.

The toggle interlock system can receive one or two padlocks with diameters of 0.19–0.31 in. (5–8 mm). Both interlocked circuit breakers must be unit-mount or both plug-in. Two sliding interlocking bars can be used to interlock three circuit breakers installed side-by-side, in which case one circuit breaker is in the ON (I) position and the two others in the OFF (O) position. (Kit S29354. Not available for 2P HD and HG devices.)

#### Interlocking of Two Devices with Rotary Handles

Interlocking involves padlocking the rotary handles on two devices which may be either circuit breakers or automatic switches.

Authorized positions:

- one device closed (ON), the other open (OFF)
- both devices open (OFF).

The system is locked using up to three padlocks (shackle diameter 0.19–0.31 in. [5 to 8 mm]).

There are two interlocking-system models:

- one for PowerPact H- and J-frame circuit breakers
- one for PowerPact L-frame circuit breakers

All rotary-handle unit-mount or plug-in PowerPact H-, J-, and L-frame circuit breakers and automatic switches of the same frame size can be interlocked. The devices must be either all unit-mount or all plug-in versions. Interlocking is not available for I-Line constructions

The rotary handles are padlocked with the devices in the OFF (I) position. The interlock mechanism inhibits the two devices from being closed (ON/I) at the same time, but allows for both devices to be open (OFF/O) simultaneously. (Kit S29369. Not available for 2P HD and HG devices.)

Table 102: Interlocking Accessories

Accessory	Means	Kit Number	Kit Number		
	Wearis	H-, J-Frame	L-Frame		
Interlocking	Mechanical for circuit breakers with rotary handles <sup>1</sup>	S29369	S32621		
(UL listed) Mechanical for circuit breakers with toggles <sup>1</sup>		S29354	S32614		

Not available in HD or HG 2P modules.



# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

#### Interlocking Devices using Keylocks (Captive Keys)

Interlocking using keylocks makes it possible to interlock two or more devices that are physically distant or that have very different characteristics, for example medium-voltage and low-voltage devices or a PowerPact H-, J-, and L-frame circuit breaker and automatic switch.

Each device is equipped with an identical keylock and the key is captive on the closed (ON) device. A single key is available for all devices. It is necessary to first open (OFF position) the device with the key before the key can be withdrawn and used to close another device.


All rotary-handle PowerPact H-, J-, and L-frame circuit breakers and automatic switches can be interlocked between each other or with any other device equipped with the same type of keylock.

For circuit breakers equipped with rotary handles or a motor operator. Interlocking with keys may be easily implemented by equipping each of the circuit breakers, either unit-mount or drawout, with a directly mounted rotary operating handle and a standard keylock, with only one key for the two keylocks. This solution enables interlocking between two circuit breakers that are geographically distant or that have significantly different characteristics.

#### Use:


- A keylock adapter (one required for each circuit breaker)
- Two identical keylocks with a single key

See Table 96 for more information.



# **Sealing Accessory**

The sealing accessory kits includes the elements required to fit seals to prevent:



- Rotary handle removal
- Opening of the motor operator
- Access to accessories
- · Access to trip unit settings
- · Access to ground-fault protection settings
- Trip unit removal
- Terminal cover removal
- Access to power connections


Table 103: Sealing Accessory Kits

Description	Kit No.	Qty.
Trip Unit Sealing Accessory Kit	MICROTUSEAL	6
Front Cover Screws Sealing Accessory Kit	S29375	6

#### **Front-Panel Escutcheons**

- For unit-mount or plug-in installation.
- Front-panel escutcheons for toggle handles secures to the panel from the front.
- Front-panel escutcheons for motor-operated or rotary-operating handle secures to the panel by four screws from the front.








Table 104: Front-Panel Escutcheons

Description	Kit Number		
	H-, J-Frame	L-Frame	
Front Panel Escutcheon for Toggle Circuit Breakers	S29315	32556	
Front Panel Escutcheon for Rotary Handle, Motor Operator or Extended Escutcheon	S29317	S32558	

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries

# **Toggle Collars (For Drawout Mounting)**



Toggle collars make it possible to maintain degrees of protection regardless of the circuit breaker position (connected, disconnected):


- Front panel escutcheons are required (identical to those for rotary handle and ammeter module)
- Toggle collars are secured by two screws on the circuit breaker
- · Front panel escutcheons are secured on the enclosure
- Toggle extension is supplied with the toggle collar

Front panel escutcheons for motor operator and rotary operating handles are the same as for the unit-mount circuit breakers.

Table 105: Toggle Collars

Description	H-, J-Frame Kit Number	L-Frame Kit Number
Toggle Collar	S29284	S32534

# **Toggle Boot**



- NEMA 1, 2, 3, 3R protection
- Fits on front of circuit breaker

Table 106: Toggle Boot

Description	Kit Number		
	H-, J-Frame <sup>1</sup>	L-Frame	
Toggle Boot	S29319	S32560	

<sup>1</sup> Not available for HD and HG 2P modules

# **Handle Extension**








Table 107. Handle Extensions							
Description	Qty.	Kit Number					
Description		H-, J-Frame	L-Frame				
T-Handle Extension (Temporary)	1	_	32595				
Toggle Extension (Fixed)	5	S29313	S432553				



#### Circuit Breaker Enclosures and Enclosure Accessories

- Square D™ brand circuit breaker enclosures are UL Listed/CSA Certified and are suitable for use as service entrance equipment, except as footnoted.
- The short circuit rating of an enclosed circuit breaker is equal to the rating of the circuit breaker installed, except as footnoted.
- Circuit breakers are ordered and shipped separately for field installation.

**Table 108: Minimum Enclosure Dimensions** 



Circuit Breaker	A	Enclosure Dimensions (h x w x d)			
	Amperage	Standard (80%)	100% Rated		
HD/HG /HJ/HL	15–150 A	15.6 x 6.12 x 3.49 in. (396 x 155 x 89 mm)	15.6 x 6.12 x 3.49 in. (396 x 155 x 89 mm)		
HR	15–150 A	18.13 x 8.63 x 4.13 in. (461 x 219 x 105 mm)	62 x 22.5 x 14 in. (1575 x 572 x 356 mm)		
JD/JG/ JJ/JL <sup>1</sup>	150–250 A	18.72 x 6.12 x 3.49 in. (476 x 155 x 89 mm)	18.72 x 6.12 x 3.49 in. (476 x 155 x 89 mm)		
JR	150-250 A	28.5 x 12.38 x 5.38 in. (724 x 314 x 137 mm)	62 x 22.5 x 14 in. (1575 x 572 x 356 mm)		
LD/LG/ LJ/LL	250–600 A	35.48 x 12.00 x 4.45 in. 901 x 305 x 113 mm)	35.48 x 12.00 x 4.45 in. (901 x 305 x 113 mm)		
LR	250-600 A	40.5 x 13.75 x 4.33 in. (1030 x 350 x 110 mm)	40.5 x 13.75 x 4.33 in. (1030 x 350 x 110 mm)		

Minimum enclosure insulation required if circuit breaker side < 4.13 in. (105 mm) from metal.


Table 109: Circuit Breaker Enclosure Catalog Numbers

Circuit Breaker				Enclosure Cat. No.				
Cat. No. Prefix	Rating	Poles	NEMA 1 Flush	NEMA 1 Surface	NEMA 3R <sup>1</sup>	NEMA 4, 4X, 5, 3, 3R Stainless Steel	NEMA 12/3R, 5 (Without Knockouts) <sup>2</sup>	
HDL,HGL,HJL,HLL	15–150 A	2, 3	J250F	J250S	J250R	J250DS	J250AWK	
JDL,JGL,JJL,JLL	150-250 A	2, 3	32301	02301	32505	J250N	325005	J250AWK
HDL	15–100 A	3	_	HD100S <sup>3, 4, 5</sup>	_	_	_	
JDL	150–250 A	3	_	JD250S <sup>3, 5, 6</sup>	_	_	_	

Enclosures with NRB or RB suffix have provisions for 3/4 in. through 2-1/2 in. bolt-on hubs in top endwall. Enclosures with R suffix have blank endwalls and require field cut opening.

Table 110: Dimensions

Cat. No.	Approximate Dimension							
Cat. No.	Series		Н		W		D	
HD100S	A01	17.00 in.	431.8 mm	7.90 in.	200.7 mm	4.75 in.	120.7 mm	
J250F	A01	32.40 in.	823 mm	15.40 in.	391 mm	6.00 in.	152 mm	
J250S	A01	31.36 in.	797 mm	14.36 in.	365 mm	6.00 in.	152 mm	
J250R	A01	31.05 in.	789 mm	14.47 in.	368 mm	6.28 in.	160 mm	
J250DS	A01	32.26 in.	819 mm	9.72 in.	247 mm	7.94 in.	202 mm	
J250AWK	A01	32.26 in.	819 mm	9.72 in.	247 mm	7.94 in.	202 mm	



Suitable for rainproof NEMA 3R application by removing drain screw from bottom endwall.

Copper wire only.

Maximum short circuit current rating is 25 kA, 240 Vac

Order service ground kit PKOGTA2 if required.

Maximum short circuit current rating is 18 kA, 480 Vac.

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Accessories and Auxiliaries


**Table 111: Insulated Grounded Neutral Assembly** 

Circuit Breaker	Circuit Breaker		y For Use With	Terminal Lug Data—Total	
Oat No Broffin Am	Ampere	NEMA 1 & 3R	NEMA 4, 4X, 5, 12 & 12K	Available (Line plus Load)	
Cat. No. Prefix Rating		Cat. No.	Cat. No.	AWG/kcmil	
HDL,HGL,HJL,HLL	15–100 A	SN100FA	SN100FA	(4) 14-1/0 Cu or (4) 12-1/0 Al	
HDL,HGL,HJL,HLL	125–150 A	SN400LA	SN400LA	(2) 1–600 or (4) 1–250 Al/Cu, plus (2) 4–300 Al/Cu	
JDL,JGL,JJL,JLL	150–250 A	SN400LA	SN400LA	(2) 1–600 or (4) 1–250 Al/Cu, plus (2) 4–300 Al/Cu	

Table 112: Service Ground Kits

Circuit Breaker	Ground Bar	Number of	Conductors	Wire Range	
Cat. No. Prefix	Cat. No.	Terminals	Per Terminal		
HDL,HGL,HJL,HLL, JDL,JGL,JJL,JLL	PKOGTJ250	2	1	6 AWG-300 kcmil Al/Cu	

# **Section 9—Circuit Breaker Mounting and Connections**



# **Mounting Configurations**

The PowerPact™ H-, J-, and L-frame circuit breakers are available in a variety of configurations.

**Table 113: Mounting Options** 

Termination Letter	Poles		Options Code Suffix					
Termination Letter	H-, J-Frame	L-Frame	Options code Sumx					
A = I-Line	3 Pole Only	3 Pole Only		(N, and D Terminations Only)				
F = Bus Bar	3 Pole Only	3 or 4 Pole	For footon, installed to resinctions, place	H = Plug-In or Drawout				
L = Lugs on Both Ends	3 Pole Only	3 or 4 Pole	For factory-installed terminations, place termination letter in the third block of the	J = No Stationary part				
M = Lugs ON End	3 Pole Only	3 or 4 Pole	circuit breaker catalog number.	0 = No Switches				
P = Lugs OFF End	3 Pole Only	3 or 4 Pole	LIGIDI3161410101U13111X1H1J1010	0 = No Shutters				
N = Plug-In	3 Pole Only	3 or 4 Pole	La Termination No. Options Code					
D = Drawout	3 Pole Only	3 or 4 Pole	Options dode					
S = Rear Connection	3 Pole Only	3 or 4 Pole						

Refer to circuit breaker installation bulletin before installing circuit breaker, accessories, or wiring.

#### **Unit-Mount Circuit Breakers**

The standard lugs can be removed for the installation of compression-type lugs or bus connections. All lugs are UL Listed/CSA Certified for their proper application and marked for use with aluminum and copper (Al/Cu) or copper only (Cu) conductors. Lugs suitable for copper and aluminum conductors are made of tin-plated aluminum.

#### Mounting


H-, J-, and L-frame circuit breakers may be mounted vertically, horizontally or flat on their back without any derating of characteristics.


Unit-mount H- and J-frame circuit breakers are supplied with two mounting screws, unit-mount L-frame circuit breakers are supplied with four mounting screws. These mounting screws are inserted through mounting holes molded into the circuit breaker case and threaded into the mounting enclosure, rails or through the panel door for flush mounting.


A DIN rail mounting bracket (catalog no. S29305) is available for the H- and J-frame circuit breakers.

**NOTE:** DIN rail mounting is not compatible with motor operated applications.

Figure 5: **Unit-Mounting Options** 









#### L-Frame Circuit Breakers (4 Mounting Screws)

Mounting on Rails






Flush Mounting

#### I-Line™ Circuit breakers

PowerPact H-, J-, and L-frame circuit breakers are available in I-Line construction for easy installation and removal in I-Line applications.

I-Line circuit breakers use "blow-on" type line side connectors. In case of a short circuit, increased magnetic flux causes the plug-on connectors of the circuit breaker to tighten their grasp on the bus bars. The I-Line connectors and circuit breaker mounting bracket are integral parts of I-Line circuit breakers and cannot be removed or replaced. I-Line circuit breakers come with mechanical load side lugs, or optional terminal nut to connect to bus bars or to compression (crimp) lugs.







Table 114: Phase Options—Example HDA36150

Phase Option Number	Phase Connection	2P Example	3P Example
1	AB	HDA261501	_
2	AC	HDA261502	_
3	ВА	HDA261503	_
4	BC	HDA261504	_
5	CA	HDA261505	_
6	СВ	HDA261506	_
Standard	ABC	_	HDA36150
6	CBA	_	HDA361506

# **Plug-In Circuit Breaker Mounting**




Plug-In Mounting


The plug-in base is mounted through a panel. The plug-in configuration makes it possible to:


- Extract and/or rapidly replace the circuit breaker without having to touch connections
- · Allow for addition of future circuits at a later date


When the circuit breaker is in the connected position, the primary voltage is fed through the circuit breaker by means of multiple finger disconnects. Control voltage of internal accessories is provided through secondary disconnects.

# Parts of a Plug-In Configuration



















Safety Trip Interlock Mounted on Back of Circuit Breaker



Drawout Mounting




Disconnecting Blocks

Accessory circuits exit the circuit breaker using one to three secondary disconnecting blocks (nine wires each). Circuit breaker connection wires for the options installed with trip unit STR53UP exit through the automatic secondary disconnecting blocks. These are made up of:


- A moving part connected to the circuit breaker through a support (one support per circuit breaker).
- A fixed part mounted on the plug-in base, equipped with connectors for wire up to 14 AWG (2.5 mm<sup>2</sup>).

For test purposes, circuit breakers may be equipped with one to three manual auxiliary connectors, which allow the auxiliaries to remain connected when in the "disconnected" position.

Figure 6: Plug-In Base (Mounting Options)



Manual Auxiliary Connector



The L-frame plug-in mounting is Listed under UL file E113555 and Certified under CSA file LR 69561.

#### **Drawout Mounting**

The cradle is made up of two side plates installed on the plug-in base and two other plates mounted on the circuit breaker.

The drawout mounting provides all of the functions of the plug-in base, plus:

- Disconnected position—the power circuit is disconnected, the circuit breaker is simply withdrawn and may still be operated (on, off, push-to-trip)
- Circuit breaker may be locked using 1 to 3 padlocks, diameter 0.19 to 0.31 inch (5–8 mm), to prevent connection
- Auxiliaries can be tested using manual auxiliary connector

Drawout mounting is on a backplate:

- Through a front panel or on rails
- Horizontally or vertically

Accessories for drawout circuit breakers:

- Auxiliary indicator contacts indicator contacts for installation on the fixed part of the cradle, indicating the "connected" and "disconnected" position
- Toggle collar for circuit breakers with toggle through front panel, intended to maintain the degree of protections whatever the position of the circuit breakers (supplied with a toggle extension)
- Keylock which can be used to
  - Prevent insertion for connection
  - Lock the circuit breaker in the connected or disconnected position
- Telescopic shaft for extended rotary handles
- Control voltage, which is provided through automatic secondary disconnect in the connected position only. Electrical accessories can be tested in the disconnected position with an external wiring harness.

The drawout-mounted cradle is listed under UL file E113555 and certified under CSA file LR69561.

Figure 7: Drawout Mounting Positions




Table 115: Plug-In and Drawout Mountings for H- and J-Frame Circuit Breakers (3P or 2P in a 3P module)


	Factory Installed Suffix	Field- Installed Cat. No.				
Complete Factory-Assembled	Plug-in base	shipped with circuit breaker	N	_		
Circuit Breakers	Drawout crad	le shipped with circuit breaker	D	_		
	Diversion Book	Circuit breaker Only	HJ00			
	Plug-In Base	Plug-in base kit		S29278		
Special Order Options for		Circuit breaker only	HJ00			
Plug-In and Drawout Circuit Breakers	Drawout Cradle	Plug-in base kit		S29278		
Broakere		Cradle side plates (fixed part of chassis)		S29282		
		Circuit breaker side plates (moving part of chassis)		S29283		
	H-Frame Shu		S37442			
	J-Frame Shut		S37443			
	Secondary	Fixed part 9-wire connector (mounted on base)		S29273		
	Disconnect	Moving part 9-wire connector (mounted on circuit breaker)		S29274		
Accessories for Plug-In and Drawout	Blocks	Support for 2-moving connectors		S29275		
Diawout	Extended esc	utcheon with extended toggle collar		S29284		
	Two position	indicating switches (connected/disconnected)		S29287		
	H-Frame Sho	H-Frame Short Terminal Covers (3P)				
	J-Frame Shor	t Terminal Covers (3P)		S37440		

Table 116: Plug-In and Drawout Mountings for L-Frame Circuit Breakers

Description			Plug-i	n Mou	ınting	Drawout Mounting			
		Poles	Factory Installed		Field- estalled	Factory Installed	Field- Installed		
			Suffix	Qty	Kit. No.	Suffix	Qty	Kit. No.	
Kit (atationam, and maying nauta)		3	N		_	D		_	
Kii (Stationary ari	Kit (stationary and moving parts)		N		_	D		_	
	Plug-in base	3			S32514			S32514	
Stationary Part	Flug-III base	4			S32515			S32515	
	Fixed part of chassis							S32532	
	Circuit breaker only		HJ00			HJ00			
Moving Port	Moving part of chassis							S32533	
Moving Fait	Moving Part	3		2x1	S32562		2x1	S32562	
	Short terminal covers			2x1	S32563		2x1	S32563	

Order two of kit.

Table 117: Plug-In and Drawout Accessories



Plug-In and Drawout Access	Field-Installed Kit No.				
-			H-, J-Frame	L-Frame	
	Fixed Part	9-Wire Connector	S29273	S29273	
Secondary Disconnecting Blocks <sup>1</sup>	Marriago Dant	9-Wire Connector	S29274	S32523	
	Moving Part	Support for Moving Connectors	2x <sup>2</sup> <b>S29275</b>	3x <sup>3</sup> <b>S32525</b>	
Manual Auxiliary Connector	9-Wire Connect	or for Disconnected Operation	_	S29272	
Shutter	Two Shutters fo	r Plug-In Base	29271	32521	
	Extended Escut	cheon for Toggle Collar	S29284	S32534	
Classic Accessories	Locking Device	(Key Lock is Not Included)	S29286	S29286	
	Two Position Inc	dicator Contacts (Connected/Disconnected)	S29287	S29287	

<sup>&</sup>lt;sup>1</sup> Included when electrical accessories are factory installed.

<sup>&</sup>lt;sup>2</sup> Order two of kit.

<sup>3</sup> Order three of kit.


#### Connection

#### **Rear Connection**

One Long and Two Short

For connection of bus bars or cables with compression lugs. Rear connections are easily installed on the circuit breaker terminals. The same connection may be installed flat, edgewise or at a 45° angle. All combinations are possible. The circuit breaker is mounted on a backplate.

Four Positions Possible for Each Connector














Table 118: Rear Connections


	H-Frame			•	J-Frame				L-Frame			
Device	Description	Poles	Factory- Installed Termination No.	Field- Installable Cat. No.	Poles	Factory- Installed Termination No.	Field- Installed Cat. No.	Poles	Factory- Installed Termination No.	Field-Installed Cat. No.		
Mixed Bear C	Rear Connection Kit1		S	_	2	S	_	3	S	S32477		
Mixed Hear O	offilection Kit.	3	S	S37432	3	S	S37437	4	S	S32478		
	Short rear connections (set of 2)	2 or 3	_	2x <sup>2</sup> S37433	2 or 3	_	2x <sup>2</sup> S37438	3	_	2x <sup>2,3</sup> S432475		
Consisting of:	Long rear connections (set of 2)	2013	_	S37434		_	S37439 <sup>4</sup>	3	_	2x <sup>3</sup> S432476		
	Short terminal cover (3P)	3	_	S37436	3	_	S37440	3	_	2x <sup>5</sup> S32562		
	Short terminal cover (4P)	4	_	_	_	_	_	4	_	2x <sup>5</sup> S32563		

<sup>1</sup> Kit contains four short rear connections, two long rear connections (four long rear connections for 4P), hardware and two terminal covers.

Table 119: L-Frame Rear Connection Hardware

Description	Cat. No.
Set of 4 M10 x 25 terminal screws and washers for one side.	S36967

#### **Mechanical Lugs**



Unit-mount H-, J-, and L-frame circuit breakers can be ordered with mechanical line and load side lugs. The standard lugs can be removed for the installation of compression-type lugs or bus connections. All lugs are UL Listed/CSA Certified for their proper application and marked for use with aluminum and copper (Al/Cu) or copper only (Cu) conductors. Lugs suitable for copper and aluminum conductors are made of tin-plated aluminum. Lugs suitable for use with copper conductors only are made of copper.

Mechanical Lugs for the H- and J-frame circuit breakers lay on top of the circuit breaker terminals and can be installed without the use of any tools. The lugs are held in place with snap features built into the insulating retainer and are secured with the clamp force applied to the wire binding screw.

Mechanical lugs are sold either factory installed or as field installable kits.

<sup>&</sup>lt;sup>2</sup> Order two kits (two in kit x two kits for total of four).

<sup>&</sup>lt;sup>3</sup> Parts only, no hardware is included. See Table 119, below.

<sup>&</sup>lt;sup>4</sup> For use with 3P circuit breakers only.

<sup>&</sup>lt;sup>5</sup> Order two kits (kit contains only one terminal cover, two terminal covers are required per circuit breaker).

Table 120: Mechanical Lug Kits for H-Frame and J-Frame Circuit Breakers

	Cir	cuit Breake	r Application	Number of Wires	Kit Cat.	Qty	
	Standard	Ampere Rating	Optional	Ampere Rating	Per Lug and Wire Range	No.	Per Kit
	HD, HG, HJ, HL	15-150 A			(1) 14-3/0 AWG Al or Cu	AL150HD	3
Al Lugs for Use with Al or Cu Wire	JD, JG, JJ, JL	150–175 A			(1) 4-4/0 AWG AI or Cu	AL175JD	3
With 7th Of Ou Willo	JD, JG, JJ, JL	200–250 A	JD,JG,JJ,JL	150–175 A	(1) 3/0-350 kcmil Al or Cu	AL250JD	3
Cu Lugs for Use			HD,HG,HJ,HL	15–150 A	(1) 14-2/0 AWG Cu	CU150HD	3
with Cu Wire Only			JD,JG,JJ,JL	150–250 A	(1) 1/0-300 kcmil Cu	CU250JD	3
Control Wire Terminal for H-frame lug kit							2
Control Wire Termin	nal for J-frame lug	kit				S37424	2

Table 121: Mechanical Lug Kits for L-Frame Circuit Breakers<sup>1</sup>

	Circui	t Break	er Appli	cation	Normhau of Wissa		Qty	Type of
	Ampere Rating	Poles	Unit Mount	I-Line	Number of Wires Per Lug and Wire Range <sup>2</sup>	Kit Cat No		Termina I Shield <sup>3</sup>
	050	3	Х	Х	(1) 2 AWG-500 kcmil AI	AL400L61K3	3	Short
	250	4	Х	_	(1) 2 AWG-600 kcmil Cu	AL400L61K4	4	Short
Al Lugs for Use with Al or Cu Wire	400/000	3	Х	_	(O) O/O AMO 500 bereil Al en Occ	AL600LS52K3	3	Medium
William Or Od Willo	400/600	4	Х	_	(2) 2/0 AWG–500 kcmil Al or Cu	AL600LS52K4	4	Medium
	400/600	3	Х	Х	(2) 3/0 AWG-500 kcmil Al or Cu	AL600LF52K3	3	Short
	050/400	3	Х	Х	(1) 2 AWG-500 kcmil Al	CU400L61K3	3	Short
	250/400	4	Х	_	(1) 2 AWG-600 kcmil Cu	CU400L61K4	4	Short
Cu Lugs for Use with Cu Wire Only	400/000	3	Х	_	(4) 0/0 4)4/0 500	CU600LS52K3	3	Medium
41	400/600	4	Х	_	(1) 2/0 AWG–500 kcmil Al or Cu	CU600LS52K4	4	Medium
	400/600	3	Х	Х	(1) 3/0 AWG-500 kcmil Al or Cu	CU600LF52K3	3	Short

<sup>&</sup>lt;sup>1</sup> For lug pack information, see Figure 31 on page 160.

# Voltage Takeoff (Control Wire Terminals) for Mechanical Lugs and Terminal Nuts


Powerpact H- and J-Frame mechanical lugs may be equipped with a separate control wire termination. The kit is available factory installed or as a field installable kit. The adaptor is secured underneath the lug and has a tab extension suitable for attachment of a 0.250 inch slip-on connector.

All L-frame mechanical lugs are pre-tapped for control wires. For control wire installation, use an 8-32 x 1/4 in. screw (not provided) into tapped control wire hole in lower left hand corner of the lug.

Fully insulated type connectors must be used to prevent live parts from extending into the wiring gutter area.



Description	Frame	Cat. No.	Qty Per Kit	
Mechanical Lugs				
Control Wire Terminal for H-Frame Lugs	HD/HG/HJ/HL	S37423	2	
Control Wire Terminal for J-Frame Lugs	JD/JG/JJ/JL	S37424	2	
Busbar Connection	•	•		
Control Wire Terminal for H-Frame Terminal Nut	HD/HG/HJ/HL	S37429	2	
Control Wire Terminal for J-Frame Terminal Nut	JD/JG/JJ/JL	S37430	2	





Mechanical Lug Control

Control


Wire Hole

Wire Terminal

<sup>&</sup>lt;sup>2</sup> For control wire installation, use an 8-32 x 1/4 in. screw (not provided) into tapped control wire hole in lower left hand corner of lug.

<sup>&</sup>lt;sup>3</sup> For terminal shield dimensions, see Figure 31 on page 160.

#### **Bus-Bar Connections**



The H-, J- and L-frame circuit breakers may be equipped with captive nuts and screws for direct connection to bars or to compression (crimp) lugs

For H- and J-frame, these are readily field-installable, simply by removing the mechanical lug and replacing with the appropriate terminal nut inset described in Table 123. They are also available factory-installed, using the Product Selector or by using the catalog suffixes below.

For L-frame, the mechanical lug can be removed, leaving the threaded nut insert intact. This configuration may be ordered with the suffixes described below. Connection hardware (terminal screws) must be ordered as in table 123.

Table 123: Factory-Installed Terminal Nut Inserts for Bus or Crimp Lug Connection

Cat. No. Termination (Position 4)	Special Terminations Options	Description
F		Terminal nut insert on both ends; no lugs either end
M		Terminal nut insert on OFF end; lugs on ON end only
Р		Terminal nut insert on ON end; lugs on OFF end only
A	-TA	I-Line on ON end; English terminal nuts on OFF end1
A	-TB	I-Line on ON end; Metric terminal nuts on OFF end1
F, M, or P	-TW	For -F-, Metric terminal nuts on both ends <sup>1</sup>
F, M, or P	-TX	For -M, lugs on ON end; Metric terminal nuts on OFF end For -P, Metric terminal nuts on ON end; lugs on OFF end

<sup>&</sup>lt;sup>1</sup> For H- and J-frame only. L-frame terminal nuts are metric only.







Table 124: Terminal Nuts for Bus Bar Connection of H-Frame and J-Frame Circuit Breakers

Description <sup>1</sup>	Frame	Тар	Cat. No.	Qty Per Kit	Torque		
H-Frame Terminal Nut Insert-English	HD/HG/HJ/HL	1/4-20	S37425	2			
H-Frame Terminal Nut Insert-English	HD/HG/HJ/HL	1/4-20	S37444	3	80–90 lb-in (9–10.2 N•m)		
H-Frame Terminal Nut Insert-Metric	HD/HG/HJ/HL	M6	S37426	2	(9-10.2 (4-111)		
J-Frame Terminal Nut Insert-English	JD/JG/JJ/JL	1/4-20	S37427	2			
J-Frame Terminal Nut Insert-English	JD/JG/JJ/JL	1/4-20	S37445	3	80–90 lb-in (9–10.2 N•m)		
J-Frame Terminal Nut Insert-Metric	JD/JG/JJ/JL	M8	S37428	2	(9-10.2 N•III)		

Screws not included.

Table 125: Bar Dimensions

Dimension	H-Frame	J-Frame	L-Frame
A	0.250 in.	0.3125 in.	0.4 in.
	(6.4 mm)	(7.9 mm)	(10 mm)
В	0.125–0.375 in.	0.125–0.375 in.	0.11–0.39 in.
	(3.2–9.5 mm)	(3.2–.5 mm)	(3–10 mm)
С	0.50 in.	0.50–0.75 in.	1.35 in.
	(12.7 mm)	(12.7–1.1 mm)	(32 mm)
D	0.3 in.	0.625 in.	<0.51 in.
	(7.6 mm)	(15.9 mm)	13 mm)
Е	0.3 in.	0.375 in.	0.64 in.
	(7.6 mm)	(9.5 mm)	(16 mm)





Table 126: L-Frame Bus Bar Connections Hardware

Description	Cat. No.
Set of 4 M10 x 25 terminal screws and washers for one side.	S36967





The power distribution connectors (PDC) can be used for multiple load wire connections on one circuit breaker. Use in place of standard distribution blocks to save space and time. Field installable kit includes tin-plated aluminum lug, connectors, and required mounting hardware.

- For use on load end of circuit breaker only
- For use in UL 508 Industrial Control applications
- For use in UL 1995/CSA C22.2 No. 236 heating and cooling equipment
- For copper wire only

**Table 127: Power Distribution Connectors** 

Frame		Kit Number	Qty per Kit	Wires per Terminal	Wire Range	Wire Binding Screw Torque
		PDC6HD6	1	6	8–6 AWG (10–16 mm <sup>2</sup> )	25 lb-in (2.8 N•m)
H-Frame		РОСОПО	'	0	14–10 AWG (2.5–6 mm <sup>2</sup> )	20 lb-in (2.3 N•m)
TI-TTAITIE	THE	PDC3HD2	1	3	2 AWG (35 mm <sup>2</sup> )	40 lb-in (4.5 N•m)
	I DOSTID2	'	3	14–3 AWG (2.5–35 mm <sup>2</sup> )	35 lb-in (4.0 N•m)	
		PDC6JD4	1	6	8–4 AWG (10–25 mm <sup>2</sup> )	35 lb-in (4.0 N•m)
		FDC03D4	'	0	14–10 AWG (2.5–6 mm <sup>2</sup> )	20 lb-in (2.3 N•m)
J-Frame	J-Frame			3 total	14–6 AWG Cu (2.5–16 mm <sup>2</sup> ) or	35 lb-in (4.0 N•m)
		PDC3JD20	1	2	4–1 AWG Cu (25–50 mm <sup>2</sup> )	40 lb-in (4.5 N•m)
				and 1	3–2/0 AWG Cu (35–70 mm <sup>2</sup> )	50 lb-in (5.6 N•m)
				5 total	4–1 AWG (25–50 mm <sup>2</sup> ) or	40 lb-in (4.5 N•m)
		PDC5DG20L3 1	3	3 000	14–6 AWG (2.5–16 mm <sup>2</sup> )	35 lb-in (4.0 N•m)
L-Frame	L-Frame			and 2	3–2/0 AWG (35–70 mm <sup>2</sup> )	50 lb-in (5.6 N•m)
					8–4 AWG (10–25 mm <sup>2</sup> )	35 lb-in (4.0 N•m)
		PDC12DG4L3 <sup>1</sup>	3	12	14–10 AWG (2.5–6 mm²)	20 lb-in (2.3 N•m)

<sup>&</sup>lt;sup>1</sup> Kit includes terminal shield.

See Table 130 for the phase barriers for power distribution connectors.

All Rights Reserved

## **Compression Lugs**

Both copper and aluminum compression lug kits are available for the H-, J-, and L-frame circuit breakers. Each kit contains required insulators and all mounting hardware. Compression lugs require the long lug cover pack, see Figure 31 on page 160.




Table 128: Compression Lug Kits for Al/Cu Connectors

Circuit	Lug Kit	Rating	at 75°C	Poles	Wires	Wire Range	Lugs per	Lugs
Breaker	Lug Kit	Al	Cu	Poles	per Lug	wire halige	Terminal	per Kit
Al/Cu Cor	nectors	_					_	
H-Frame	YA060HD	≤ 60 A	≤ 60 A	3	1	6–2 AWG Cu or AI (16–35 mm²)	1	3
YA150HD		≤ 150 A	≤ 150 A	3	1	1/0-4/0 AWG Cu or Al (50-95 mm <sup>2</sup> )	1	3
J-Frame	YA150JD	≤ 200 A	≤ 200 A	A 3 1		1–3/0 AWG Cu or Al (50–95 mm²)	2	3
J-Frame	YA250J35	≤ 250 A	≤ 250 A	3	1	3/0 AWG-350 kcmil Cu or AI (95-185 mm²)	2	3
	YA400L31K3	230 A	285 A	3	1	4-300 kcmil Al/Cu (25–150 mm²)	1	3
	YA600L32K3	460 A	570 A	3	2	4-300 kcmil A/Cu (25–150 mm²)	2	6
	YA400L51K3	310 A	380 A	3	1	2/0-500 kcmil A/Cu (70–240 mm²)	1	3
	YA600L52K3	620 A	760 A	3	2	2/0-500 kcmil Al/Cu (70–240 mm <sup>2</sup> )	2	6
L-Frame	YA400L71K3	385 A	475 A	3	1	500-750 kcmil A (240–400 mm²)I 500 kcmil Cu (240 mm²)	1	3
	YA600L32K4	460 A	570 A	4	2	4-300 kcmil A/Cu (25–150 mm²)	1	8
	YA400L51K4	310 A	380 A	4	1	2/0-500 kcmil Al/Cu (70–240 mm²)	2	4
	YA600L52K4	620 A	760 A	4	2	2/0-500 kcmil Al/Cu (70–240 mm²)	1	8
	YA400L71K4	385 A	475 A	4	1	500-750 kcmil Al (240–400 mm²) 500 kcmil Cu (240 mm²)	2	4

Table 129: Compression Lug Kits for Cu Connectors

Circuit	Lug Kit	Rating	@ 75 C	Poles	Wires	Wire Range	Lugs per	Lugs
Breaker	Lug Kit	Al	Cu	Foles	per Lug	Wife halige	Terminal	per Kit
H-Frame	CYA060HD	_	≤ 60 A	3	1	6–1/0 AWG Cu (16–50 mm <sup>2</sup> )	1	3
TH TAINE	CYA150HD	_	≤ 150 A	3	1	4–2/0 AWG Cu (25–70 mm <sup>2</sup> )	1	3
J-Frame	CYA150JD	_	≤ 150 A	3	1	4–2/0 AWG Cu (25–70 mm <sup>2</sup> )	2	3
J-i raine	CYA250J3	_	≤ 250 A	3	1	2/0 AWG-300 kcmil Cu (70-185 mm²)	2	3
	CYA400L31K3	_	285 A	3	1	2/0-300 kcmil Cu (70–150 mm²)	1	3
	CYA600L32K3	_	570 A	3	2	2/0-300 kcmil Cu (70–150 mm <sup>2</sup> )	2	6
	CYA400L51K3	_	380A	3	1	250-500 kcmil Cu (150–240 mm²)	1	3
	CYA600L52K3	_	760A	3	2	250-500 kcmil Cu (150–240 mm²)	2	6
L-Frame	CYA400L71K3	_	475 A	3	1	500-750 kcmil AI (240–400 mm²) 500 kcmil Cu (240 mm²)	1	3
	CYA400L31K4	_	285A	4	1	2/0-300 kcmil Cu (70–150 mm²)	1	4
	CYA600L32K4	_	570 A	4	2	2/0-300 kcmil Cu (70–150 mm <sup>2</sup> )	2	8
	CYA400L51K4	_	380 A	4	1	250-500 kcmil Cu (150–240 mm²)	1	4
	CYA600L52K4	_	760 A	4	2	250-500 kcmil Cu (150–240 mm²)	2	8

#### **Terminal Shields**





Table 130: Terminal Shields and Phase Barriers



Used With		Descr	iption			Dimension B	Cat. No.	Qty Per Kit
		Frame		Max.	Vire Size			
H- and J-Frame	Short Lug	H-Frame 60 A		3 AWG		0.50 in.	S37446	1
Mechanical Lugs	echanical Lugs Shield	H-Frame 150 A	4	3/0 A\	VG	0.50 in.	S37447	1
	J-Frame			350 kcmil		0.24 in.	S37448	1
		Compatible with:						
		PDC	Compression L		Lugs			
H- and J-Frame Power		FDC	Aluminu		Copper			
Distribution Connectors	H-Frame Long	PDC6HD6	YA060	HD	CYA060HD	2.24	S37449	1
and Compression Lugs	Lug Shield	PDC3HD2	YA150	HD	CYA150HD	2.24	337449	'
	J-Frame Long Lug Shield	PDC6JD4	DC6JD4 YA150J		CYA150JD	1.68	S37450	1
		PDC3JD2			CYA250J3	1.00	337430	'

NOTE: L-frame terminal shields are shipped with the mechanical lug kits, see Table 121.

#### Section 10—Installation Recommendations

# **Operating Conditions**


#### **Temperature Derating**

- PowerPact<sup>™</sup> H-, J-, and L-frame circuit breakers may be used between -13°F and 158°F (-25 °C and +70 °C). For temperatures higher than 104° F (40° C°) inside the enclosure, devices must be derated.
- Circuit breakers should be put into service under normal ambient, operating-temperature conditions.
- The permissible storage-temperature range for PowerPact H-, J-, and L-frame circuit breakers in the original packing is -58°F¹ and 185°F (-50 °C¹ and +85 °C).

Table 131: Temperature Derating for H-Frame Trip Unit Thermal Protection—Long-Time

Temp	erature <sup>1</sup>	Potir	Rating (A) I <sub>n</sub>														
°C	°F	naui	ig (A)	'n													
-10	14	23	30	38	46	53	60	68	76	88	103	112	123	137	160	180	221
0	32	21	28	36	43	49	56	63	71	83	97	107	117	131	151	171	207
10	50	20	26	33	40	46	52	59	66	77	90	101	111	126	141	161	194
20	68	18	24	31	37	42	48	54	62	72	84	96	105	120	132	152	180
30	86	17	22	28	34	39	44	50	56	66	77	88	98	110	121	139	165
40	104	15	20	25	30	35	40	45	50	60	70	80	90	100	110	125	150
50	122	12	17	21	25	30	34	38	43	53	62	72	80	86	95	109	131
60	140	9	14	17	20	24	28	31	35	46	53	63	70	72	80	93	111

Shaded areas indicate temperature rerated values, non-shaded areas inside an enclosure are standard circuit breaker ampere ratings at 104° F (40° C°).



#### **H-Frame Trip Curve**

- (I<sub>n</sub>) Fixed threshold thermal protection against overload
- (I<sub>i</sub>) **Fixed** threshold instantaneous protection against short circuits

1

J-Frame Trip Unit

- (I<sub>n</sub>) Fixed threshold thermal protection against overload
- (I<sub>m</sub>) Adjustable instantaneous protection against short circuits

Table 132: Temperature Derating for J-Frame Trip Unit Thermal Protection—Long-Time

Tempe	erature <sup>1</sup>	Detino (A) I								
°C	°F	Rating (A) I <sub>n</sub>	ung (A) I <sub>n</sub>							
-10	14	221	264	289	330	377				
0	32	207	247	273	310	354				
10	50	194	230	256	290	330				
20	68	180	213	240	270	307				
30	86	165	194	220	248	279				
40	104	150	175	200	225	250				
50	122	131	150	176	193	214				
60	140	111	124	151	160	177				

<sup>1</sup> Shaded areas indicate temperature rerated values, non-shaded areas are standard circuit breaker ampere ratings at 104° F (40° C°).

<sup>&</sup>lt;sup>1</sup> -40°F (-40 °C) for Micrologic trip units with an LCD screen.



# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Installation Recommendations

PowerPact H-, J- and L-Frame Circuit Breakers Equipped with Electronic Trip Units

Electronic trip units are not affected by variations in temperature. If the trip units are used in high-temperature environments, the Micrologic<sup>™</sup> trip unit setting must nevertheless take into account the temperature limits of the circuit breaker.

Changes in temperature do not affect measurements by electronic trip units.

- The built-in CT sensors with Rogowski coils measure the current.
- The control electronics compare the value of the current to the settings defined for 104°F (40°C).

Because temperature has no effect on the CT measurements, the tripping thresholds do not need to be modified.

However, the temperature rise caused by the flow of current combined with the ambient temperature increases the temperature of the device. To avoid reaching the thermal withstand value, it is necessary to limit the current flowing through the device, that is the maximum  $I_r$  setting as a function of the temperature.

The table below indicates the maximum long-time (LT) protection setting  $I_r$  (A) depending on the ambient temperature.

Table 133: Derating Circuit Breakers with Micrologic Trip Units

		Tempe	ature						
Type of Device	Rating	104°F (40°C)	113°F (45°C)	122°F (50°C)	131°F (55°C)	140°F (60°C)	149°F (65°C)	158°F (70°C)	
H-Frame		•	•	•	•		•	•	
	60 A	No derat	ng						
Unit-mount, plug-in or drawout	100 A	No derating							
	150 A	No derating							
J-Frame									
Unit-mount	250	250	250	250	245	237	230	225	
Plug-in or drawout	250	250	245	237	230	225	220	215	
L-Frame									
Unit-mount	400	400	400	400	390	380	370	360	
Plug-in or drawout	400	400	390	380	370	360	350	340	
Unit-mount	600	600	600	600	585	570	550	535	
Plug-in or drawout	600	570	550	535	520	505	490	475	

Example. A unit-mount PowerPact L-frame circuit breaker equipped with a Micrologic can have a maximum I<sub>r</sub> setting of:

- 400 A up to 122°F (50 °C)
- 380 A up to 140°F (60 °C)

#### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Installation Recommendations

# 2000 M

#### **Altitude Derating**

Altitude does not significantly affect the characteristics of PowerPact H-, J-, and L-frame circuit breakers circuit breakers up to 6560 ft (2000 m). Above this altitude, it is necessary to take into account the decrease in the dielectric strength and cooling capacity of air.

The following table gives the corrections to be applied for altitudes above 6560 ft (2000 m). The breaking capacities remain unchanged.

Table 134: Altitude Derating

Altitude		6560 ft (2000 m)	9840 ft (3000 m)	13120 ft (4000 m)	16400 ft (5000 m)
Dielectric withstand voltage		3000 V	2500 V	2100 V	1800 V
Insulation voltage	Vi	800 V	700 V	600 V	500 V
Maximum operational voltage	V <sub>e</sub>	690 V	590 V	520 V	460 V
Average current capacity (A) at 104°F (40°C)	I <sub>n</sub> x	1 0.	0.96	0.93	0.9

#### 400 Hz Derating

Application of H- and J-frame circuit breakers at frequencies above 60 Hz requires that special consideration be given to the effects of high frequency on the circuit breaker characteristics. Thermal and instantaneous operations must be treated separately.

At frequencies below 60 Hz, the thermal derating of PowerPact H and J-frame circuit breakers is negligible. However, at frequencies above 60 Hz, thermal derating is required.

One of the most common high frequency applications is at 400 Hz.


Table 135: 400 Hz Derating

Circuit Breaker	400 Hz Derating Multiplier
H-Frame	0.90
J-Frame	0.90
L-Frame, 400 A	0.80
L-Frame, 600 A	0.65

For more information, refer to Data Bulletin 0100DB0101, *Determining Current Carrying Capacity in Special Applications*.

#### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Installation Recommendations

# **Installation in Equipment**



#### **Power from the Top or Bottom**

PowerPact H-, J-, and L-frame circuit breakers with factory-sealed trip units can be supplied from either the top or the bottom without any reduction in performance. This capability facilitates connection when installed in end-use equipment.

All connection and insulation accessories can be used on circuit breakers supplied either from the top or bottom.

#### Weight

The table below presents the weights of the circuit breakers and the main accessories, which must be summed to obtain the total weight. The values are valid for all performance categories.

Table 136: Weights

Type of Device		Circuit Breakers	Base	Cradle	Motor Operator
H-frame, 100 A	2P	3.95 lb (1.79 kg)	1.75 lb (0.8 kg)	4.85 lb (2.2 kg)	2.65 lb (1.2 kg)
	3P	4.52 lb (2.05 kg)	1.75 lb (0.8 kg)	4.85 lb (2.2 kg)	2.65 lb (1.2 kg)
H-frame, 150 A	2P	4.08 lb (1.85 kg)	1.75 lb (0.8 kg)	4.85 lb (2.2 kg)	2.65 lb (1.2 kg)
	3P	4.85 lb (2.2 kg)	1.75 lb (0.8 kg)	4.85 lb (2.2 kg)	2.65 lb (1.2 kg)
J-frame, 250 A	3P	5.29 lb (2.4 kg)	1.75 lb (0.8 kg)	4.85 lb (2.2 kg)	2.65 lb (1.2 kg)
L-frame, 600 A	3P	13.65 lb (6.19 kg)	5.29 lb (2.4 kg)	4.85 lb (2.2 kg)	6.17 lb (2.8 kg)
	4P	17.92 lb (8.13 kg)	6.17 lb (2.8 kg)	4.85 lb (2.2 kg)	6.17 lb (2.8 kg)

# **Safety Clearances and Minimum Distances**

#### **General Rules**

When installing a circuit breaker, minimum distances (safety clearances) must be maintained between the device and panels, bars and other protection devices installed nearby. These distances, which depend on the voltage, are defined by tests carried out in accordance with UL standards.

If installation is not checked by type tests, it is also necessary to:

- · use insulated bars for circuit-breaker connections
- segregate the busbars using phase barriers

For PowerPact H-, J-, and L-frame devices, terminal shields and interphase barriers are recommended and may be mandatory depending on the operating voltage of the device and type of installation (unit-mount, drawout, etc.).

#### **Power Connections**


The table below indicates the connection requirements for PowerPact H-, J-, and L-frame devices to ensure insulation of live parts for the various types of connection.

- unit-mount devices with front connection or rear connection
- plug-in or drawout devices.

Connection accessories such as crimp lugs, terminal extensions (straight, right-angle, double-L and 45°) and spreaders are supplied with interphase barriers. Long terminal shields provide a degree of protection of IP40 (ingress).


# **Safety Clearance**

#### **Safety Clearances**




If dimension A < 0.56 in. for H- and J-frame circuit breaker, attach fiber insulating plate, not provided, to enclosure cover.

#### H- and J-Frame Fiber Insulating Plate




#### **Enclosure Dimensions**



Minimum enclosure insulation required if circuit breaker side < 4.13 in. (105 mm) from metal.

#### J-Frame Minimum Enclosure Insulation



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Installation Recommendations

**Table 137: Minimum Safety Clearances** 

	Clearance	Clearance						
Operating Voltage	Between	Between Device and Sheet Metal						
	Devices	Painted Sheet Metal		Bare Sheet Metal				
V ≤ 440 V for devices equipped with:								
No accessories	0	0	30	30	5	40	40	
<ul> <li>Interphase barriers</li> </ul>	0	0	0	0	0	0	0	
<ul> <li>Long terminal shields</li> </ul>	0	0	0	0	0	0	0	
440 < V ≤ 600 for devices equipped with:								
<ul> <li>Interphase barriers<sup>1</sup></li> </ul>	0	0	0	0	20	10	10	
Long terminal shields	0	0	0	0	10	10	10	
V > 600 V for devices equipped with:								
<ul> <li>Long terminal shields</li> </ul>	0	10	50	50	20	100	100	

<sup>1</sup> Only for J-frame devices.

# **Clearances with Respect to Live Bare Busbars**

Table 138: Minimum Safety Clearances to Bare Busbars

Operating Voltage	Clearances to Live Bare Busbars <sup>1</sup>				
Operating voltage	Spacing ≤ 60 mm		Spacing > 60 mm		
V ≤ 440 V	350	350	80	80	
440 V < V ≤ 600 V	350	350	120	120	

<sup>1</sup> These clearances can be reduced for special installations as long as the configuration is checked by tests.

# **Control Wiring**

## Remote Tripping by Undervoltage Trip (MN) or Shunt Trip (MX)

Power requirements are approximately:

- 30 VA for pick-up of the undervoltage trip (MN) and shunt trip (MX)
- 300–500 VA for the motor operator.


Table 139: Recommended Maximum Cable Lengths<sup>1</sup>

Power Supply Voltage (Vdc)		12 Vdc		24 Vdc		48 Vdc	
Cable cross-section		16 AWG (1.5 mm²)	14 AWG (2.5mm²)	16 AWG (1.5 mm²)	14 AWG (2.5mm²)	16 AWG (1.5 mm²)	14 AWG (2.5mm²)
Undervoltage	V source 100%	49 ft (15 m)	_	525 ft (160 m)	_	2100 ft (640 m)	_
Trip (MN)	V source 85%	23 ft (7 m)	_	131 ft (40 m)	_	525 ft (160 m)	_
Shunt Trip	V source 100%	197 ft (60 m)	_	787 ft (240 m)	_	3150 ft (960 m)	_
(MX)	V source 85%	98 ft (30 m)	_	394 ft (120 m)	_	1575 ft (480 m)	_
NIOLOI .	V source 100%		_	33 ft (10 m)	16 m)	213 ft (65 m)	361 ft (110 m)
	V source 85%	_	_	6.6 ft (2 m)	4 m)	56 ft (17 m)	82 ft (25 m)

<sup>&</sup>lt;sup>1</sup> The indicated length is that of each of the two wires.

#### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Installation Recommendations

#### **External Neutral Voltage Tap (ENVT)**




This connection is required for accurate power measurements on 3-pole circuit breakers equipped with Micrologic 5 / 6 E trip units in installations with a distributed neutral. It can be used to measure phase-neutral voltages and calculate power using the 3 wattmeter method.

PowerPact H-, J-, and L-frame 3-pole circuit breakers come with a wire installed on the device for the connection to the ENVT. This wire is equipped with a connector for connection to an external wire with:

- cross-sectional area of 18–14 AWG (1 mm² to 2.5 mm²)
- maximum length of 32.8 ft (10 m).

#### **External Neutral Current Transformer (ENCT)**



This connection is required to protect the neutral on 3-pole circuit breakers equipped with Micrologic 5 / 6 A or E trip units in installations with a distributed neutral. For Micrologic 6 A or E, it is required for ground-fault protection.

The ENCT is connected in the same way for unit-mount, plug-in or drawout devices:

- unit-mount devices are connected using terminals T1 and T2 of the internal terminal block.
- plug-in and drawout devices are not connected using the auxiliary terminals.


The wires must be connected/disconnected inside the devices using terminals T1 and T2.

The ENCT must be connected to the Micrologic trip unit by a shielded twisted pair. The shielding should be connected to the enclosure earth only at the CT end, no more than 12 in. (30 cm) from the CT.

- the power connections of the CT to the neutral (H2 and H1) must be made in the same way for power supply from the top or the bottom (see figure). Make sure they are not reversed for devices with power supply from the bottom.
- cross-sectional area of 22–16 AWG (0.4 mm² to 1.5 mm²)
- maximum length of 32.8 ft (10 m).

#### PowerPact™ H-, J-, and L-Frame Circuit Breakers Installation Recommendations

#### ULP Connection System Between Micrologic, FDM121 Module and Modbus™ Interface



ULP connection system.

The ULP (Universal Logic Plug) wiring system used by H-, J- and L-frame circuit breakers for connection through the Modbus network requires neither tools nor settings. The prefabricated cables are used for both data transfer and distribution of 24 Vdc power. Connectors on each component are identified by ULP symbols, ensuring total compatibility between each component.

A line terminator must be fitted to all components with an unused RJ45 connector.

Table 140: Available Cables


Cable	Available Lengths
NSX cord for connection of the internal terminal block to the Modbus	4.27 ft (1.3 m)
interface or the FDM121 display using an RJ45 connector.	9.84 ft (3 m)
	0.98 ft (0.3 m)
ULP cables with RJ45 connectors at each end for the other	1.97 ft (0.6 m)
connections between ULP wiring components	3.28 ft (1 m)
For greater distances, two cables can be interconnected using the RJ45 female/ female connector. Maximum length of 32.8 ft (10 m)	2.56 ft (2 m)
between 2 modules and 98.4 ft (30 m) in all.	9.84 ft (3 m)
	16.4 ft (5 m)

# 24 Vdc Power Supply Module


An external 24 Vdc power supply is required for installations with communication networks, regardless of the type of trip unit.

On installations without communication networks, the power supply is available as an option for Micrologic 5/6 to:

- modify settings when the circuit breaker is open (OFF position)
- display measurements when the current flowing through the circuit breaker is low
- maintain the display of the cause of tripping.




Power supply, without the Communication function, using the terminal block with a backup battery.



Power supply, with the communication function, using the Modbus interface.

To determine power requirements of devices, see page 84.

#### Wiring



- 1 Modbus interface module with connection accessory.
- 2 24 Vdc power supply of Micrologic for Powerpact H-, J-, and L-Frame communication modules.
- 3 ULP cord.
- 4 NSX cord.
- 5 Modbus cable + 24 Vdc part no. 50965 (Schneider Electric) recommended or part no. 7895A (Belden).
- 6 24 Vdc power supply of Micrologic for PowerPact M-Frame/ Masterpact circuit breakers.

#### Micrologic 5 or 6 Without the Communication Function

The external 24 Vdc supply is connected through the circuit breaker terminal block.

Use of a 24 Vdc battery provides backup power for approximate 3 hours (100 mA) in the event of an interruption in the external supply.

#### Micrologic 5 or 6 With the Communication Function

The external 24 Vdc supply is connected through the Modbus interface using a five-pin connector, including two for the power supply. Stacking accessories (see page 81) can be used to supply a number of interfaces by fast clip-on connection.

The 24 Vdc power is distributed downstream by the ULP (Universal Logic Plug) communication cables with RJ45 connectors. This system ensures both data transfer and power distribution to the connected modules.

#### **Recommendations for 24 Vdc Wiring**

Do not connect the positive terminal to ground

- Do not connect the negative terminal to ground.
- The maximum length for each conductor (+/-) is 33 ft (10 m).
- For connection distances greater than ten metres, the plus and minus conductors of the 24 Vdc supply must be twisted to improve EMC.
- The 24 Vdc conductors must cross the power cables perpendicularly. If this is difficult or impossible, the plus and minus conductors must be twisted.



#### PowerPact™ H-, J-, and L-Frame Circuit Breakers **Installation Recommendations**

#### **Modbus**

Each PowerPact H-, J-, and L-frame circuit breaker equipped with Micrologic 5/6 and an FDM121 display is connected to the Modbus network using the Modbus com module. Connection of all the circuit breakers and other Modbus devices in the equipment to a Modbus bus is made much easier by using a Modbus RJ45 junction block installed in the equipment.

Recommendations for Modbus Wiring:


- The shielding may be grounded on one end only
- The conductors must be twisted to improve immunity (EMC)
- The Modbus conductors must cross the power cables perpendicularly

A unit-mount PowerPact L-frame circuit breaker with a Micrologic trip unit can have a maximum I<sub>r</sub> setting of:

- 400 A up to 122°F (50 °C)
- 380 A up to 140°F (60 °C)

# **Section 11—Wiring Diagrams**

#### **Unit-Mount Circuit Breakers**




**Communicating Motor Operator** 

Continued on next page

#### PowerPact™ H-, J-, and L-Frame Circuit Breakers **Wiring Diagrams**

#### **Unit-Mount Circuit Breakers** (continued)

#### **Indication Contacts**



The diagram is shown with circuits de-energized, relays in normal position, and all devices open, connected, and charged.

Terminal connections shown as O must be connected by the customer.

Micrologic Trip Unit A or E				
	Communication			
A/E	H (WH), L(BL): data			
	-(BK), +(RD): 24 Vdc power supply			
	ZSI (Zone Selective Interlocking)			
	Z1: ZSI OUT SOURCE			
	Z2: ZSI OUT			
A/E	Z3: ZSI IN SOURCE			
	Z4: ZSI IN ST (short time)			
	Z5: ZSI IN GF (ground fault)			
	(Z3, Z4, and Z5 for L-frame circuit breaker only)			
ENCT: External Neutral Current Transformer: -Shielded cable with 1 twisted pair (T1, T2) -Shielding earthed at CT end only  A/E Connection L = 12 in. (30 cm) maxMaximum length of 33 ft (10 m) -Cable size of 22 AWG -Recommended cable: Belden 9451SB or equiva				
E	ENVT: External Neutral Voltage Tap for Connection to the Neutral using a 3P Circuit Breaker			

#### **Color Code for Auxiliary Wiring**

RD: Red VI: Violet WH: White GY: Gray YE: Yellow OR: Orange BK: Black BL: Blue

GN: Green

Remote	Operation
MN	Underv

oltage Release

or MX

#### **Motor Operator**

Α4 Opening Order **A2** Closing Order

B4, A1 Power Supply to Motor Operator

Shunt Release

Manual Position (manu) L1 B2 Overcurrent Trip Switch Interlocking (mandatory for correct operation)

вро Opening Pushbutton

**BPF** Closing Pushbutton

#### **Communicating Motor Operator**

B4, A1 Motor Operator Power Supply **BSCM** Breaker Status and Control Module

#### **Indication Contacts**

OF2/OF1 Device ON/OFF Auxiliary Switches

OF3 Device ON/OFF Auxiliary Switches (L-Frame)

SDE Overcurrent Trip Switch


(short-circuit, overload, ground fault, earth leakage)

SD Alarm Switch

CAF2/CAF1 Early-Make Contact (rotary handle only) **CAO1** Early-Break Contact (rotary handle only)




## **Plug-In and Drawout Circuit Breakers**



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Wiring Diagrams

## Plug-In and Drawout Circuit Breakers (continued)



**Remote Operation** 

The diagram is shown with circuits de-energized, relays in normal position, and all devices open, connected, and charged.

Terminal connections shown as  $\square$  and O must be connected by the customer.

Micrologic Trip Unit A or E			
	Communication		
A/E	H (WH), L(BL): data		
	-(BK), +(RD): 24 Vdc power supply		
	ZSI (Zone Selective Interlocking)		
	Z1: ZSI OUT SOURCE		
	Z2: ZSI OUT		
A/E	Z3: ZSI IN SOURCE		
	Z4: ZSI IN ST (short time)		
	Z5: ZSI IN GF (ground fault)		
	(Z3, Z4, and Z5 for L-frame circuit breaker only)		
A/E	ENCT: External Neutral Current Transformer: -Shielded cable with 1 twisted pair (T1, T2) -Shielding earthed at CT end only Connection L = 12 in. (30 cm) maxMaximum length of 33 ft (10 m) -Cable size of 22 AWG -Recommended cable: Belden 9451SB or equivalent		
E	ENVT: External Neutral Voltage Tap for Connection to the Neutral using a 3P Circuit Breaker		
Color Code	for Auxiliary Wiring		
RD: Red	VI: Violet		
\\/ ⊢ \\/hito	GV: Gray		

RD: Red VI: Violet
WH: White GY: Gray
YE: Yellow OR: Orange
BK: Black BL: Blue

GN: Green

01/2014

MN	Undervoltage Release		
or			
MX	Shunt Release		
Motor Opera	ator		
A4	Opening Order		
A2	Closing Order		
B4, A1	Power Supply to Motor Operator		
L1	Manual Position (manu)		
B2	Overcurrent Trip Switch Interlocking (mandatory for correct operation)		
ВРО	Opening Pushbutton		
BP	Closing Pushbutton		
Communicating Motor Operator			
B4, A1	Motor Operator Power Supply		
BSCM	Breaker Status and Control Module		
Indication Contacts			
OF2/OF1	Device ON/OFF Auxiliary Switches		
OF3	Device ON/OFF Auxiliary Switches (L-Frame)		
SDE	Overcurrent Trip Switch (short-circuit, overload, ground fault, earth leakage)		
SD	Alarm Switch		

CAF2/CAF1 Early-Make Contact (rotary handle only)

Early-Break Contact (rotary handle only)

CAO1


#### **Motor Operator**

**NOTE:** The diagram is shown with circuits de-energized, relays in normal position, and all devices open, connected, and charged.


After tripping initiated by the "Push to trip" button, the undervoltage release (MN), or the shunt release (MX), device can be reset automatically, remotely, or manually.

Following tripping due to an electrical fault, reset must be carried out manually.

#### **Motor Operator with Automatic Reset**



#### **Motor Operator with Remote Reset**



#### **Symbols**

Q: Circuit BreakerA4: Opening OrderA2: Closing Order


B4, A1: Motor Operator Power SupplyL1: Manual Position (manu)

B2: Overcurrent Trip Switch Interlocking (mandatory for correct operation)

BPO: Opening Pushbutton
BPF: Closing Pushbutton
SDE: Fault-Trip Indication Contact

(short-circuit, overload, ground fault, earth leakage)

#### **Motor Operator with Manual Reset**



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Wiring Diagrams


#### **Motor Operator** (continued)

#### **Symbols**

Q: Circuit Breaker


**B4, A1:** Motor Operator Power Supply **BSCM:** Breaker Status and Control Module

#### **Communicating Motor Operator**



Schematic of the communicating motor operator .

#### **RSU Screen for Communicating Motor Operator**



Single-line diagram of communicating motor operator

Opening, closing and reset orders are transmitted through the communication network. The "Enable automatic reset" and "Enable reset even if SDE" parameters must be set using the RSU software using the screen by clicking the blue text.

"Auto/Manu" is a switch on the front of the motor operator.

Terminal connections shown as O must be connected by the customer.

## **SDx Module with Micrologic™ Trip Unit**

**NOTE:** The diagram is shown with circuits deenergized, relays in normal position, and all devices open, connected, and charged.


#### Symbols

SD1, SD3: SDx Module Power Supply SD2: Output 1 (80 mA max.) SD4: Output 2 (80 mA max.)


	SD2	SD4
Micrologic 3	SDT	_
Micrologic 5	SDT or Output 1	PAL I <sub>r</sub> or Output 2
Micrologic 6	SDT or Output 1	SDG or Output 2

Terminal connections shown as O must be connected by the customer.

#### Connection



#### Operation



I: Charge Current

PAL I<sub>r</sub>: Thermal Overload Pre-Alarm SDG: Ground-Fault Signal

SDT: Thermal-Fault Signal
Q: Circuit Breaker



## PowerPact™ H-, J-, and L-Frame Circuit Breakers **Wiring Diagrams**

## **SDTAM Module with Micrologic M Trip Unit**

NOTE: The diagram is shown with circuits deenergized, relays in normal position, and all devices open, connected, and charged.


#### Symbols

SD1, SD3: SDTAM Module Power Supply SD2: Thermal Fault Signal (80 mA max.) SD4: Contactor Control Output (80 mA max.)


	SD2	SD4
Micrologic 2 M	SDT	KA1

Terminal connections shown as O must be connected by the customer.

#### Connection



#### Operation



l: Charge Current SDT: Thermal Fault Signal

**KA1:** Auxiliary Relay (RBN or RTBT Relay)

KM1: Motor Contactor Q: Circuit Breaker

## Modbus™ Module

Detailed connection of the circuit breakers on Connection communication network Modbus EGX / 100 / 300 24 V Power Supply 24 V 0 V Rx- Rx+ Tx- Tx+ White Modbus Line Blue Termination 8 8 Modbus Communication Interface Module (PowerPact H-, J-, L-Frame) Blue Network A B A' White Blue Breaker A B A' Blue White 811 () C |812 311 B/Rx+ blue A/Rx- white CA/Rx- white CA/Rx+ yellow A/Tx- brown 0 V black CA/V red CA/Rx- brown CA/V red CA/Rx- black CA/V red CA/Rx- black CA/Rx- bla CD CE CT E6 E7 E3 E1 E1 Masterpact NT/NW (PowerPact P/R-Frame) (Masterpact NT/NW)

# **Section 12—Dimensions**

### PowerPact™ H-Frame Circuit Breakers

Figure 8: 15-150 A Bus Bar PowerPact H-Frame 2P HD/HG Thermal-Magnetic Only Circuit Breaker




Figure 9: 15–150 A Unit Mount PowerPact H-Frame 2P HD/HG Thermal-Magnetic Only Circuit Breaker




Figure 10: 15-150 A Bus Bar PowerPact H-Frame 3P Circuit Breaker




Figure 11: 15-150 A Lug-Lug PowerPact H-Frame 3P Circuit Breaker




Figure 12: 15-150 A Rear Connected PowerPact H-Frame 3P Circuit Breaker




Figure 13: Motor Operator Detail (PowerPact H-Frame Circuit Breaker)





Figure 14: Rotary Handle Detail (PowerPact H-Frame Circuit Breaker)



#### **PowerPact J-Frame Circuit Breakers**

Figure 15: 150-250 A Bus Bar PowerPact J-Frame 3P Circuit Breaker





Figure 16: 150-250 A Lug-Lug PowerPact J-Frame 3P Circuit Breaker




8.00 48996-023-01 -Ø .20 [5,1] (MOUNTING HOLE) [203,2] -6.46 [164,1] 1.38 [35,0] 1.54 [39,1] 2.06 [52,4] 4.12 1.37 [34,8] 2.84 [72,2] Dim. "A" Dim. "B" Trip Unit Thermal-Magnetic 2.04 3.44 and MCP Micrologic [147,6] [51,8] [87,4] 3.49 -6.02.48 [12,2] [152,9] Electronic Trip [50<u>,1]</u> [88,6] 1.04 [26,5] 5.00 Ø.34 [8,6] ISOMETRIC VIEW SCALE 1:2 3.24 2.95 [82,4] [74,9] [126,9] 1.66 2.06 [52,3] [42,1] 1.00 [25,3] 3.44 [87,3] [18,0] 4.49 [114,2] 1.38 [35,0] 1.38 [35,0] Dimensions: [6,0] - 5.51 [140,0]

150-250 A Rear Connected PowerPact J-Frame 3P Circuit Breaker

Figure 18: **Motor Operator Detail** (PowerPact J-Frame Circuit Breaker)

7.52 [191,0] -Ø.20 [5,1] (MOUNTING HOLE) -7.52 [191,0] -6.22 [158,0] 1.30 [33,0] 1.38 [35,0] 1.30 [33,0] 1.38 [35,0] 1.38 [35,0] 2.06 [52,4] 4.12 [104,7] 2.06 [52,4] 1.37 [34,8] .86 [22,0] 1.38 [35,0] .86 [21,8] -2.36 [59,9] -2.68 [68,1] -5.50 [139,8] -6.17 — [156,7] 6.65 — [169,0] [148,0] .27 [6,8] -6.66 [169,0] 7.01 [178,1] 5.63 [143,1] 3.24 2.87 [82,4] [72,9] [101,7] Dim. "A" Dim. "B" Trip Unit ·4.11 [104,5] and MCP Micrologic Electronic Trip [45,7] [87,4] [88,6]

Figure 19: **Rotary Handle Detail** (PowerPact J-Frame Circuit Breaker)



in. Dimensions: [mm]

### PowerPact H- and J-Frame Plug-In Circuit Breakers

Figure 20: 15-250 A PowerPact H- and J-Frame 3P Circuit Breaker Plug-In Base





Figure 21: 15-250 A PowerPact H- and J-Frame Plug-In 3P Circuit Breaker



#### **PowerPact H- and J-Frame Drawout Circuit Breakers**

Figure 22: 15–250 A PowerPact H- and J-Frame 3P Circuit Breaker Cradle





Figure 23: 15-250 A PowerPact H- and J-Frame Drawout 3P Circuit Breaker



## **PowerPact H- and J-Frame Circuit Breaker Mounting**

Figure 24: PowerPact H-Frame 2P HD/HG Thermal-Magnetic Only Circuit Breaker





Figure 25: PowerPact H- and J-Frame 3P Circuit Breaker



### PowerPact H- and J-Frame Circuit Breaker Door Cutouts

Figure 26: PowerPact H- and J-Frame Circuit Breaker Toggle Handle Door Cutout




Figure 27: PowerPact H- and J-Frame Circuit Breaker Toggle Handle With Escutcheon Door Cutout




Figure 28: PowerPact H- and J-Frame Circuit Breaker Fixed Rotary Handle Cutout




Figure 29: PowerPact H- and J-Frame Circuit Breaker Door Mounted Rotary Handle Cutout





Figure 30: PowerPact H- and J-Frame Circuit Breaker Motor Operator Cutout



#### **PowerPact L-Frame Circuit Breakers**

Figure 31: PowerPact L-Frame Fixed Mounted Electronic Trip Circuit Breaker





Figure 32: PowerPact L-Frame Circuit Breaker Mounting



<sup>&</sup>lt;sup>1</sup> For 2 pole circuit breaker, the middle holes are not required.

<sup>&</sup>lt;sup>2</sup> For rear connected circuit breakers only.

<sup>&</sup>lt;sup>3</sup> V is ≤ 78 in. (20 mm) on C-frame circuit breakers with secondary disconnecting blocks.

Figure 33: Front Panel Cutouts for PowerPact L-Frame Fixed or Plug-In Circuit Breakers






Figure 34: PowerPact L-Frame Circuit Breaker Front Panel Cutouts for Toggle Boot and Escutcheon



## **PowerPact L-Frame Plug-In and Drawout Mounting**

Figure 35: PowerPact L-Frame Plug-In Circuit Breaker (On Base)



	G10	G11	H16	H17	K1	L	L1	L2	P4	P7	P8	P9
inch	5.90	11.8	6.20	12.40	1.77	2.75	5.51	7.28	6.61	1.06	1.77	3.93
mm	150	300	157.5	315	45	70	140	185	168	27	45	100

Figure 36: PowerPact L-Frame Drawout Circuit Breaker (on Cradle)




Figure 37: PowerPact L-Frame Circuit Breaker Mounting Through a Backplate




Figure 38: PowerPact L-Frame Circuit Breaker Mounting on Rails (Plug-In Base or Cradle)






Figure 39: PowerPact L-Frame Circuit Breaker Front-Panel Cutouts



### **PowerPact L-Frame Circuit Breaker Handles and Handle Operators**

Figure 40: PowerPact L-Frame Circuit Breaker Motor Operators



C5: without keylock C6: with keylock

	A14	A15	A16	A17	В	B1	B2	B8	B9	C4	C5	C6	D1
inch	1.57	4.84	2.05	3.94	2.76	5.51	7.28	2.42	4.84	8.46	10.08	10.16	3.94
mm	40	123	52	100	70	140	185	61.5	123	215	256	258	100

Figure 41: PowerPact L-Frame Circuit Breaker Motor Operator Front-Panel Cutouts




Figure 42: PowerPact L-Frame Circuit Breaker Cable-Operating Handles





Figure 43: PowerPact L-Frame Circuit Breaker Rotary-Operating Handles



	A14	A15	A18	В	B1	B2	B8	В9	B10	<b>C</b> 7	C8	C9	D1
inch	1.57	4.84	0.97	2.76	5.51	7.28	2.42	4.84	0.20	5.71	7.05	7.40	3.94
mm	40	123	24.6	70	140	185	61.5	123	5	145	179	188	100

Figure 44: PowerPact L-Frame Motor-Control Center Circuit Breaker Direct Rotary-Operating Handle





Figure 45: PowerPact L-Frame Circuit Breaker Extended Rotary Handle Mounting



	R1 min	R1 max	R2 min	R2 max	A18	B10	D1
inch	7.68	23.62	10.71	23.62	0.97	0.20	3.94
mm	195	600	272	600	24.6	5	100

### L-Frame Circuit Breaker Front Accessories

Figure 46: PowerPact L-Frame Circuit Breaker Extended Escutcheons





Figure 47: PowerPact L-Frame Circuit Breaker Front-Panel Escutcheons



## **PowerPact L-Frame Circuit Breaker Interlocking Systems**

Figure 48: PowerPact L-Frame Circuit Breaker Interlocking Systems with Rotary-Operating Handles






Figure 49: PowerPact L-Frame Circuit Breaker Interlocking Systems with Toggle Handles



### **PowerPact L-Frame Circuit Breaker Connectors**

Figure 50: PowerPact L-Frame Circuit Breaker Fixed-Mounted Connections



	G4	G5	K1	P13
inch	4.46	8.93	1.77	1.02
mm	113.5	227	45	526

Figure 51: PowerPact L-Frame Circuit Breaker Front Connections




Figure 52: PowerPact L-Frame Circuit Breaker Rear Connections




Figure 53: PowerPact L-Frame Circuit Breaker Plug-In or Drawout Mounting Connections




Figure 54: PowerPact L-Frame Circuit Breaker Rear Connections Fitted at Lower Limit





Figure 55: PowerPact L-Frame Circuit Breaker Rear Connections Fitted at Upper Limit




	Е	G35	P22	P23
inch	0.23	5.07	4.50-7.14	3.93-6.57
mm	6	129	114.5–181.5	100-167

# **Section 13—Trip Curves**

### PowerPact H- and J-Frame Thermal-Magnetic Trip Circuit Breakers

Figure 56: H-Frame 15-35 A (HD, HG, HJ, and HL) Thermal-Magnetic Trip



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 57: H-Frame 40-60 A (HD, HG, HJ, and HL) Thermal-Magnetic Trip





Figure 58: H-Frame 70-100 A (HD, HG, HJ, and HL) Thermal-Magnetic Trip



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 59: H-Frame 110-150 A (HD, HG, HJ, and HL) Thermal-Magnetic Trip





Figure 60: J-Frame 150-250 A (JD, JG, JJ, JL, and JR) Thermal-Magnetic Trip



### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 61: J-Frame 100 A (JG) 500 Vdc Thermal-Magnetic 500 Trip





Figure 62: J-Frame 125 A (JG) 500 Vdc Thermal-Magnetic Trip



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 63: J-Frame 150 A (JG) 500 Vdc Thermal-Magnetic Trip





Figure 64: J-Frame 175 A (JG) 500 Vdc Thermal-Magnetic Trip



### PowerPact™ H-, J-, and L-Frame Circuit Breakers **Trip Curves**

Figure 65: J-Frame 200 A (JG) 500 Vdc Thermal-Magnetic Trip




Figure 66: J-Frame 225 A (JG) 500 Vdc Thermal-Magnetic Trip




Figure 67: J-Frame 250 A (JG) 500 Vdc Thermal-Magnetic Trip





Figure 68: H-Frame 150 A Typical Peak Let-Through Curves

# ELECTRONIC MOLDED CASE CIRCUIT BREAKERS POWERPACT™ H-FRAME CURRENT LIMITING CIRCUIT BREAKERS 150 A FRAME AT 240, 480 AND 600 V, 3Ø 15-150 A

#### PEAK LET-THROUGH CURRENT Ip



Available Short Circuit Current (RMS Symmetrical Amperes x 10³)





Figure 69: H-Frame 150 A Typical I<sup>2</sup>t Let-Through Curves

### **ELECTRONIC MOLDED CASE CIRCUIT BREAKERS** POWERPACT™ H-FRAME CURRENT LIMITING CIRCUIT BREAKERS 150 A FRAME AT 240, 480 AND 600 V, 3Ø 15-150 A

#### LET-THROUGH CURRENT I2t







Figure 70: J-Frame 250 A Typical Peak Let-Through Curves

#### **ELECTRONIC MOLDED CASE CIRCUIT BREAKERS** POWERPACT™ J-FRAME CURRENT LIMITING CIRCUIT BREAKERS 250 A FRAME AT 240, 480 AND 600 V, 3Ø 150-250 A

### PEAK LET-THROUGH CURRENT IP






Drawing No. 48095-050-09 April 2012 Rev. 01

Figure 71: J-Frame 250 A Typical I<sup>2</sup>t Let-Through Curves

# ELECTRONIC MOLDED CASE CIRCUIT BREAKERS POWERPACT™ J-FRAME CURRENT LIMITING CIRCUIT BREAKERS 250 A FRAME AT 240, 480 AND 600 V, 3Ø 150-250 A

LET-THROUGH CURRENT I2t





awing No. 48095-050-08 April 2012

Figure 72: H- and J-Frame Motor Circuit Protector




Figure 73: H-Frame UL Listed Current-Limiting Circuit Breaker

#### THERMAL-MAGNETIC MOLDED CASE CIRCUIT BREAKERS H-FRAME® CURRENT LIMITING CIRCUIT BREAKERS H 150 A FRAME AT 240, 480 AND 600 V, 3Ø HJ, HL AND HR 15-150 A

PEAK LET-THROUGH CURRENT IP







Figure 74: H-Frame UL Listed Current-Limiting Circuit Breaker

# THERMAL-MAGNETIC MOLDED CASE CIRCUIT BREAKERS H-FRAME® CURRENT LIMITING CIRCUIT BREAKERS H 150 A FRAME AT 240, 480 AND 600 V, 3Ø HJ, HL AND HR 15—150 A

LET-THROUGH CURRENT I2t



© 2012 Schneider Electric all rights reserved

Figure 75: J-Frame UL Listed Current -Limiting Circuit Breaker

## THERMAL-MAGNETIC MOLDED CASE CIRCUIT BREAKERS J-FRAME<sup>®</sup> CURRENT LIMITING CIRCUIT BREAKERS J 250 A FRAME AT 240, 480 AND 600 V, 3Ø JJ, JL AND JR 150-250 A

PEAK LET-THROUGH CURRENT IP





Figure 76: J-Frame UL Listed Current-Limiting Circuit Breaker

# THERMAL-MAGNETIC MOLDED CASE CIRCUIT BREAKERS J-FRAME® CURRENT LIMITING CIRCUIT BREAKERS J 250 A FRAME AT 240, 480 AND 600 V, 3Ø JJ, JL AND JR 150—250 A

LET-THROUGH CURRENT I2t



© 2012 Schneider Electric all rights reserved

Drawing No. 48095-050-13 April 2012 Rev. 02

Figure 77: Ground Fault Module GFM150HD Trip Curve




Figure 78: Ground Fault Module GFM250JD Trip Curve





Figure 79: Earth Leakage Module Trip Curve



### PowerPact H- and J-Frame Thermal-Magnetic Trip MCP Instantaneous Trip Points

**Table 141: M71 Instantaneous Trip Points** 

		Automatic	c Setting (A) Manual Adjustment (A)								
	I <sub>m</sub> Setting	1	2	6x	8x	9x	10x	11x	12x	13x	
Matax Tuna	NEMA	A, B, C, D	B, E	(51.4)							
Motor Type	IEC	N	Н	(FLA) x (I <sub>m</sub> )							
	1.5	12	16.5	9	12	13.5	15	16.5	18	19.5	
	3	24	33	18	24	27	30	33	36	39	
	6	48	66	36	48	54	60	66	72	78	
	8	64	88	48	64	72	80	88	96	104	
FLA	11	88	121	66	88	99	110	121	132	143	
	14	112	154	84	112	126	140	154	168	182	
	17	136	187	102	136	153	170	187	204	221	
	20	160	220	120	160	180	200	220	240	260	
	25	200	275	150	200	225	250	275	300	325	
Dampening for motor in-rush (% FLA)		1300%	1700%	1300%	_						

Table 142: M72 Instantaneous Trip Points

		Automatic	Setting (A) <sup>1</sup>		Ma	anual A	al Adjustment (A) <sup>1</sup>					
	I <sub>m</sub> Setting	1	2	6x	8x	9x	10x	11x	12x	13x		
Motor Type	NEMA	A, B, C, D	B, E	(FLA) x (I <sub>m</sub> )								
Motor Type	IEC	N	Н									
	14	112	154	84	112	126	140	154	168	182		
	17	136	187	102	136	153	170	187	204	221		
	21	168	231	126	168	189	210	231	252	273		
	24	192	264	144	192	216	240	264	288	312		
FLA	27	216	297	162	216	243	270	297	324	351		
	29	232	319	174	232	261	290	319	348	377		
	32	256	352	192	256	288	320	352	384	416		
	36	288	396	216	288	324	360	396	432	468		
	42	336	462	252	336	378	420	462	504	546		
Dampening for motor in-rush (% FLA)		1300%	1700%	1300%	_							

 $<sup>^{1}</sup>$   $\pm 5\%$  of nominal amperage shown above

Table 143: M73 Instantaneous Trip Points

		Automatic	Setting (A)1	ting (A) <sup>1</sup> Manual Adjustment (A) <sup>1</sup>							
	I <sub>m</sub> Setting	1	2	6x	8x	9x	10x	11x	12x	13x	
Motor Type	NEMA	A, B, C, D	B, E	(FLA) x (I <sub>m</sub> )							
wotor rype	IEC	N	Н								
	30	240	330	180	240	270	300	330	360	390	
	35	280	385	210	280	315	350	385	420	455	
	41	328	451	246	328	369	410	451	492	533	
	46	368	506	276	368	414	460	506	552	598	
FLA	51	408	561	306	408	459	510	561	612	663	
	56	448	616	336	448	504	560	616	672	728	
	63	504	693	378	504	567	630	693	756	819	
	71	568	781	426	568	639	710	781	852	923	
	80	640	880	480	640	720	800	880	960	1040	
Dampening for motor in-rush (% FLA)		1300%	1700%	1300%			_	_	•	•	

 $<sup>1 \</sup>pm 5\%$  of nominal amperage shown above

Table 144: M74 Instantaneous Trip Points

		Automatic	Manual Adjustment (A) <sup>1</sup>							
	I <sub>m</sub> Setting	1	2	6x	8x	9x	10x	11x	12x	13x
Motor Type	NEMA	A, B, C, D	B, E	(FLA) x (I <sub>m</sub> )						
wotor Type	IEC	N	Н							
	58	464	638	348	464	522	580	638	696	754
	71	568	781	426	568	639	710	781	852	923
	79	632	869	474	632	711	790	869	948	1027
	86	688	946	516	688	774	860	946	1032	1118
FLA	91	728	1001	546	728	819	910	1001	1092	1183
	97	776	1067	582	776	873	970	1067	1164	1261
	110	880	1210	660	880	990	1100	1210	1320	1430
	119	952	1309	714	952	1071	1190	1309	1428	1547
	130	1040	1430	780	1040	1170	1300	1430	1560	1690
Dampening for motor in-rush (% FLA)		1300%	1700%	1300%			_	_		

 $<sup>^{1}</sup>$   $\pm 5\%$  of nominal amperage shown above

Table 145: M75 Instantaneous Trip Points


		Automatic	Manual Adjustment (A) <sup>1</sup>								
	I <sub>m</sub> Setting	1	2	6x	8x	9x	10x	11x	12x	13x	
Motor Type	NEMA	A, B, C, D	B, E	(FLA) x (I <sub>m</sub> )							
	IEC	N	Н								
	114	912	1254	684	912	1026	1140	1254	1368	1482	
	137	1096	1507	822	1096	1233	1370	1507	1644	1781	
	145	1160	1595	870	1160	1305	1450	1595	1740	1885	
	155	1240	1705	930	1240	1395	1550	1705	1860	2015	
FLA	163	1304	1793	978	1304	1467	1630	1793	1956	2119	
	172	1376	1892	1032	1376	1548	1720	1892	2064	2236	
	181	1448	1991	1086	1448	1629	1810	1991	2172	2353	
	210	1680	2310	1260	1680	1890	2100	2310	2500 <sup>2</sup>	2500	
	217	1736	2387	1302	1736	1953	2170	2387	2500 2	2500	
mpening for motor in-rush (% FLA) 110		1100-1300%	1100–1700%	1100– 1300%				_			

 $<sup>^{1}</sup>$   $\pm$  5% of nominal amperage shown above

<sup>&</sup>lt;sup>2</sup> 2500 A maximum instantaneous trip point

### PowerPact H-Frame Electronic Trip Circuit Breakers— 60 A/100 A/150 A Frame

Figure 80: Micrologic 3.2 Electronic Trip Unit Long Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.2 Long Time Trip Curve 60A, 100A, 150A H-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.

Figure 81: Micrologic 3.2S Electronic Trip Unit Long Time / Short Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.2S Long Time/ Short Time Trip Curve 60A, 100A, 150A H-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 82: Micrologic 3.2/3.2S/5.2A/5.2E/6.2A/6.2E Electronic Trip Unit Instantaneous Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.2/3.2S/5.2A or E/6.2A or E Instantaneous Trip Curve 60A, 100A, 150A H-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. In = Maximum dial setting of Ir. 60A H-Frame: In = 60A = Max Ir setting 100A H-Frame: In = 100A = Max Ir setting 150A H-Frame: In = 150A = Max Ir setting

Figure 83: Micrologic 5.2A/5.2E/6.2A/6.2E Electronic Trip Unit Long Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 5.2A or E/6.2A or E Long Time Trip Curve 60A, 100A, 150A H-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 84: Micrologic 5.2A/5.2E/6.2A/6.2E Electronic Trip Unit Short Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 5.2A or E/6.2A or E Short Time Trip Curve 60A, 100A, 150A H-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 85: Micrologic 6.2A/6.2E Electronic Trip Unit Ground Fault Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 6.2A or E Ground Fault Trip Curve 100A, 150A H-Frame

The time-current curve information is to be used for application and coordination purposes only.

 Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 86: Micrologic 6.2A/6.2E Electronic Trip Unit Ground Fault Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 6.2A or E Ground Fault Trip Curve 60A H-Frame

The time-current curve information is to be used for application and coordination purposes only.

 Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 87: Micrologic 2.2 M Electronic Trip Unit Overload Trip Curve



**CURRENT IN MULTIPLES OF FLA** 

#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 2.2M Overload Trip Curve 30A, 50A, 100A, 150A H-Frame, 250A J-Frame


The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- If overload still exists past overload relay delay, MCP will open 0.4 seconds later.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. Isd minimum and maximum only shown.
- 4. li = 15 x ln ln = 30A, 50A, 100A, 150A, 250A MCP will trip <30ms at 15 x ln

### J-Frame Electronic Trip Circuit Breakers—250 A Frame

Figure 88: Micrologic 3.2 and 3.2-W Electronic Trip Unit Long-Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.2 and 3.2-W Long Time Trip Curve 250A J-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 89: Micrologic 3.2S and 3.2S-W Electronic Trip Unit Long Time / Short Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.2S and 3.2S-W Long Time/Short Time Trip Curve 250A J-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 90: Micrologic 3.2, 3.2-W, 3.2S, 3.2S-W, 5.2A, 5.2A-W, 5.2E, 5.2E-W, 6.2A, 6.2A-W, 6.2E, and 6.2E-W Electronic Trip Curve Instantaneous Trip Curve



MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.2, 3.2-W, 3.2S, 3.2S-W, 5.2A, 5.2A-W, 5.2E, 5.2E-W, 6.2A, 6.2A-W, 6.2E, and 6.2E-W Instantaneous Trip Curve 250A J-Frame


The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. In = Maximum dial setting of Ir. 250A J-Frame: In = 250A = Max Ir setting

Curves apply from -35°C to +70°C (-31°F to +158°F) ambient temperature.

Micrologic 5.2A, 5.2A-W, 5.2E, 5.2E-W, 6.2A, 6.2A-W, 6.2E, and 6.2E-W Electronic Trip Unit Long Time Trip Curve Figure 91:




MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic<sup>™</sup> 5.2A, 5.2A-W, 5.2E, 5.2E-W, 6.2A, 6.2A-W, 6.2E, and 6.2E-W Long Time Trip Curve 250A J-Frame

The time-current curve information is to be used for application and coordination purposes only.

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- 2. Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the

Figure 92: Micrologic 5.2A, 5.2A-W, 5.2E, 5.2E-W, 6.2A, 6.2A-W, 6.2E, and 6.2E-W Electronic Trip Unit Short Time Trip Curve




MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 5.2A, 5.2A-W, 5.2E, 5.2E-W, 6.2A, 6.2A-W, 6.2E, and 6.2E-W Short Time Trip Curve 250A J-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 93: Micrologic 6.2A, 6.2A-W, 6.2E, and 6.2E-W Electronic Trip Unit Ground Fault Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 6.2A, 6.2A-W, 6.2E, and 6.2E-W Ground Fault Trip Curve 250A J-Frame

The time-current curve information is to be used for application and coordination purposes only.

 Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the

Figure 94: Micrologic 2.2 M Electronic Trip Unit Overload Trip Curve



MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 2.2M Overload Trip Curve 30A, 50A, 100A, 150A H-Frame, 250A J-Frame


The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- If overload still exists past overload relay delay, MCP will open 0.4 seconds later.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. Isd minimum and maximum only shown.
- 4. li = 15 x ln ln = 30A, 50A, 100A, 150A, 250A MCP will trip <30ms at 15 x ln

## PowerPact L-Frame Electronic Trip Circuit Breakers— 250 A/400 A/600 A Frame

Figure 95: Micrologic 3.3 and 3.3-W Electronic Trip Unit Long Time Trip Curve




### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.3 and 3.3-W Long Time Trip Curve 250A, 400A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

- There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- 2. Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the

Figure 96: Micrologic 3.3S and 3.3S-W Electronic Trip Unit Long Time/Short Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.3S and 3.3S-W Long Time/Short Time Trip Curve 250A, 400A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 97: Micrologic 3.3, 3.3-W, 3.3S, and 3.3S-W Electronic Trip Unit Instantaneous Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.3, 3.3-W, 3.3S, and 3.3S-W Instantaneous Trip Curve 250A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. In = Maximum dial setting of Ir. 250A L-Frame: In = 250A = Max Ir setting Curves apply from -35°C to +70°C (-31°F to +158°F) ambient temperature.

Figure 98: Micrologic 3.3, 3.3-W, 3.3S, 3.3S-W, 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Electronic Trip Unit Instantaneous Trip Curve




MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.3, 3.3-W, 3.3S, 3.3S-W, 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Instantaneous Trip Curve 400A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. In = Maximum dial setting of Ir. 400A L-Frame: In = 400A = Max Ir setting

Figure 99: Micrologic 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Electronic Trip Unit Long Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Long Time Trip Curve 400A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 100: Micrologic 5.3, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Electronic Trip Unit Short Time Trip Curve



MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Short Time Trip Curve 400A L-Frame


The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Curves apply from -35°C to +70°C (-31°F to +158°F) ambient temperature.

Figure 101: Micrologic 1.3 M Electronic Trip Unit Instantaneous Trip Curve



#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 1.3M Instantaneous Trip Curve 400A L-Frame


The time-current curve information is to be used for application and coordination purposes only.

### Notes:

 Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the

# PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 102: Micrologic 2.3 M Electronic Trip Unit Overload Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 2.3M Overload Trip Curve 400A, 600A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

### Notes:

- If overload still exists past overload relay delay, MCP will open 0.4 seconds later.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. Isd minimum and maximum only shown.
- 4. li = 12 x ln ln = 400A, 600A MCP will trip <30ms at 12 x ln

Figure 103: Micrologic 3.3 and 3.3W Electronic Trip Unit Long Time Trip Curve



### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.3 and 3.3-W Long Time Trip Curve 600A L-Frame


The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.

### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 104: Micrologic 3.3S and 3.3S-W Electronic Trip Unit Long Time/Short Time Trip Curve




#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.3S and 3.3S-W Long Time/Short Time Trip Curve 600A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.

Figure 105: Micrologic 3.3, 3.3-W, 3.3S, 3.3S-W, 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Electronic Trip Unit Instantaneous Trip Curve



MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 3.3, 3.3-W, 3.3S, 3.3S-W, 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Instantaneous Trip Curve 600A L-Frame


The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.
- 3. In = Maximum dial setting of Ir. 600A L-Frame: In = 600A = Max Ir setting Curves apply from -35°C to +70°C (-31°F to +158°F) ambient temperature.

### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 106: Micrologic 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Electronic Trip Unit Long Time Trip Curve




MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Long Time Trip Curve 600A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current

Figure 107: Micrologic 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W Electronic Trip Unit Short Time Trip



MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 5.3A, 5.3A-W, 5.3E, 5.3E-W, 6.3A, 6.3A-W, 6.3E, and 6.3E-W **Short Time Trip Curve** 600A L-Frame


The time-current curve information is to be used for application and coordination purposes only.

#### Notes:

- 1. There is a thermal-imaging effect that can act to shorten the long-time delay. The thermal imaging effect comes into play if a current above the long-time delay pickup value exists for a time and then is cleared by the tripping of a downstream device or the circuit breaker itself. A subsequent overload will cause the circuit breaker to trip in a shorter time than normal. The amount of time delay reduction is inverse to the amount of time that has elapsed since the previous overload. Approximately 20 minutes is required between overloads to completely reset thermal-imaging.
- 2. Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the

### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 108: Micrologic 6.3A, 6.3A-W, 6.3E, and 6.3E-W Ground-Fault Trip Curve




### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 6.3A, 6.3A-W, 6.3E, and 6.3E-W Ground Fault Trip Curve 400A, 600A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.

Figure 109: Micrologic 1.3 M Electronic Trip Unit Instantaneous Trip Curve



#### MICROLOGIC™ ELECTRONIC TRIP UNITS Micrologic™ 1.3M Instantaneous Trip Curve 600A L-Frame

The time-current curve information is to be used for application and coordination purposes only.

### Notes:

Total clearing times shown include the response times of the trip unit, the circuit breaker opening, and the extinction of the current.

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 110: L-Frame 600 A Typical Peak Let-Through Curves

# ELECTRONIC MOLDED CASE CIRCUIT BREAKERS POWERPACT™ L-FRAME CURRENT LIMITING CIRCUIT BREAKERS 600 A FRAME AT 240, 480 AND 600 V, 3Ø LD, LG, LJ, LL AND LR 250-600 A PEAK LET-THROUGH CURRENT Ip





Figure 111: L-Frame 600 A Typical I<sup>2</sup>t Let-Through Curves

# ELECTRONIC MOLDED CASE CIRCUIT BREAKERS POWERPACT™ L-FRAME CURRENT LIMITING CIRCUIT BREAKERS 600 A FRAME AT 240, 480 AND 600 V, 3Ø LD, LG, LJ, LL AND LR 250—600 A LET-THROUGH I²t




# PowerPact™ H-, J-, and L-Frame Circuit Breakers Trip Curves

Figure 112: L-Frame UL Listed Current-Limiting Circuit Breaker

# ELECTRONIC MOLDED CASE CIRCUIT BREAKERS POWERPACT™ L-FRAME CURRENT LIMITING CIRCUIT BREAKERS 600 A FRAME AT 240, 480 AND 600 V, 3Ø LJ, LL AND LR 250-600 A

PEAK LET-THROUGH CURRENT Ip



01/2014

Figure 113: L-Frame UL Listed Current-Limiting Circuit Breaker

# ELECTRONIC MOLDED CASE CIRCUIT BREAKERS POWERPACT™ L-FRAME CURRENT LIMITING CIRCUIT BREAKERS 600 A FRAME AT 240, 480 AND 600 V, 3Ø LJ, LL AND LR 250-600 A LET-THROUGH I²t


Maximum, Tet-Through Pi (Amperees's Seconds x 10°)

These of on meaning was seconds and the set programs and the set programs are seconds and the set programs and the set programs are seconds and the set programs are seconds at 10°)

240 A 300 A

**Availability (RMS Symmetrical Amperes)** 

Figure 114: L-Frame Circuit Breaker Reflex Tripping



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Catalog Numbers

# Catalog Numbers

28271 122 HDA-8150(1) 309 HD.35015C 260 HD.3515CU31X 281 HGA-85000(131X 28) 25556 HJ HDA-81506(131 HD HD.35015C 260 HD.3515CU31X 281 HGA-85000(131X 28) 25556 HJ HDA-81506 HJ HD.35015C 270 HD.3515CU31X 281 HGA-85000(131X 28) 25556 HJ HDA-81506 HJ HD.35015C 270 HD.3515CU31X 281 HGA-85000(131X 28) 25556 HJ HDA-81506 HJ HD.35015C 270 HD.3515CU31X 281 HGA-85000(131X 28) 25556 HJ HDA-81506 HJ HD.35015C 270 HD.3515CU31X 281 HGA-85000(131X 28) 25556 HJ HDA-81506 H	00074	400	LID 400450()	1101 000450	00	11D1 004E001104V 00	110 40000011041/
192566			HDA26150()30			HDL36150CU31X 28	HGA36060U31X32
Seption						HDL36150CU33X28	HGA36060U33X32
Seption	32556	113	HDA261502 119	HDL36020	26	HDL36150CU43X 28	HGA36060U43X(32
685823							
685824							
685826							
685826							
688827	685825	83	HDA261506 119	HDL36025C	26	HDL36150TU33X 34	HGA3607030
688827	685826	83	HDA36015 30	HDI 36025T	33	HDI 36150TU43X 34	HGA36080 30
695823							
965831 84 HDA56030 30 HDL56050T 33 HDL5615UJSY 28 HAA5610UJSY 32 9 H21LD1 100 HDA56036 30 HDL56050SC 26 HDL5615UJSY 28 HGA510UJSY 28 H21LD1 100 HDA56036 30 HDL56050SC 26 HDL5615UJSY 28 HGA510UJSY 28 H21LD1 100 HDA56036 30 HDL56050SC 26 HDL5615UJSY 28 HGA510UJSY 28 H21LD1 100 HDA56060 30 HDL56040 26 HDL5615UJSY 28 H21LD1 107 HDA56060 30 HDL56040 26 HDL5615UJSY 28 H21LD1 107 HDA56060 30 HDL56040T 33 HDL5615UJSY 28 H21LD1 107 HDA56060UJSY 28 HDL56050T 33 HDL5615UJSY 28 H21LD1 107 HDA56060UJSY 28 HDL56040 26 HDL5615UJSY 28 H21LD1 107 HDA56060UJSY 28 HDL56040 26 HDL5615UJSY 28 H21LD1 107 HDA56060UJSY 28 HDL56040 26 HDL5615UJSY 28 H21LD1 107 HDA56060UJSY 28 HDL56045 26 HES060UJSY 38 H21LD1 107 HDA56060UJSY 28 HDL56045 26 HES060UJSY 38 H21LD1 107 HDA56060UJSY 28 HDL56045 26 HES060UJSY 38 HCA63110 30 HDL5615UJSY 28 HDL56045 26 HES060UJSY 38 HCA63110 30 HDL5615UJSY 28 HDL56045 26 HES060UJSY 38 HCA63110 30 HDL5615UJSY 28 HDL56050 26 HES060UJSY 38 HCA63110 30 HDL5615UJSY 38 HCA63110 30 HDL5615							
9421LD1 108 HDA36053 30 HDL36035 26 HDL36150U31X 28 HCA3610U31X 32 9421LD1 108 HDA36064 30 HDL36035C 26 HDL36150U31X 28 HCA3610U44X 32 9421LD1 108 HDA36064 30 HDL36035C 33 HDL36150U4X 28 HCA3610U44X 32 9421LD1 107 HDA36060U31X 32 HDL36050C 26 HDL36150U31X 28 HCA3610U44X 32 9421LD1 107 HDA36060U31X 32 HDL36040C 26 HDL36150U31X 28 HCA3610U44X 32 9421LD1 107 HDA36060U31X 32 HDL36040C 26 HDL36150U31X 38 HCA3610U31X 32 HDL36040C 26 HDL36150U31X 35 HDL36150U31X 32 HDL36040C 26 HCA36150U31X 35 HDA3610U31X 32 HDL36040C 26 HCA36150U31X 35 HDA3610U31X 32 HDL36040C 26 HCA36150U31X 35 HDA3610U31X 32 HDL36040C 26 HCA36150U31X 35 HDA3610C 34 HDL36150U31X 35 HDA3610U31X 32 HDL36040C 26 HCA36150U31X 35 HDA3610U31X 35 HDA3610U31X 32 HDL3604C 26 HCA36150U31X 35 HDA36150U31X 32 HDL3604C 26 HCA36150U31X 35 HDA36150U31X 32 HDA3610U31X 32 HDL36050C 26 HCA3600U31X 35 HDA36150U31X 32 HDA36050U31X 35 HDA36150U31X 32 HDA36050C 36 HCA36150U31X 36 HDA36150U31X 32 HDA36050C 36 HCA36150U31X 35 HDA36150U31X 32 HDA36050C 35 HDA36150U31X 36 HDA36150U31X 32 HDA36050C 35 HDA36150U31X 36 HCA36150U31X 32 HDA36150U31X 32 HDA36050C 35 HDA36150U31X 36 HCA36150U31X 36 HCA36150U31X 36 HCA36150U31X 32 HDA36050C 35 HDA36150U31X 36 HCA36150U31X 36 HCA3							
9421LD1 108 HDA98040 30 HDL9803ST 38 HDL9810JUXX 28 HCA9810DUAXX 32 94 LDL9810DUAXX 32 94	685831	84	HDA3603030	HDL36030T	33	HDL36150TU54X 34	HGA36100U31X32
9421LD1 108 HDA98040 30 HDL9803ST 38 HDL9810JUXX 28 HCA9810DUAXX 32 94 LDL9810DUAXX 32 94	9421LC46	108	HDA3603530	HDL36035	26	HDL36150U31X28	HGA36100U33X32
9421L144 108 HDA96054 30 HDL960501 33 HDL96060 26 HDL36150L4X 28 HAAS100L5XX 32 9421L146 109 HDA96050 30 HDL960600 26 HDL36150L5XX 32 HDL960600 25 HDL36150L5XX 32 HDL960600 30 HDL960600 26 HDL36150L5XX 32 HDL960600 30 HDL960600 26 HDL36150L5XX 32 HDL960600 30 HDL96							
9421L146 108 HDA36960 30 HDL3604C 26 HDL36150USX 28 HGA3610USX 32 P42L11 107 HDA36900USX 32 HDL3604C 26 HDL3615UUSX 28 HGA3610USX 32 P42L11 107 HDA36900USX 32 HDL3604C 33 HDL3615UUSX 28 HGA36110 30 HDL3615UUSX 28 HGA36110 30 HDL3615UUSX 28 HGA36110 30 HDL3615UUSX 28 HGA36110 30 HDL3615UUSX 28 HGA3615USX 28 HDL3615UUSX 28 HGA3615USX 32 P42L15 108 HDA36960USX 32 P42L15 108 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 108 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 108 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 10 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 10 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 10 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 10 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 10 HDA36970 30 HDL36050 26 HE3060USX 35 HGA3615USX 32 P42L15 10 HDA36970 30 HDL36050 27 HDA3							
9421L16							
9421LIJ 107 HDA66000U31X 32 HDL6045 38 HGA86150 30 9421LI7 108 HDA6600U31X 32 HDL6045 26 HE3000U31X 88 HGA86150 30 9421LI7 108 HDA6600U31X 32 HDL5045C 26 HE300U31X 88 HGA86150 30 9421LI7 108 HDA6600U31X 32 HDL5045C 26 HE300U31X 88 HGA86150 30 9421LI5 108 HDA6600U51X 32 HDL5045C 26 HE300U31X 88 HGA86150 30 9421LI5 108 HDA6600U51X 32 HDL50605C 26 HE300U31X 35 HGA86150 30 9422CSF30 108 HDA6600U51X 32 HDL50605C 26 HE300U43X 99 HGA86150U51X 32 9422CSF30 108 HDA66000 30 HDL50606C 26 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA66000 30 HDL50606C 26 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA6600 30 HDL50606C 26 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA6600 30 HDL50606C 26 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA6600 30 HDL50606C 26 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA6600 30 HDL50606C 26 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA6600 30 HDL50606C 26 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA6600 30 HDL50606C 32 HE300U43X 99 HGA86150U53X 32 9422CSF30 108 HDA66100U33X 32 HDL50606CU53X 28 HE300U44X 99 HGA86150U53X 32 9422CSF30 109 HDA66100U33X 32 HDL50606CU53X 28 HE300U44X 99 HGA86150U53X 32 9422CSF30 109 HDA66100U33X 32 HDL50606CU53X 34 HE300U43X 99 HGA86150U53X 32 HDL50606CU53X 34 HE300U53X 35 HGL50600F6 35 36 44 HDA66100U53X 32 HDL50606CU53X 38 HG5060U53X 35 HGL50600F6 35 36 44 HDA66100U53X 32 HDL50606CU53X 34 HE300U53X 35 HGL50600F6 36 44 HDA66100U53X 32 HDL50606CU53X 34 HE300U53X 35 HGL50600C 26 HDA66100U53X 34 HDA66100U53X 35 HGL50600C 26 HDA66100U53X 35 HGL50600C 36 HDA66100U53X 35 HGL50600C 36 HDA66100U53X 36 HGL50600C 3			HDA3605030				
9421LIJ 107 HDA96900U33X 22 HDL96045C 26 HE3060U31X 35 HGA86125 30 9421LS13 108 HDA96900U43X 22 HDL96045C 36 HE3060U33X 35 HGA86150U31X 32 9421LS8 108 HDA96900U43X 32 HDL9605D 26 HE3060U33X 35 HGA86150U31X 32 9421LS8 108 HDA96900U43X 32 HDL9605D 26 HE3060U33X 35 HGA86150U31X 32 9422CSF10 108 HDA86900U33X 32 HDL9605D 26 HE3060U43X 69 HGA86150U31X 32 9422CSF30 108 HDA86900 30 HDL9606C 26 HE3060U43X 69 HGA86150U31X 32 9422CSF30 108 HDA86900 30 HDL9606C 26 HE3060U43X 35 HGA86150U31X 32 9422CSF30 108 HDA86900 30 HDL9606C 26 HE3060U43X 35 HGA86150U31X 32 9422CSF30 108 HDA86900 30 HDL9606C 26 HE3060U43X 36 HGA86150U31X 32 9422CSF30 108 HDA86900 30 HDL9606C 26 HE3060U43X 36 HGA86150U31X 32 9422CSF30 108 HDA86900 30 HDL9606C 26 HE3060U43X 36 HGA86150U51X 32 9422CSF30 108 HDA8610U31X 32 HDL9606CU31X 28 HE3060U43X 36 HGA86150U51X 32 9422CSF30 108 HDA8610U31X 32 HDL9606CU31X 28 HE3060U43X 36 HGA86150U51X 32 9422CSF30 108 HDA8610U31X 32 HDL9606CU31X 28 HE3060U43X 36 HGA86150U51X 32 9422CSF30 108 HDA8610U31X 32 HDL9606CU31X 28 HE3060U43X 36 HGA86150U51X 32 9422CSF30 108 HDA8610U31X 32 HDL9606CU31X 34 HE306U31X 36 HGA86150U51X 32 9422CSF30 108 HDA8610U41X 32 HDL9606CU31X 34 HE306U51X 36 HGA8616U51X 32 9422CSF30 108 HDA8610U41X 32 HDL9606CU31X 34 HE306U51X 36 HGL2601C 26 HGA8616U51X 32 HDL9606CU31X 34 HE306U51X 36 HGL2601C 26 HGA8616U51X 32 HDL9606CU31X 34 HE306U51X 36 HGL2601C 26 HGA8616U51X 34 HGA8616U51X 34 HGL2601C 26 HGA8616U51X 35 HGL2606CU31X 35 HGL2601C 26 HGA8616U51X 35 HGL2601C 26 HGA8616U51X 35 HGL2601C 26 HGA8616U51X 35 HGL2601C 26 HGA861	9421LH6	.108	HDA36060 30	HDL36040C	26	HDL36150U53X28	HGA36100U54X32
9421LIJ 107 HDA69600U33X 32 HDL59045C 26 HE3960U31X 35 HGA81125 30 9421LIS1 108 HDA69600U44X 32 HDL59045T 33 HE3960U31X 35 HGA81150 30 9421LIS1 108 HDA69600U44X 32 HDL59045T 33 HE3960U33X 35 HGA81150U31X 32 9421LS8 108 HDA69600U3X 32 HDL59050 26 HE3960U33X 35 HGA81150U31X 32 9422CSF10 108 HDA6960V3 30 HDL59605 33 HE3960U43X 69 HGA81150U44X 32 HDL59605T 33 HE3960U43X 69 HGA81150U44X 32 HDL59605T 33 HE3960U43X 69 HGA81150U43X 32 HDL59605T 33 HE3960U43X 69 HGA81150U44X 32 HGA81150U43X 32 HDL59605CU31X 28 HE3960U43X 69 HGA81150U43X 32 HGA81150U43X 34 HGA81150U33X 34 HGA81150U33X 32 HGA81150U43X 32 HGA81150U33X 34 HGA81	9421LJ1	107	HDA36060U31X32	HDL36040T	33	HDL36150U54X28	HGA3611030
9421L137	94211.14	107					
9421LS   108							
94221S							
9422CSF10 108 HDA\$600U54X 32 HDL\$6050C 26 HE3060U43X 35 HGA\$615U4X 32 9422CSF30 108 HDA\$6070 30 HDL\$6050T 33 HE3060U43X 69 HGA\$615U4X 32 9422CSF30 108 HDA\$6080 30 HDL\$6050C 26 HE3060U44X 89 HGA\$615U53X 32 9422CSF30 108 HDA\$6100 30 HDL\$6050C 26 HE3060U44X 89 HGA\$615U53X 32 9422CSF30 108 HDA\$6100 30 HDL\$6050C 26 HE3060U44X 89 HGA\$615U53X 32 9422CSF30 108 HDA\$6100 30 HDL\$6050C 28 HE3060U44X 89 HGA\$615U53X 32 9422CSF30 108 HDA\$6100 30 HDL\$6050CU31X 28 HE3060U44X 89 HGL\$60515 5.35 9422CSL\$10 108 HDA\$6100U33X 32 HDL\$6050CU31X 28 HE3060U54X 89 HGL\$615 5.35 9422CSL\$10 108 HDA\$6100U35X 32 HDL\$6050CU31X 28 HE3060U54X 39 HGL\$60515 5.35 9422CSL\$10 108 HDA\$6100U35X 32 HDL\$6050CU31X 28 HE3060U54X 35 HGL\$60515 5.35 9422CSL\$10 108 HDA\$6100U35X 32 HDL\$6050CU31X 28 HE3060U54X 35 HGL\$60515 5.35 9422CSL\$10 109 HDA\$6100U54X 32 HDL\$6050CU31X 34 HE3060U54X 35 HGL\$60515 5.35 9422CSL\$10 109 HDA\$6100U54X 32 HDL\$6050CU31X 34 HE3060U54X 35 HGL\$6050 2.66 AL1551D 124 HDA\$610U54X 32 HDL\$6050CU31X 34 HE3100U31X 35 HGL\$6050C 2.66 AL1551D 124 HDA\$6110 30 HDL\$6050CU31X 34 HE3100U31X 35 HGL\$6050C 2.66 AL1551D 124 HDA\$6150 119 HDL\$6050CU3X 34 HE3100U31X 35 HGL\$6050C 2.66 AL406L5 KX 124 HDA\$6150 119 HDL\$6050CU3X 34 HE3100U31X 35 HGL\$6050C 2.66 AL406L5 KX 124 HDA\$6150 119 HDL\$6050CU3X 34 HE3100U31X 35 HGL\$6050C 2.66 AL406L5 KX 124 HDA\$6150U3X 32 HDL\$6050CU3X 34 HE3100U31X 35 HGL\$6050C 2.66 AL406L5 KX 124 HDA\$6150U3X 32 HDL\$6050CU3X 34 HE3100U3X 35 HGL\$6050C 2.66 AL406L5 KX 124 HDA\$6150U3X 32 HDL\$6050CU3X 34 HE3100U3X 35 HGL\$6050C 2.66 AL406L5 KX 124 HDA\$6150U3X 32 HDL\$6050CU3X 34 HE3100U3X 35 HGL\$6050C 2.66 CU350D 124 HDA\$6150U3X 32 HDL\$6050CU3X 38 HE3100U3X 35 HGL\$6050C 2.66 CU350D 124 HDA\$6150U3X 32 HDL\$6050CU3X 38 HE3100U3X 35 HGL\$6050C 2.66 CU350D 124 HDA\$6150U3X 32 HDL\$6050CU3X 38 HE3100U3X 35 HGL\$6050C 2.66 CU350D 124 HDA\$6150U3X 32 HDL\$6050CU3X 38 HE3100U3X 35 HGL\$6050C 2.66 CU350D 124 HDA\$6150U3X 32 HDL\$6050CU3X 38 HE3150U3X 35 HGL\$6050C 2.66 CU350D 124 HDA\$6150U3X 32 HDL\$6050CU3X 38 HBL\$6050C 36 HGL\$6050C 2.66 HDL\$6050C 36 HDL\$6050C 36 HDL\$				HDL360451	33	HE3060U33X35	HGA36150U31X32
9422CSF90 108 HDAS6070 30 HDLS606DT 33 HE3060U43X 69 HGA36150U44X 32 9422CSF90 108 HDAS6080 30 HDLS606DC 26 HE3060U43X 35 HGA36150U54X 32 9422CSF90 108 HDAS6090 30 HDLS606DC 26 HE3060U44X 35 HGA36150U54X 32 9422CSF90 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U44X 35 HGCA961DC 35 9422CSF10 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U44X 35 HGCA961DC 35 9422CSF10 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U44X 35 HGCA961DC 35 9422CSF10 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U54X 35 HGCA961DC 35 9422CSF10 108 HDAS610U44X 32 HDLS606CU31X 32 HDLS606CU31X 35 HGCA961DC 26 9422RSI 108 HDAS610U44X 32 HDLS606CU31X 31 HE306U54X 69 HGLS606C 26 64 LT561D 124 HDAS610U44X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL1561D 124 HDAS610U54X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL1561D 124 HDAS616UU54X 32 HDLS606CU31X 34 HE310U31X 68 HGLS606C 26 AL2561D 124 HDAS616U54X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS616U54X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS616U54X 30 HDLS606CU31X 34 HE310U31X 36 HGLS606C 26 AL2561D 124 HDAS615U31X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS615U31X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS615U31X 32 HDLS606CU31X 34 HE310U31X 36 HGLS606C 26 AL2561D 124 HDAS615U31X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 36 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 CU500LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 28 HE316U31X 35 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 28 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 38 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 34 HGLS606C 26 HDLS606C 26 HDLS606C 26 HDLS606C 36 HDLS6	9421LS8	.108	HDA36060U53X32	HDL36050	26	HE3060U33X68	HGA36150U33X32
9422CSF90 108 HDAS6070 30 HDLS606DT 33 HE3060U43X 69 HGA36150U44X 32 9422CSF90 108 HDAS6080 30 HDLS606DC 26 HE3060U43X 35 HGA36150U54X 32 9422CSF90 108 HDAS6090 30 HDLS606DC 26 HE3060U44X 35 HGA36150U54X 32 9422CSF90 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U44X 35 HGCA961DC 35 9422CSF10 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U44X 35 HGCA961DC 35 9422CSF10 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U44X 35 HGCA961DC 35 9422CSF10 108 HDAS610U31X 32 HDLS606CU31X 28 HE3060U54X 35 HGCA961DC 35 9422CSF10 108 HDAS610U44X 32 HDLS606CU31X 32 HDLS606CU31X 35 HGCA961DC 26 9422RSI 108 HDAS610U44X 32 HDLS606CU31X 31 HE306U54X 69 HGLS606C 26 64 LT561D 124 HDAS610U44X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL1561D 124 HDAS610U54X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL1561D 124 HDAS616UU54X 32 HDLS606CU31X 34 HE310U31X 68 HGLS606C 26 AL2561D 124 HDAS616U54X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS616U54X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS616U54X 30 HDLS606CU31X 34 HE310U31X 36 HGLS606C 26 AL2561D 124 HDAS615U31X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS615U31X 30 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL2561D 124 HDAS615U31X 32 HDLS606CU31X 34 HE310U31X 36 HGLS606C 26 AL2561D 124 HDAS615U31X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 34 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 36 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 CU500LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 AL600LS52K4 124 HDAS615U31X 32 HDLS606CU31X 28 HE310U31X 35 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 28 HE316U31X 35 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 28 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 38 HGLS606C 26 CU500LS52K4 124 HDAS615CU31X 32 HDLS606CU31X 34 HGLS606C 26 HDLS606C 26 HDLS606C 26 HDLS606C 36 HDLS6	9422A1	108	HDA36060U54X 32	HDI 36050C	26	HF3060U43X 35	HGA36150U43X 32
9422CSFS0 108 HDA3690B 30 HDL36960C 26 HE3960U43X 96 HGA36150U53X 32 9422CSF57 108 HDA36910 30 HDL36960CU31X 28 HE3960U44X 96 HGF36000F66 35 9422CSJ70 108 HDA3610U33X 22 HDL36960CU31X 28 HE3960U44X 96 HGF3600F66 35 9422CSJ10 108 HDA3610U33X 22 HDL36960CU3X 28 HE3960U53X 35 HGF3600F16 35 9422CSJ10 108 HDA3610U33X 28 HDL36960CU3X 28 HE3960U53X 96 HGL26015 26 9422ESJ 108 HDA3610U33X 32 HDL36960CU3X 28 HE3960U53X 97 HGL26015 26 HGS5600F16 35 9422CSJ10 108 HDA3610U44X 32 HDL36960CU3X 32 HDL3696							
9422CSF50							
9422CSI70 108 HDA86100 30 HDL8606CU31X 28 HE3060U4X 69 HGF58000F16 35 9422CSI30 108 HDA86100U31X 32 HDL8606CU43X 28 HE3060U53X 69 HGL26015C 26 9422CSI30 108 HDA86100U31X 32 HDL8606CU43X 28 HE3060U53X 69 HGL26015C 26 9422CSI30 108 HDA8610U4XX 32 HDL8606CU43X 28 HE3060U54X 69 HGL26015C 26 9422CSI30 108 HDA8610U4XX 32 HDL8606CU43X 28 HE3060U54X 69 HGL26015C 26 9422CSI30 109 HDA8610U4XX 32 HDL8606TU33X 28 HE3060U54X 69 HGL2602C 25 AL 550HD 124 HDA8610U4XX 32 HDL8606TU33X 34 HE306U54X 69 HGL2602C 25 AL 550HD 124 HDA8610U4XX 32 HDL8606TU33X 34 HE306U54X 69 HGL2602C 25 AL 550HD 124 HDA8610U4XX 32 HDL8606TU33X 34 HE306U54X 69 HGL2602C 25 AL 550HD 124 HDA8610U45X 32 HDL8606TU33X 34 HE306U54X 69 HGL2602C 25 AL 550HD 124 HDA8610U45X 32 HDL8606TU33X 34 HE306U54X 69 HGL2602C 25 AL 550HD 124 HDA8615D 119 HDL8606TU33X 34 HE306U54X 35 HGL2602C 25 AL 550HD 124 HDA8615D 119 HDL8606TU33X 34 HE306U54X 35 HGL2602C 26 AL 550HD 124 HDA8615D 119 HDL8606TU33X 34 HE306U54X 35 HGL2603C 26 AL 550HD 124 HDA8615D 30 HDL8606GU34X 28 HE300U54X 35 HGL2603C 26 AL 550HD 124 HDA8615D 30 HDL8606GU34X 28 HE300U54X 59 HGL2603C 26 AL 550HD 124 HDA8615D 30 HDL8606GU34X 28 HE300U54X 59 HGL2603C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606GU34X 28 HE300U54X 59 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606GU34X 28 HE300U54X 59 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HE300U54X 59 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HE300U54X 59 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HE300U54X 59 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HE300U54X 59 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HE300U54X 69 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HE300U54X 69 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HGL3605U54X 69 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HGL3605U54X 69 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HGL3605U54X 69 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8606U54X 28 HGL3605U54X 69 HGL2604C 26 AL 550HD 124 HDA8615DU34X 32 HDL8							
9422CSJ310 108 HDA96100U31X 32 HDL39660CU33X 28 HE3060U53X 35 HGF36000F15 35 9422CSJ30 108 HDA96100U33X 32 HDL39660CU53X 28 HE3060U54X 35 HGL26015C 26 9422CSJ50 108 HDA9610U43X 32 HDL39660CU53X 28 HE3060U54X 35 HGL26015C 26 9422RSI 109 HDA9610U53X 32 HDL39660CU53X 38 HE3060U54X 35 HGL26015C 26 9422RSI 109 HDA9610U53X 32 HDL39600TU31X 34 HE310U31X 35 HGL2602C 26 AL50HD 124 HDA9610U53X 32 HDL39600TU31X 34 HE310U31X 35 HGL2602C 26 AL50HD 124 HDA9610U53X 34 HDL39606TU31X 35 HGL2602C 26 AL50HD 124 HDA9610U53X 34 HDL39606TU31X 34 HE310U33X 68 HGL2602C 26 AL50HD 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U33X 68 HGL2602C 26 AL50HD 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U33X 68 HGL2602C 26 AL50HD 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U33X 68 HGL2603C 26 AL60HD584X 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U44X 35 HGL2603C 26 AL60HD584X 124 HDA9615D 6 HD 19 HDL39606TU54X 34 HE310U44X 35 HGL2603C 26 AL60HD584X 124 HDA9615D 6 HD 19 HDL39606TU54X 34 HE310U44X 69 HGL2603C 26 AL60HD584X 124 HDA9615D033X 32 HDL3960HD33X 28 HE310U53X 35 HGL2603C 26 AL60HD584X 124 HDA9615D033X 32 HDL3960HJ3X 28 HE310U53X 35 HGL26040 26 AL60HD584X 124 HDA9615D033X 32 HDL3960HJ3X 28 HE310U53X 35 HGL26040 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ3X 28 HE310U54X 35 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D05C 26 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D05C 26 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D05C 26 HDL3960HJ4X 34 HE310U43X 35 HGL2604C 26 CU28DJD 124 HDA9615D05C	9422CSF50	. 108	HDA3609030	HDL36060C	26	HE3060U44X35	HGA36150U54X32
9422CSJ310 108 HDA96100U31X 32 HDL39660CU33X 28 HE3060U53X 35 HGF36000F15 35 9422CSJ30 108 HDA96100U33X 32 HDL39660CU53X 28 HE3060U54X 35 HGL26015C 26 9422CSJ50 108 HDA9610U43X 32 HDL39660CU53X 28 HE3060U54X 35 HGL26015C 26 9422RSI 109 HDA9610U53X 32 HDL39660CU53X 38 HE3060U54X 35 HGL26015C 26 9422RSI 109 HDA9610U53X 32 HDL39600TU31X 34 HE310U31X 35 HGL2602C 26 AL50HD 124 HDA9610U53X 32 HDL39600TU31X 34 HE310U31X 35 HGL2602C 26 AL50HD 124 HDA9610U53X 34 HDL39606TU31X 35 HGL2602C 26 AL50HD 124 HDA9610U53X 34 HDL39606TU31X 34 HE310U33X 68 HGL2602C 26 AL50HD 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U33X 68 HGL2602C 26 AL50HD 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U33X 68 HGL2602C 26 AL50HD 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U33X 68 HGL2603C 26 AL60HD584X 124 HDA9615D 15 HD 19 HDL39606TU44X 34 HE310U44X 35 HGL2603C 26 AL60HD584X 124 HDA9615D 6 HD 19 HDL39606TU54X 34 HE310U44X 35 HGL2603C 26 AL60HD584X 124 HDA9615D 6 HD 19 HDL39606TU54X 34 HE310U44X 69 HGL2603C 26 AL60HD584X 124 HDA9615D033X 32 HDL3960HD33X 28 HE310U53X 35 HGL2603C 26 AL60HD584X 124 HDA9615D033X 32 HDL3960HJ3X 28 HE310U53X 35 HGL26040 26 AL60HD584X 124 HDA9615D033X 32 HDL3960HJ3X 28 HE310U53X 35 HGL26040 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ3X 28 HE310U54X 35 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D043X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D05C 26 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D05C 26 HDL3960HJ4X 32 HDL3960HJ4X 33 HGL2604C 26 CU28DJD 124 HDA9615D05C 26 HDL3960HJ4X 34 HE310U43X 35 HGL2604C 26 CU28DJD 124 HDA9615D05C	9422CSF70	.108	HDA3610030	HDL36060CU31X	28	HE3060U44X69	HGF36000F0635
9422CSLSI30							
9422FSI 108 HDA36100U43X 32 HDL36660CU53X 28 HE3060U54X 35 HGL26015C 26 9422FSI 109 HDA3610U53X 32 HDL36660TJ31X 34 HE310U31X 35 HGL2602C 26 9422FSI 109 HDA3610U53X 32 HDL36660TJ31X 34 HE310U31X 35 HGL2602C 26 AL175LD 124 HDA36110U53X 32 HDL36660TJ31X 34 HE310U31X 35 HGL2602C 26 AL175LD 124 HDA36110 30 HDL3660TU43X 34 HE310U33X 35 HGL2602C 26 AL175LD 124 HDA3615C 119 HDL3660TU43X 34 HE310U33X 35 HGL2602C 26 AL175LD 124 HDA3615C 119 HDL3660TU43X 34 HE310U33X 35 HGL2603C 26 AL400L61K3 124 HDA3615D 119 HDL3660TU53X 34 HE310U43X 35 HGL2603C 26 AL400L61K3 124 HDA3615D 119 HDL3660TU53X 34 HE310U43X 35 HGL2603C 26 AL400L61K3 124 HDA3615D 30 HDL3660TU53X 34 HE310U43X 35 HGL2603C 26 AL400L61K3 124 HDA3615D 31 HD 1500E001X 32 HE310U43X 35 HGL2603C 26 AL600L672K3 124 HDA3615D3 119 HDL3660U31X 28 HE310U43X 35 HGL2603C 26 AL600L672K3 124 HDA3615D3 32 HDL3660U31X 28 HE310U45X 36 HGL2603C 26 AL600L672K3 124 HDA3615D33X 32 HDL38600U3X 28 HE310U45X 35 HGL2603C 26 AL600L672K3 124 HDA3615D3X3 32 HDL38600U3X 28 HE310U45X 35 HGL2603C 26 AL600L672K3 124 HDA3615D3X3 32 HDL38600U43X 28 HE310U45X 35 HGL2603C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U44X 28 HE310U45X 35 HGL2603C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U44X 28 HE310U45X 35 HGL2603C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U44X 28 HE310U45X 35 HGL2605C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U54X 28 HE310U45X 35 HGL2605C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U54X 28 HE310U45X 35 HGL2605C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U54X 28 HE310U45X 35 HGL2605C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U54X 38 HE310U35X 35 HGL2605C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U54X 35 HGL2605C 26 AL600L672K3 124 HDA3615D3X3X 32 HDL38600U54X 38 HGL3600C 26 AL600L672K3 124 HDA3615D3X3X 35 HDL3600C 26 HDL360C							
9422RSI 108 HDA36100J44X 32 HDL36660T 33 HE3060U54X 69 HGL2602C 26 AL15DHD 124 HDA36100J54X 32 HDL36660TJ31X 34 HE3100J31X 35 HGL2602C 26 AL15DHD 124 HDA36110 30 HDL36600TJ3XX 34 HE3100J31X 68 HGL2602C 26 AL15DHD 124 HDA3611C 30 HDL36600TJ4XX 34 HE3100J3X 68 HGL2602C 26 AL25DJD 124 HDA3615C 19 HDL36600TJ4XX 34 HE3100J3X 68 HGL2602C 26 AL25DJD 124 HDA3615D 19 HDL36600TJ4XX 34 HE3100J3X 68 HGL2603C 26 AL400L611X3 124 HDA3615D 19 HDL36600TJ4XX 34 HE3100J4X 35 HGL2603C 26 AL400L61X4 124 HDA3615D 30 HDL3600TJ5XX 34 HE3100J4XX 35 HGL2603C 26 AL400L61X4 124 HDA3615D 30 HDL3600TJ5XX 34 HE3100J4XX 35 HGL2603C 26 AL600LFSEX 124 HDA3615DJ3X 32 HDL3600J3XX 28 HE310U5XX 35 HGL2603C 26 AL600LSEXK 124 HDA3615DJ3XX 32 HDL3600J4XX 28 HE310U5XX 35 HGL2603C 26 AL600LSEXK 124 HDA3615DJ3X 32 HDL3600J4XX 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ4X 32 HDL3600J4XX 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ4X 32 HDL3600J4XX 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ4X 32 HDL3600J4X 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 32 HDL3600J4X 38 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 32 HDL3600J4X 38 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 37 HDL3660J4X 38 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 37 HDL3660J4X 38 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 37 HDL3660J5X 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 37 HDL3660J5X 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 37 HDL3660J5X 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 37 HDL3660J5X 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 124 HDA3615DJ5X 37 HDL3660J5X 28 HE310U5XX 35 HGL2603C 26 CUSSDJD 128 HDA3660J5X 28 HDL3660C 26 CUSSDJD 128 HDA3660J5X 28 HDL3660C 26 CUSSDJD 128 HDA3660J5X 28 HDL3660C 26 CUSSDJD 128 HDL3660C 26 CUSS							
9422RS			HDA36100U43X32	HDL36060CU53X	28	HE3060U54X35	HGL26015C26
9422RS	9422RSI	.108	HDA36100U44X32	HDL36060T	33	HE3060U54X69	HGL2602026
ALTSDID 124 HDA3610U54X 32 HDL36660TU38X 34 HE3100U31X 68 HGL26025C 26 AL25DID 124 HDA36110 30 HDL36660TU34X 34 HE3100U33X 55 HGL26025C 26 AL25DID 124 HDA36150 119 HDL36600TU34X 34 HE3100U33X 56 HGL26030C 26 AL25DID 124 HDA36150 119 HDL36600TU54X 34 HE3100U34X 56 HGL26030C 26 AL400L611K4 124 HDA36150 139 HDL36600TU54X 34 HE3100U44X 65 HGL26035C 26 AL400L611K4 124 HDA36150 139 HDL3600DU31X 28 HE3100U44X 69 HGL26035C 26 AL600L552K3 124 HDA3615003X 2 HDL3600DU31X 28 HE3100U44X 69 HGL26035C 26 AL600L552K4 124 HDA36150U31X 32 HDL3600DU31X 28 HE3100U5XX 69 HGL26040C 26 CU50DID 124 HDA36150U45X 32 HDL3600DU31X 28 HE3100U5XX 69 HGL2604C 26 CU50DID 124 HDA36150U45X 32 HDL3600DU31X 28 HE3100U54X 35 HGL2604C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE3100U54X 35 HGL2604C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE3100U5XX 69 HGL2604C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U5XX 69 HGL2604C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U5XX 69 HGL2605C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U5XX 69 HGL2605C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U3XX 88 HGL2605C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U3XX 88 HGL2605C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U3XX 88 HGL2605C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U3XX 88 HGL2605C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600DU3X 28 HE310U3XX 88 HGL2605C 26 CU40DL611K4 124 HDA36150U5XX 32 HDL3600C 26 HE3150U4XX 35 HGL2605C 26 CU40DL611K4 128 HDL2605C 26 HDL3600C 26 HE3150U4XX 35 HGL2600C 26 CU40DL611K4 128 HDL2605C 26 HDL3600C 26 HE3150U4XX 35 HGL2600C 26 CU40DL611K4 128 HDL2605C 26 HDL3600C 26 HE3150U4XX 36 HGL2600C 26 CU40DL611K4 128 HDL2605C 26 HDL3600C 26 HE3150U4XX 36 HGL2600C 26 CU40DL611K4 128 HDL2605C 26 HDL3600C 26 HE3150U4XX 36 HGL2600C 26 CU40DL611K4 128 HDL2605C 26 HDL3600C 36 HDL3600C 36 HDL3600C 30 HGL2605C 36 HDL3600C 30 HGL260				HDI 36060TU31X	34	HF3100U31X 35	HGI 26020C 26
ALTSUD 124 HDA36115 30 HDL36660TU43X 34 HE3100U33X 85 HGL26005 26 AL400L61K3 124 HDA36150 30 HDL36660TU43X 34 HE3100U43X 35 HGL2603C 26 AL400L61K4 124 HDA36150 30 HDL36660TU53X 34 HE3100U43X 35 HGL2603C 26 AL600LF2K3 124 HDA36150 30 HDL36660TU53X 34 HE3100U44X 35 HGL2603C 26 AL600LF2K3 124 HDA36150U31X 32 HDL36060U31X 28 HE3100U44X 69 HGL2603C 26 AL600LS2K4 124 HDA36150U31X 32 HDL36060U31X 28 HE3100U44X 35 HGL2604C 26 AL600LS2K4 124 HDA36150U31X 32 HDL36060U31X 28 HE3100U53X 36 HGL2604C 26 CU250D 124 HDA36150U31X 32 HDL36060U43X 28 HE3100U54X 36 HGL2604C 26 CU250D 124 HDA36150U31X 32 HDL36060U34X 28 HE3100U54X 36 HGL2604C 26 CU400L61K3 124 HDA36150U3X 32 HDL36060U54X 28 HE3100U54X 36 HGL2604C 26 CU400L61K3 124 HDA36150U53X 32 HDL36060U54X 28 HE3100U54X 36 HGL2604C 26 CU400L61K4 124 HDA36150U53X 32 HDL36060U54X 28 HE3100U54X 69 HGL2604C 26 CU400L61K4 124 HDA36150U54X 32 HDL3607C 26 HE3150U31X 35 HGL2606C 26 CU400L61K4 124 HDA36150U54X 32 HDL3607C 26 HE3150U31X 36 HGL2606C 26 CU600L52K3 124 HDP36000F16 35 HDL3607C 26 HE3150U31X 36 HGL2606C 26 CU600L52K3 124 HDP3600F15 26 HDL3607C 26 HE3150U3X 36 HGL2606C 26 CYA60HD 128 HDL2601C 26 HDL3608C 26 HE3150U43X 35 HGL2606C 26 CYA60HD 128 HDL2601C 26 HDL3608C 26 HE3150U43X 35 HGL2606C 26 CYA60HD 128 HDL2601C 26 HDL3608C 26 HE3150U43X 35 HGL2606C 26 CYA60HD 128 HDL2602C 26 HDL3608C 26 HE3150U43X 35 HGL2607C 26 CYA60HD 128 HDL2602C 26 HDL3608C 26 HE3150U43X 35 HGL2606C 26 CYA60U31K4 128 HDL2602C 26 HDL3608C 26 HE3150U43X 35 HGL2606C 26 CYA60U31K4 128 HDL2602C 26 HDL3609C 26 HE3150U43X 35 HGL2607C 26 CYA60U31K4 128 HDL2602C 26 HDL3609C 26 HE3150U43X 35 HGL2607C 26 CYA60U31K4 128 HDL2602C 26 HDL3609C 26 HE3150U43X 35 HGL2609C 26 CYA60U31K4 128 HDL2602C 26 HDL3609C 26 HE3150U43X 35 HGL2609C 26 CYA60U31K4 128 HDL2602C 26 HDL3609C 26 HE3150U43X 35 HGL2609C 26 HDL3609C 26 HDL3609C 30 HGL2609C 36 HDL3609C 30 HGL2609C 36 HDL3609C 30 HGL36005C 30 HGL36005C 30 HGL36							
AL250UD							
AL400L61K3 124 HDA36150 319 HDL36060TU53X 34 HE3100U43X 35 HGL260305 26 AL600L52K3 124 HDA36150 30 HDL36060U31X 28 HE3100U44X 35 HGL26035C 26 AL600L52K3 124 HDA36150U31X 32 HDL36060U31X 28 HE310U5X 35 HGL26035C 26 AL600L52K4 124 HDA36150U31X 32 HDL36060U31X 28 HE310U5X 35 HGL26040 26 CU150HD 124 HDA36150U3X 32 HDL36060U31X 28 HE310U5X 35 HGL26040 26 CU250LD 124 HDA36150U3X 32 HDL36060U43X 28 HE310U5X 35 HGL26045 26 CU250LD 124 HDA36150U5X 32 HDL36060U43X 28 HE310U5X 35 HGL26045 26 CU400L61K3 124 HDA36150U5X 32 HDL36060U43X 28 HE310U5X 35 HGL26045 26 CU400L61K3 124 HDA36150U5X 32 HDL36060U5X 28 HE310U5X 35 HGL26045 26 CU400L61K3 124 HDA36150U5X 32 HDL36070 26 HE3150U31X 35 HGL26050 26 CU400L61K3 124 HDA36150U5X 32 HDL36070 26 HE3150U31X 35 HGL26050 26 CU400L5EXEX 124 HDF36000F16 35 HDL36070 26 HE3150U3X 35 HGL26060 26 CU600L5EXEX 124 HDF36000F15 35 HDL36070 26 HE3150U3X 35 HGL26060 26 CU600L5EXEX 124 HDF36000F15 35 HDL36070 26 HE3150U3X 35 HGL26060 26 CVANDON 128 HDL26015 26 HDL36080 26 HE3150U3X 35 HGL26060 26 CVA150HD 128 HDL26015 26 HDL36080 26 HE3150U3X 35 HGL26060 26 CVA150HD 128 HDL26020 26 HDL36080 26 HE3150U3X 35 HGL26060 26 CVA150HD 128 HDL26020 26 HDL36080 26 HE3150U3X 35 HGL26080 26 CVA150HD 128 HDL26030 26 HDL36090 26 HE3150U3X 35 HGL26080 26 CVA150HD 128 HDL26020 26 HDL36090 26 HE3150U3X 35 HGL26080 26 CVA150HD 128 HDL26030 26 HDL36090 26 HE3150U3X 35 HGL26080 26 CVA250JJ 128 HDL26030 26 HDL36090 31 HE3150U3X 35 HGL26080 26 CVA250JJ 128 HDL26050 26 HDL36000 26 CVA400L51K3 128 HDL26050 26 HDL36000 26 HE3150U4X 35 HGL26080 26 CVA400L51K3 128 HDL26050 26 HDL36000 26 HE3150U4X 36 HGL26080 26 CVA400L51K3 128 HDL26050 26 HDL36100 26 CVA400L51K3 128 HDL26050 26 HDL36100 27 CVA400L51K3 128 HDL26050 26 HDL36100 27 CVA400L51K3 128 HDL26040 26 HDL36100 27 CVA400L51K3 128 HDL							
AL400L61K4	AL250JD	. 124	HDA3612530	HDL36060TU44X	34	HE3100U33X68	HGL2603026
AL400L61K4	AL400L61K3	124	HDA36150 119	HDL36060TU53X	34	HE3100U43X35	HGL26030C26
ALGOOLFSEXS 124 HDA3615001X 32 HDL36060U31X 28 HE3100U53X 35 HGL26040 26 ALGOOLSSEX 124 HDA36150U31X 32 HDL36060U33X 28 HE3100U53X 35 HGL26040 26 CU150HD 124 HDA36150U33X 32 HDL36060U43X 28 HE3100U53X 35 HGL26040 26 CU150HD 124 HDA36150U43X 32 HDL36060U43X 28 HE3100U54X 35 HGL26045 26 CU250LD 124 HDA36150U43X 32 HDL36060U43X 28 HE3100U54X 35 HGL26045 26 CU250LD 124 HDA36150U43X 32 HDL36060U53X 28 HE3100U54X 35 HGL26045 26 CU250LD 124 HDA36150U43X 32 HDL36060U53X 28 HE3100U54X 35 HGL26055 26 CU400L61K3 124 HDA36150U53X 32 HDL36060U53X 28 HE3150U31X 35 HGL26055 26 CU400L61K4 124 HDA36150U53X 32 HDL36070 26 HE3150U31X 35 HGL26050 26 CU600L55EX 124 HDP36000F6 35 HDL36070 26 HE3150U33X 35 HGL26060 26 CU600L55EX 124 HDP36000F6 35 HDL36070 26 HE3150U33X 35 HGL26060 26 CU600L55EX 124 HDL26015 26 HDL36070 26 HDL36070 33 HE3150U33X 35 HGL26060 26 CVA5060HD 128 HDL26015 26 HDL36080 26 HB3150U43X 35 HGL26070 26 CVA5060HD 128 HDL26020 26 HDL36080 26 HB3150U43X 35 HGL26070 26 CVA500LD 128 HDL26020 26 HDL36080 26 HB3150U44X 35 HGL26080 26 CVA50LD 128 HDL26020 26 HDL36090 26 HB3150U44X 35 HGL26080 26 CVA50LD 128 HDL26020 26 HDL36090 26 HB3150U44X 35 HGL26080 26 CVA40LB 1K4 128 HDL26025 26 HDL36090 26 HB3150U44X 35 HGL26080 26 CVA40LB 1K4 128 HDL26025 26 HDL36090 26 HB3150U34X 35 HGL26090 26 CVA40LB 1K4 128 HDL26030 26 HDL36100 26 HDL36100 26 CVA40LB 1K4 128 HDL26030 26 HDL36100 26 HDL36100 26 HDL36100 26 CVA40LB 1K4 128 HDL26030 26 HDL36100 26 HDL36100 26 HDL36100 26 HDL36100 26 CVA40LB 1K4 128 HDL26030 26 HDL36100 26 HD							
ALGOOLSSEX 124 HDA36150U31X 32 HDL36660U33X 28 HE3100U53X 69 HGL26040 26 CU150HD 124 HDA36150U33X 32 HDL36660U44X 28 HE3100U54X 69 HGL26045 26 CU250LD 124 HDA36150U43X 32 HDL36660U44X 28 HE3100U54X 69 HGL26045 26 CU250LD 124 HDA36150U43X 32 HDL36660U54X 28 HE3100U54X 69 HGL26045 26 CU400L61K3 124 HDA36150U34X 32 HDL36660U54X 28 HE3150U31X 35 HGL26045 26 CU400L61K3 124 HDA36150U54X 32 HDL36670 26 HE3150U31X 35 HGL26050 26 CU400L61K3 124 HDA36150U54X 32 HDL36670 26 HE3150U31X 35 HGL26050 26 CU400L61K3 124 HDA36150U54X 32 HDL36070 26 HE3150U31X 35 HGL26050 26 CU400L55XX 124 HDP36000F06 35 HDL36070 26 HE3150U33X 35 HGL26050 26 CU400L55XX 124 HDP36000F06 35 HDL36070 26 HE3150U33X 35 HGL26050 26 CU400L55XX 124 HDP36000F15 35 HDL36070 33 HE3150U33X 35 HGL26070 26 CV4060HD 128 HDL26015C 26 HDL36080 26 HB3150U33X 35 HGL26070 26 CV4060HD 128 HDL26015C 26 HDL36080 26 HB3150U43X 35 HGL26070 26 CV4150HD 128 HDL26015C 26 HDL36080C 26 HB3150U44X 35 HGL26070 26 CV4150HD 128 HDL26020 26 HDL36080C 36 HB3160U44X 35 HGL26070 26 CV4150HD 128 HDL26020 26 HDL36089C 36 HB3150U44X 35 HGL26080 26 CV4400L31K3 128 HDL26025C 26 HDL36090C 36 HB3150U44X 35 HGL26080 26 CV4400L31K3 128 HDL26025C 26 HDL36090T 33 HB3150U55X 35 HGL26090 26 CV4400L31K3 128 HDL26025C 26 HDL36090T 33 HB3150U55X 35 HGL26090 26 CV4400L31K3 128 HDL26035 26 HDL36100C 36 HB3160U54X 35 HGL26000 26 CV4400L51K3 128 HDL26035 26 HDL36100C 37 HDL2605X 35 HGL26000 26 CV4400L51K3 128 HDL26035 26 HDL36100C 38 HGL2605() 30 HGL26110 26 CV4400L51K4 128 HDL26035 26 HDL36100CU33X 28 HGA2605() 30 HGL26110 26 CV4400L51K4 128 HDL26035 26 HDL36100CU33X 28 HGA26005() 30 HGL26110 26 CV4400L51K4 128 HDL26035 26 HDL36100CU33X 38 HGA26005() 30 HGL26110 26 CV4400L51K4 128 HDL26045C 26 HDL36100CU33X 38 HGA26005() 30 HGL26110 26 CV4400L51K4 128 HDL26045 26 HDL36100CU33X 38 HGA26005() 30 HGL36150C 26 HDL36100CU33X 38 HGA26005() 30 HGL36150C 26 HDL36100TU33X 34 HGA26005() 30 HGL36150C 26 HDL36100TU33X 34 HGA26005() 30 HGL36015C 26 HDL36100TU33X 34 HGA26005() 30 HGL36015C 26 HDL36100TU33X 34 HGA2600							
ALBODUSSZK4   124							
CU150HD 124 HDA36150U43X 32 HD136060U53X 28 HE3100U54X 35 HGL26045 26 CU250LD 124 HDA36150U43X 32 HD136060U53X 28 HE3150U31X 35 HGL26050 26 CU400L61K3 124 HDA36150U53X 32 HD136070C 26 HE3150U31X 35 HGL26050 26 CU400L61K3 124 HDA36150U53X 32 HD136070C 26 HE3150U31X 35 HGL26060 26 CU600L52K3 124 HDF36000F16 35 HD136070C 26 HE3150U33X 35 HGL26060 26 CU600L52K3 124 HDF36000F16 35 HD136070C 26 HE3150U33X 35 HGL26060 26 CU600L52K3 124 HDF36000F15 35 HD136070C 26 HE3150U33X 35 HGL26060 26 CU600L52K4 124 HDF36000F15 26 HD136070T 33 HE3150U33X 35 HGL26070 26 CU600L52K4 124 HD126015 26 HD136080 26 HE3150U33X 35 HGL26070 26 CV34150HD 128 HD126015 26 HD136080 26 HE3150U43X 35 HGL26070 26 CV34150HD 128 HD126020 26 HD136080T 33 HE3150U44X 35 HGL26080 26 CV34150HD 128 HD126020 26 HD136080T 33 HE3150U44X 35 HGL26080 26 CV34150HD 128 HD126025 26 HD136090 26 HE3150U43X 35 HGL26080 26 CV34150HD 128 HD126025 26 HD136090T 33 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126025 26 HD136090T 33 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126030 26 HD136100C 26 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126030 26 HD136100C 26 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126030 26 HD136100C 26 HE3150U43X 36 HGL26100 26 CV3400L31K3 128 HD126035 26 HD136100C 26 HE3150U43X 37 HGL26100 26 CV3400L31K3 128 HD126035 26 HD136100CU33X 28 HG3605() 30 HGL26110 26 CV3400L31K3 128 HD126035 26 HD136100CU33X 28 HG3605() 30 HGL26110 26 CV3400L31K4 128 HD126040 26 HD136100CU33X 28 HG3605() 30 HGL26150 26 CV3400L32K4 128 HD126040 26 HD136100CU33X 28 HG3605() 30 HGL26150 26 HD136100CU33X 28 HG3605() 30 HGL26150 26 HD136100CU33X			HDA36150U31X32	HDL36060U33X	28	HE3100U53X35	HGL2604026
CU150HD 124 HDA36150U43X 32 HD136060U53X 28 HE3100U54X 35 HGL26045 26 CU250LD 124 HDA36150U43X 32 HD136060U53X 28 HE3150U31X 35 HGL26050 26 CU400L61K3 124 HDA36150U53X 32 HD136070C 26 HE3150U31X 35 HGL26050 26 CU400L61K3 124 HDA36150U53X 32 HD136070C 26 HE3150U31X 35 HGL26060 26 CU600L52K3 124 HDF36000F16 35 HD136070C 26 HE3150U33X 35 HGL26060 26 CU600L52K3 124 HDF36000F16 35 HD136070C 26 HE3150U33X 35 HGL26060 26 CU600L52K3 124 HDF36000F15 35 HD136070C 26 HE3150U33X 35 HGL26060 26 CU600L52K4 124 HDF36000F15 26 HD136070T 33 HE3150U33X 35 HGL26070 26 CU600L52K4 124 HD126015 26 HD136080 26 HE3150U33X 35 HGL26070 26 CV34150HD 128 HD126015 26 HD136080 26 HE3150U43X 35 HGL26070 26 CV34150HD 128 HD126020 26 HD136080T 33 HE3150U44X 35 HGL26080 26 CV34150HD 128 HD126020 26 HD136080T 33 HE3150U44X 35 HGL26080 26 CV34150HD 128 HD126025 26 HD136090 26 HE3150U43X 35 HGL26080 26 CV34150HD 128 HD126025 26 HD136090T 33 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126025 26 HD136090T 33 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126030 26 HD136100C 26 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126030 26 HD136100C 26 HE3150U43X 36 HGL26080 26 CV3400L31K3 128 HD126030 26 HD136100C 26 HE3150U43X 36 HGL26100 26 CV3400L31K3 128 HD126035 26 HD136100C 26 HE3150U43X 37 HGL26100 26 CV3400L31K3 128 HD126035 26 HD136100CU33X 28 HG3605() 30 HGL26110 26 CV3400L31K3 128 HD126035 26 HD136100CU33X 28 HG3605() 30 HGL26110 26 CV3400L31K4 128 HD126040 26 HD136100CU33X 28 HG3605() 30 HGL26150 26 CV3400L32K4 128 HD126040 26 HD136100CU33X 28 HG3605() 30 HGL26150 26 HD136100CU33X 28 HG3605() 30 HGL26150 26 HD136100CU33X	AL600LS52K4	.124	HDA36150U33X32	HDL36060U43X	28	HE3100U53X69	HGL26040C26
CU2SOJD 124 HDA36150U44X 32 HDL3660GUS3X 28 HE310OU54X 69 HGL26045C 26 CU400L61K3 124 HDA36150U54X 32 HDL3660GUS4X 28 HE3150U31X 35 HGL2605C 26 CU400L61K4 124 HDA36150U54X 32 HDL36607C 26 HE315DU31X 68 HGL26050C 26 CU600L552K3 124 HDF36000F16 35 HDL36070C 26 HE315DU31X 68 HGL26050C 26 CU600LS52K3 124 HDF36000F15 35 HDL36070T 33 HE315OU33X 68 HGL2606C 26 CU600LS52K4 124 HDF36000F15 26 HDL36080 26 HE315DU33X 68 HGL26060C 26 CU600LS52K4 124 HDL26015 26 HDL36080 26 HE315DU3XX 69 HGL26070C 26 CVA060HD 128 HDL26015C 26 HDL36080 33 HE315DU3XX 69 HGL26070C 26 CVA150HD 128 HDL2602C 26 HDL36080T 33 HE315DU4XX 69 HGL26070C 26 CVA150HD 128 HDL2602C 26 HDL36090C 26 HE315DU4XX 69 HGL26080 26 CVA260J3 128 HDL2602C 26 HDL36090C 26 HE315DU4XX 69 HGL26080 26 CVA260J3 128 HDL26025C 26 HDL36090C 26 HE315DU4XX 69 HGL26080 26 CVA400L31K3 128 HDL26025C 26 HDL36090C 26 HE315DU5XX 69 HGL26080 26 CVA400L31K4 128 HDL2603C 26 HDL36090C 26 HE315DU5XX 69 HGL26090C 26 CVA400L31K4 128 HDL2603C 26 HDL36090C 26 HE315DU5XX 69 HGL26090C 26 CVA400L51K3 128 HDL2603C 26 HDL36100 26 CVA400L51K4 128 HDL2603C 26 HDL3610C 26 HE315DU5XX 35 HGL26100 26 CVA400L51K4 128 HDL2603C 26 HDL3610C 26 HE315DU5XX 35 HGL26100 26 CVA400L51K4 128 HDL2603C 26 HDL3610CU3X1X 28 HGA26015() 30 HGL26110 26 CVA400L51K4 128 HDL2603C 26 HDL3610CU3X1X 28 HGA26015() 30 HGL26110 26 CVA400L51K4 128 HDL2603C 26 HDL3610CU3X1X 28 HGA2605() 30 HGL26110 26 CVA400L51K4 128 HDL2603C 26 HDL3610CU3X1X 28 HGA2605() 30 HGL2615C 26 CVA600L32K4 128 HDL2604C 26 HDL3610CU3X1X 28 HGA2605() 30 HGL2615C 26 CVA600L32K4 128 HDL2604C 26 HDL3610CU3X1X 28 HGA2605() 30 HGL2615C 26 CVA600L32K4 128 HDL2604C 26 HDL3610CU3X1X 34 HGA2605() 30 HGL2615C 26 CVA600L52K4 128 HDL2604C 26 HDL3610OCU3X 28 HGA26005() 30 HGL2615C 26 CVA600L52K4 128 HDL2604C 26 HDL3610CU3X1X 34 HGA2605() 30 HGL2615C 26 CVA600L52K4 128 HDL2604C 26 HDL3610OCU3X 34 HGA26005() 30 HGL2615C 26 HDL3610OCU3X 34 HGA26005()			HDA36150U43X32	HDL36060U44X	28	HE3100U54X35	HGL2604526
CUJA0L61K3 124 HDA36150U53X 32 HDL36060U54X 28 HE3150U31X 35 HGL26050 26 CUJA0L61K4 124 HDA36150U53X 32 HDL36070C 26 HE3150U31X 68 HGL26050C 26 CUG00L52K3 124 HDF36000F16 35 HDL36070C 26 HE3150U33X 35 HGL26060 26 CUG00L52K3 124 HDF36000F15 35 HDL36070T 33 HE3150U33X 35 HGL26070 26 CUG00L52K4 124 HDL26015 26 HDL36080C 26 HE3150U43X 35 HGL26070 26 CYA060HD 128 HDL26015C 26 HDL36080C 26 HE3150U43X 35 HGL26070 26 CYA150HD 128 HDL2602C 26 HDL36080C 26 HE3150U43X 35 HGL26070 26 CYA150HD 128 HDL2602C 26 HDL36090 26 HE3150U43X 35 HGL26080 26 CYA150HD 128 HDL2602C 26 HDL36090 26 HE3150U43X 35 HGL26080 26 CYA150HD 128 HDL2602C 26 HDL36090 26 HE3150U43X 35 HGL26080 26 CYA40L31K3 128 HDL2602C 26 HDL36090 26 HE3150U43X 35 HGL26080 26 CYA40L31K3 128 HDL2602C 26 HDL36090 26 HE3150U43X 35 HGL26080 26 CYA40L31K4 128 HDL2602C 26 HDL36090 33 HE3150U53X 35 HGL26080 26 CYA40L31K4 128 HDL2603C 26 HDL36100 26 HE3150U53X 35 HGL26090 26 CYA40L51K4 128 HDL2603C 26 HDL36100 26 HE3150U53X 35 HGL26090 26 CYA40L51K4 128 HDL2603C 26 HDL36100C 26 HDL36100C 26 CYA40L51K4 128 HDL2603C 26 HDL36100C 26 HDL36100C 36 HGL26100C 26 CYA40L51K4 128 HDL2603C 26 HDL36100C 38 HGL2605C 30 HGL26100 26 CYA40L51K4 128 HDL2603C 26 HDL36100C 38 HGL2605C 30 HGL26110C 26 CYA40L51K4 128 HDL2603C 26 HDL36100CU33X 28 HGA2605() 30 HGL26110C 26 CYA600L32K3 128 HDL26045 26 HDL36100CU33X 28 HGA2605() 30 HGL26110C 26 CYA600L32K4 128 HDL2604C 26 HDL36100CU33X 28 HGA2605() 30 HGL26110C 36 CYA600L32K4 128 HDL2604C 26 HDL36100CU33X 34 HGA2605() 30 HGL26150C 26 CYA600L52K4 128 HDL2604C 26 HDL36100CU33X 34 HGA26005() 30 HGL26150C 26 HDL36100TU33X 34 HGA26005() 30 HGL26150C 26 CYA600L52K4 128 HDL2604C 26 HDL36100TU33X 34 HGA26005() 30 HGL26150C 26 HDL36100TU33X 34 HGA26005() 30 HGL26150C 26 HDL36100TU33X 34 HGA26005() 30 HGL26150C 26 HDL36100TU33X 34 HGA26000() 30 HGL36015C 26 HDL36100TU34X 34 HGA26000()							
CU400L61K4 124 HDA36150U54X 32 HDL36070 26 HE3150U31X 88 HGL26050C 26 CU600L552K3 124 HDF36000F06 35 HDL36070C 26 HE3150U33X 35 HGL26060 26 CU600L552K3 124 HDF36000F15 35 HDL36070T 33 HE3150U33X 88 HGL26070 26 CU600L552K4 124 HDL26015 26 HDL36080C 26 HE3150U43X 89 HGL26070 26 CVA060HD 128 HDL26015 26 HDL36080C 26 HE3150U43X 89 HGL26070 26 CVA150HD 128 HDL26020 26 HDL36080C 36 HE3150U44X 89 HGL26080 26 CVA150HD 128 HDL26020 26 HDL36080T 33 HE3150U44X 89 HGL26080 26 CVA150HD 128 HDL26025 26 HDL36080T 33 HE3150U44X 89 HGL26080 26 CVA250J3 128 HDL26025 26 HDL36090C 26 HE3150U43X 89 HGL26080 26 CVA250J3 128 HDL26025 26 HDL36090C 26 HE3150U53X 89 HGL26090 26 CVA400L31K3 128 HDL26025 26 HDL36090C 26 HE3150U53X 89 HGL26090 26 CVA400L31K3 128 HDL26035 26 HDL36090C 26 HE3150U53X 89 HGL26090 26 CVA400L31K3 128 HDL26030 26 HDL36100 26 HE3150U54X 35 HGL26100 26 CVA400L51K4 128 HDL26035 26 HDL36100C 26 HE3150U54X 35 HGL26100 26 CVA400L51K4 128 HDL26035 26 HDL36100C 36 HE3150U54X 69 HGL26100 26 CVA400L71K3 128 HDL26035 26 HDL36100CU31X 28 HGA2605(5) 30 HGL26110 26 CVA400L71K3 128 HDL26035 26 HDL36100CU31X 28 HGA2605(5) 30 HGL26110 26 CVA600L32K3 128 HDL26040 26 HDL36100CU31X 28 HGA2605(5) 30 HGL26110 26 CVA600L32K4 128 HDL26040 26 HDL36100CU31X 28 HGA2605(5) 30 HGL26110 26 CVA600L32K4 128 HDL26040 26 HDL36100CU31X 34 HGA2603(6) 30 HGL26155 26 CVA600L32K4 128 HDL26045 26 HDL36100CU31X 34 HGA2603(6) 30 HGL26155 26 CVA600L32K4 128 HDL26045 26 HDL36100TU31X 34 HGA2605(6) 30 HGL26155 26 CVA600L32K4 128 HDL26045 26 HDL36100TU31X 34 HGA2603(6) 30 HGL26155 26 CVA600L32K4 128 HDL26045 26 HDL36100TU31X 34 HGA2603(6) 30 HGL26155 26 CVA600L32K4 128 HDL26045 26 HDL36100TU31X 34 HGA2603(6) 30 HGL36155 26 CVA600L32K4 128 HDL26045 26 HDL36100TU31X 34 HGA2603(6) 30 HGL36155 26 CVA600L32K4 128 HDL26045 26 HDL36100TU31X 34 HGA2603(6) 30 HGL360155 33 HGA26035(6) 30 HGL36005 26 HDL36100TU31X 34 HGA2603(6) 30 HGL36055 36 HDL36005 26 HDL36100TU31X 34 HGA2603(6) 30 HGL360355 30 HGL360355 33 HGA2603(6) 30 HDL26000 26 HDL36100TU31X 34 HGA2600(6) 30 HG							
CUGOLESZK3 124 HDF36000F06 35 HDL36070C 26 HE3150U33X 35 HGL26060 26 CU600LSSZK3 124 HDF36000F15 35 HDL36070T 33 HE3150U33X 68 HGL26060C 26 CU600LSSZK4 124 HDL26015 26 HDL36080 26 HE3150U43X 35 HGL26070 26 CYA060HD 128 HDL26015C 26 HDL36080C 26 HE3150U43X 35 HGL26070C 26 CYA150HD 128 HDL2602C 26 HDL36080C 33 HE3150U43X 35 HGL26080C 26 CYA150HD 128 HDL2602C 26 HDL36080C 26 HE3150U44X 35 HGL26080C 26 CYA150HD 128 HDL2602C 26 HDL36080C 26 HE3150U44X 35 HGL26080C 26 CYA250J3 128 HDL2602C 26 HDL36080C 26 HE3150U44X 69 HGL26080C 26 CYA400L31K3 128 HDL2602S 26 HDL36080C 26 HE3150U53X 35 HGL26080 26 CYA400L31K3 128 HDL2602S 26 HDL36080T 33 HE3150U53X 69 HGL26090C 26 CYA400L31K4 128 HDL2603C 26 HDL36090T 33 HE3150U53X 69 HGL26090C 26 CYA400L51K3 128 HDL2603C 26 HDL36100C 26 HE3150U54X 35 HGL2600C 26 CYA400L51K3 128 HDL2603C 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L51K3 128 HDL2603S 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L51K4 128 HDL2603S 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L71K3 128 HDL2603S 26 HDL36100C 31X 28 HGA26015() 30 HGL26110C 26 CYA600L32K4 128 HDL2603S 26 HDL36100CU33X 28 HGA2603() 30 HGL26110C 26 CYA600L32K3 128 HDL26040C 26 HDL36100CU33X 28 HGA2603() 30 HGL26110C 26 CYA600L32K4 128 HDL26040C 26 HDL36100CU33X 28 HGA2603() 30 HGL2615C 26 CYA600L32K4 128 HDL2604C 26 HDL36100TU31X 34 HGA26030() 30 HGL2615C 26 CYA600L32K4 128 HDL2604C 26 HDL36100TU31X 34 HGA26030() 30 HGL2615C 26 CYA600L32K4 128 HDL2604C 26 HDL36100TU31X 34 HGA26030() 30 HGL2615C 26 CYA600L32K4 128 HDL2604C 26 HDL36100TU31X 34 HGA26030() 30 HGL2615C 26 CYA600L32K4 128 HDL2606C 26 HDL36100TU31X 34 HGA26030() 30 HGL3615C 26 CYA600L32K4 128 HDL2604C 26 HDL36100TU31X 34 HGA26030() 30 HGL36015T 33 HGA2603() 30 HGL3600C 26 HDL36100TU31X 34 HGA26030() 30 HGL36015C 26 HDL3600C 26 HDL36100TU31X 34 HGA26030() 30 HGL36015C 26 HDL3600C 36 HDL3600C 30 HDL3600C 3							
CUEDOLSSZK3 124 HDF3600F15 35 HDL36070T 33 HE3150U33X 68 HGL26606C 26 CV4060HD 128 HDL26015C 26 HDL36080 26 HE3150U43X 35 HGL26070 26 CVA150HD 128 HDL26020 26 HDL36080C 26 HE3150U43X 35 HGL26070C 26 CVA150HD 128 HDL26020 26 HDL36080T 33 HE3150U44X 35 HGL26080 26 CVA150HD 128 HDL26020 26 HDL36080T 33 HE3150U44X 35 HGL26080 26 CVA250J3 128 HDL26025 26 HDL36090 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26025C 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26025C 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26035 26 HDJ36090T 33 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26030 26 HDJ36100C 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26030 26 HDJ36100C 26 HE3150U54X 35 HGL26100 26 CVA400J31K3 128 HDL26030 26 HDJ36100C 26 HE3150U54X 35 HGL26100 26 CVA400J31K3 128 HDL26035C 26 HDJ36100C 26 HE3150U54X 35 HGL26110 26 CVA400J31K4 128 HDL26035C 26 HDJ36100CU33X 28 HGA26020() 30 HGL26110C 26 CVA400J31K4 128 HDL26035C 26 HDJ36100CU33X 28 HGA26020() 30 HGL26110C 26 CVA600J32K3 128 HDL26040C 26 HDJ36100CU33X 28 HGA26020() 30 HGL2615C 26 CVA600J32K4 128 HDL26040C 26 HDJ36100CU33X 28 HGA26020() 30 HGL2615C 26 CVA600J32K4 128 HDL26045C 26 HDJ36100CU33X 28 HGA26030() 30 HGL2615C 26 CVA600J32K4 128 HDL26045C 26 HDJ36100TJ33X 34 HGA26036() 30 HGL2615C 26 ELM150HD 105 HDL26050C 26 HDJ36100TJ33X 34 HGA26036() 30 HGL2615C 26 ELM250JD 105 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26060() 30 HGL36005T 33 HDA26050() 30 HDL26070C 26 HDJ36100J33X 28 HGA26000() 30 HGL36005T 33 HDA26050() 30 HDL26090C 26 HDJ36100J33X 28 HGA2600() 30 HGL36005T 33 HDA26040() 30 HDL26090C 26 HDJ36100J33X 28 HGA2600()			HDA36150U54X32	HDL36070	26		HGL26050C26
CUEDOLSSZK3 124 HDF3600F15 35 HDL36070T 33 HE3150U33X 68 HGL26606C 26 CV4060HD 128 HDL26015C 26 HDL36080 26 HE3150U43X 35 HGL26070 26 CVA150HD 128 HDL26020 26 HDL36080C 26 HE3150U43X 35 HGL26070C 26 CVA150HD 128 HDL26020 26 HDL36080T 33 HE3150U44X 35 HGL26080 26 CVA150HD 128 HDL26020 26 HDL36080T 33 HE3150U44X 35 HGL26080 26 CVA250J3 128 HDL26025 26 HDL36090 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26025C 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26025C 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26035 26 HDJ36090T 33 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26030 26 HDJ36100C 26 HE3150U53X 35 HGL26090 26 CVA400J31K3 128 HDL26030 26 HDJ36100C 26 HE3150U54X 35 HGL26100 26 CVA400J31K3 128 HDL26030 26 HDJ36100C 26 HE3150U54X 35 HGL26100 26 CVA400J31K3 128 HDL26035C 26 HDJ36100C 26 HE3150U54X 35 HGL26110 26 CVA400J31K4 128 HDL26035C 26 HDJ36100CU33X 28 HGA26020() 30 HGL26110C 26 CVA400J31K4 128 HDL26035C 26 HDJ36100CU33X 28 HGA26020() 30 HGL26110C 26 CVA600J32K3 128 HDL26040C 26 HDJ36100CU33X 28 HGA26020() 30 HGL2615C 26 CVA600J32K4 128 HDL26040C 26 HDJ36100CU33X 28 HGA26020() 30 HGL2615C 26 CVA600J32K4 128 HDL26045C 26 HDJ36100CU33X 28 HGA26030() 30 HGL2615C 26 CVA600J32K4 128 HDL26045C 26 HDJ36100TJ33X 34 HGA26036() 30 HGL2615C 26 ELM150HD 105 HDL26050C 26 HDJ36100TJ33X 34 HGA26036() 30 HGL2615C 26 ELM250JD 105 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26040() 30 HGL36015C 26 ELM250JD 104 HDL26050C 26 HDJ36100TJ33X 34 HGA26060() 30 HGL36005T 33 HDA26050() 30 HDL26070C 26 HDJ36100J33X 28 HGA26000() 30 HGL36005T 33 HDA26050() 30 HDL26090C 26 HDJ36100J33X 28 HGA2600() 30 HGL36005T 33 HDA26040() 30 HDL26090C 26 HDJ36100J33X 28 HGA2600()	CU600LF52K3	.124	HDF36000F0635	HDL36070C	26	HE3150U33X35	HGL2606026
CUGOOLSSZK4 124 HDL26015 26 HDL36080 26 HE3150U43X 35 HGL26070 26 CYA600HD 128 HDL26015C 26 HDL36080C 26 HE3150U43X 35 HGL26070 26 CYA150HD 128 HDL26020 26 HDL36080T 33 HE3150U44X 35 HGL26080 26 CYA150HD 128 HDL26020C 26 HDL36090 26 HE3150U44X 69 HGL26080C 26 CYA250J3 128 HDL26025 26 HDL36090C 26 HE3150U44X 69 HGL26080C 26 CYA400L31K3 128 HDL26025C 26 HDL36090T 33 HE3150U53X 35 HGL26090C 26 CYA400L31K3 128 HDL26030 26 HDL36090T 33 HE3150U53X 69 HGL26090C 26 CYA400L31K3 128 HDL26030 26 HDL36100 26 HE3150U53X 35 HGL2600C 26 CYA400L51K3 128 HDL26030 26 HDL36100 26 HE3150U53X 35 HGL2600C 26 CYA400L51K3 128 HDL26030 26 HDL36100 26 HE3150U53X 69 HGL26100C 26 CYA400L51K3 128 HDL26030C 26 HDL36100C 26 HE3150U54X 35 HGL26100 26 CYA400L51K3 128 HDL26030C 26 HDL36100C 38 HGL2610C 36 CYA400L51K3 128 HDL26035C 26 HDL36100CU31X 28 HGA26015() 30 HGL26110C 26 CYA400L31X3 128 HDL26035C 26 HDL36100CU33X 28 HGA26025() 30 HGL26110C 26 CYA600L32K3 128 HDL26040 26 HDL36100CU33X 28 HGA26025() 30 HGL26125 26 CYA600L32K3 128 HDL26040 26 HDL36100CU33X 28 HGA26035() 30 HGL26125 26 CYA600L52K3 128 HDL26040C 26 HDL36100CU53X 28 HGA26035() 30 HGL26125 26 CYA600L52K4 128 HDL26045C 26 HDL36100TU31X 34 HGA26035() 30 HGL26150 26 CYA600L52K4 128 HDL26045C 26 HDL36100TU33X 34 HGA26035() 30 HGL26150C 26 ELM550HD 105 HDL26050C 26 HDL36100TU33X 34 HGA2604() 30 HGL36015C 26 ELM550HD 105 HDL26050C 26 HDL36100TU33X 34 HGA26005() 30 HGL36015C 26 HDL36100TU43X 34 HGA2604() 30 HGL36015C 26 HDL36100U33X 28 HGA2600() 30 HGL36015C 26 HDL36100U33X 28 HGA2600() 30 HGL36005C 26 HDL36100U33X 28 HGA2600() 30 HGL36005C 26 HDL36100U33X 28 HGA2600() 30 HGL36005C 26 HDL36100U33X 28 HGA26			HDE36000E15 35				
CYA60HD 128 HDL26015C 26 HDL36080C 26 HE3150U43X 89 HGL26070C 26 CYA150JD 128 HDL26020 26 HDL36080T 33 HE3150U44X 35 HGL26080 26 CYA250J3 128 HDL26025 26 HDL36090C 26 HE3150U44X 89 HGL26080C 26 CYA250J3 128 HDL26025 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CYA400J31K3 128 HDL26025 26 HDL36090T 33 HE3150U53X 35 HGL26090 26 CYA400J31K4 128 HDL26025 26 HDL36090T 33 HE3150U53X 35 HGL26090 26 CYA400J31K4 128 HDL26030 26 HDL36100 26 HE3150U54X 35 HGL26100 26 CYA400J31K3 128 HDL26030 26 HDJ36100 26 HE3150U54X 35 HGL261100 26 CYA400J31K3 128 HDL26030 26 HDJ36100C 26 HE3150U54X 35 HGL261100 26 CYA400J31K3 128 HDL26035 26 HDJ36100C 26 HE3150U54X 35 HGL261100 26 CYA400J31K3 128 HDJ26035 26 HDJ36100CU31X 28 HGA26015() 30 HGL26110 26 CYA400J31K3 128 HDJ26035 26 HDJ36100CU31X 28 HGA26020() 30 HGL26110 26 CYA600J32K3 128 HDJ26040 26 HDJ36100CU33X 28 HGA26020() 30 HGJ26110 26 CYA600J32K3 128 HDJ26040 26 HDJ36100CU33X 28 HGA26025() 30 HGJ26150 26 CYA600J32K4 128 HDJ26040 26 HDJ36100CU33X 28 HGA26030() 30 HGJ26150 26 CYA600J32K4 128 HDJ26045 26 HDJ36100CU33X 31 HGA26030() 30 HGJ26150 26 CYA600J52K4 128 HDJ26045 26 HDJ36100TJ31X 34 HGA26030() 30 HGJ26150 26 CYA600J52K4 128 HDJ26045 26 HDJ36100TJ31X 34 HGA26040() 30 HGJ26150 26 ELM150HD 105 HDJ26050 26 HDJ36100TJ31X 34 HGA26040() 30 HGJ26150 26 ELM250JD 105 HDJ26050 26 HDJ36100TJ31X 34 HGA26040() 30 HGJ36015 26 ELM250JD 104 HDJ26050 26 HDJ36100TJ33X 34 HGA26040() 30 HGJ36015 26 ELM250JD 104 HDJ26050 26 HDJ36100TJ33X 34 HGA26040() 30 HGJ36015 26 ELM250JD 104 HDJ26050 26 HDJ36100TJ33X 34 HGA26040() 30 HGJ36015 26 ELM250JD 104 HDJ26050 26 HDJ36100TJ33X 34 HGA26040() 30 HGJ36015 26 ELM250JD 104 HDJ26050 26 HDJ36100TJ33X 34 HGA26050() 30 HGJ36015 26 HDJ36100J33X 28 HGA26050() 30 HGJ36020 26 HDJ36100J33X 28 HGA26050() 30 HGJ36020 26 HDJ36100J33X 28 HGA26040() 30 HGJ36025 26 HDJ36100J33X 28 HGA26050() 30 HGJ36035 26 HDJ36							
CYA150HD 128 HDL26020 26 HDL36080T 33 HE3150U44X 55 HGL26080 26 CYA150JD 128 HDL2602C 26 HDL36090 26 HE3150U44X 69 HGL26080C 26 CYA250J3 128 HDL26025 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CYA400L31K3 128 HDL26025 26 HDL36090T 33 HE3150U53X 69 HGL26090C 26 CYA400L31K3 128 HDL26030 26 HDL36100 26 HDL36100 26 CYA400L31K3 128 HDL26030C 26 HDL36100 26 HDL36100 26 CYA400L51K3 128 HDL26030C 26 HDL36100C 26 HE3150U54X 69 HGL26090C 26 CYA400L51K3 128 HDL26030C 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L51K3 128 HDL26035C 26 HDL36100CU33X 28 HGA26015() 30 HGL26110C 26 CYA400L51K3 128 HDL26035C 26 HDL36100CU33X 28 HGA26015() 30 HGL26110C 26 CYA400L31K3 128 HDL26040 26 HDL36100CU33X 28 HGA26020() 30 HGL26125 26 CYA600L32K3 128 HDL26040 26 HDL36100CU43X 28 HGA26030() 30 HGL26125 26 CYA600L32K3 128 HDL26040 26 HDL36100CU33X 28 HGA26030() 30 HGL26125 26 CYA600L32K3 128 HDL26045 26 HDL36100CU33X 28 HGA26030() 30 HGL26125 26 CYA600L52K3 128 HDL26045 26 HDL36100TJ3X 34 HGA26035() 30 HGL26150 26 CYA600L52K3 128 HDL26045 26 HDL36100TJ3X 34 HGA26040() 30 HGL26150 26 ELM150HD 105 HDL26050 26 HDL36100TJ3X 34 HGA26040() 30 HGL26150 26 ELM250JD 105 HDL26050 26 HDL36100TU3X 34 HGA26040() 30 HGL36015T 33 GFM250JD 104 HDL26060 26 HDL36100TU43X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060 26 HDL36100TU43X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060 26 HDL36100TU43X 34 HGA26090() 30 HGL36015T 33 GFM250JD 104 HDL26060 26 HDL36100TU43X 34 HGA26090() 30 HGL36015C 26 HDA26020() 30 HDL26070 26 HDL36100TU43X 34 HGA26090() 30 HGL36015C 36 HDA26030() 30 HDL26070 26 HDL36100TU43X 34 HGA26090() 30 HGL36015C 36 HDA26030() 30 HDL26090 26 HDL36100TU43X 34 HGA26090() 30 HGL36015C 36 HDA26030() 30 HDL26090 26 HDL36100TU43X 34 HGA26090() 30 HGL3602C 26 HDA36000() 30 HDL26090 26 HDL36100TU44X 28 HGA26000() 30 HGL3602C 26 HDA36000() 30 HDL26090 26 HDL36100U44X 28 HGA26000() 30 HGL36025 26 HDA36000() 30 HDL26090 26 HDL36100U44X 28 HGA26100() 30 HGL36025 36 HDA26090() 30 HDL26090 26 HDL36100U44X 28 HGA26000() 30 HGL36035C 36 HDA26090(							
CYA50JJ 128 HDL2602C 26 HDL3609C 26 HE3150U4X 69 HGL26080C 26 CYA250J3 128 HDL26025 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CYA400L31K3 128 HDL26025C 26 HDL36090T 33 HE3150U53X 69 HGL26090C 26 CYA400L31K4 128 HDL2603C 26 HDL36100C 26 HE3150U54X 35 HGL26090 26 CYA400L51K3 128 HDL2603C 26 HDL36100C 26 HE3150U54X 69 HGL2610C 26 CYA400L51K3 128 HDL26035 26 HDL36100C 26 HE3150U54X 69 HGL2610C 26 CYA400L51K3 128 HDL26035 26 HDL36100C 21 CYA400L51K4 128 HDL26035 26 HDL36100C 21 CYA400L51K4 128 HDL26035 26 HDL36100CU31X 28 HGA26015() 30 HGL26110 26 CYA400L71K3 128 HDL2604C 26 HDL36100CU33X 28 HGA2602() 30 HGL26110 26 CYA600L32K4 128 HDL2604C 26 HDL36100CU33X 28 HGA2602() 30 HGL2615C 26 CYA600L32K4 128 HDL2604C 26 HDL36100CU33X 28 HGA2603() 30 HGL26125 26 CYA600L32K4 128 HDL2604C 26 HDL36100CU33X 28 HGA2603() 30 HGL2615C 26 CYA600L52K4 128 HDL2604C 26 HDL36100CU33X 34 HGA2603() 30 HGL2615C 26 CYA600L52K4 128 HDL2604C 26 HDL36100TU31X 34 HGA2603() 30 HGL2615D 26 CYA600L52K4 128 HDL26045 26 HDL36100TU31X 34 HGA2603() 30 HGL2615D 26 CYA600L52K4 128 HDL26045 26 HDL36100TU31X 34 HGA2603() 30 HGL36015 26 ELM250JD 105 HDL2605C 26 HDL36100TU33X 34 HGA2604() 30 HGL36015 26 GFM150HD 105 HDL2605C 26 HDL36100TU33X 34 HGA2605() 30 HGL36015 26 GFM150HD 104 HDL2606C 26 HDL36100TU33X 34 HGA2605() 30 HGL36015 26 HDA2605() 30 HDL2607C 26 HDL36100TU33X 34 HGA2605() 30 HGL36015 36 HDA2605() 30 HDL2607C 26 HDL36100TU33X 34 HGA2605() 30 HGL3602C 26 HDA2605() 30 HDL2607C 26 HDL36100TU33X 34 HGA2605() 30 HGL3602C 26 HDA2605() 30 HDL2607C 26 HDL36100TU33X 34 HGA2605() 30 HGL3602C 26 HDA2605() 30 HDL2607C 26 HDL36100TU33X 34 HGA2605() 30 HGL3602C 26 HDA2605() 30 HDL2607C 26 HDL36100TU33X 34 HGA2605() 30 HGL3602C 26 HDA2605() 30 HDL2607C 26 HDL36100U33X 28 HGA2610() 30 HGL3602C 26 HDA2605() 30 HDL2607C 26 HDL36100U33X 28 HGA2615() 30 HGL3602C 26 HDA2605() 30 HDL2609C 26 HDL36100U33X 28 HGA2615() 30 HGL3602C 26 HDA2605() 30 HDL2609C 26 HDL36100U33X 28 HGA2615() 30 HGL3603C 26 HDA2605() 30 HDL2609C 26 HDL36100U33X 28 HGA2615() 30 HGL3603C 26 HDA2							
CYA400L31K3 128 HDL26025C 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CYA400L31K4 128 HDL26030 26 HDL36100 26 HE3150U54X 35 HGL26100 26 CYA400L51K4 128 HDL26030 26 HDL36100C 26 HE3150U54X 35 HGL26100 26 CYA400L51K4 128 HDL26035C 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L51K4 128 HDL26035C 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L71K3 128 HDL26035C 26 HDL36100CU31X 28 HGA26015() 30 HGL26110C 26 CYA400L71K3 128 HDL26035C 26 HDL36100CU31X 28 HGA26005() 30 HGL26110C 26 CYA600L32K3 128 HDL26040 26 HDL36100CU31X 28 HGA26002() 30 HGL26125 26 CYA600L32K4 128 HDL26040 26 HDL36100CU31X 28 HGA26002() 30 HGL26125 26 CYA600L32K4 128 HDL26045C 26 HDL36100TU31X 28 HGA26035() 30 HGL26125 26 CYA600L52K4 128 HDL26045C 26 HDL36100TU31X 34 HGA26035() 30 HGL26150 26 ELM50HD 105 HDL26050C 26 HDL36100TU31X 34 HGA26040() 30 HGL26150C 26 ELM50HD 105 HDL26050C 26 HDL36100TU31X 34 HGA26040() 30 HGL26150C 26 ELM50HD 105 HDL26050C 26 HDL36100TU31X 34 HGA26050() 30 HGL36015C 26 GFM150HD 104 HDL26060C 26 HDL36100TU43X 34 HGA26050() 30 HGL36015C 26 HDL36100TU31X 34 HGA26050() 30 HGL3602C 26 HDL36100TU31X 28 HGA26000() 30 HGL3602C 26 HDL36100TU31X 28 HGA26050() 30 HGL3602C 26 HDL36100TU31X 28 HGA26000() 30 HGL3602C 26 HDL36100TU31X 28 HGA26000() 30 HGL3602C 26 HDL36100U31X 28 HGA26000() 30 HGL3602C 26 HDL36100U31X 28 HGA26000() 30 HGL3602C 26 HDL36100U31X 28 HGA2605() 30 HGL3602C 26 HDL36100U31X 28 HGA2605() 30 HGL3602C 26 HDL36100U31X 28 HGA2605() 30 HGL3603C 26 HDL36100U31X 28	CYA150HD	. 128	HDL2602026	HDL36080T	33	HE3150U44X35	HGL2608026
CYA400L31K3 128 HDL26025C 26 HDL36090C 26 HE3150U53X 35 HGL26090 26 CYA400L31K4 128 HDL26030 26 HDL36100 26 HE3150U54X 35 HGL26100 26 CYA400L51K4 128 HDL26030 26 HDL36100C 26 HE3150U54X 35 HGL26100 26 CYA400L51K4 128 HDL26035C 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L51K4 128 HDL26035C 26 HDL36100C 26 HE3150U54X 69 HGL26100C 26 CYA400L71K3 128 HDL26035C 26 HDL36100CU33X 28 HGA26015() 30 HGL26110C 26 CYA600L32K3 128 HDL26035C 26 HDL36100CU33X 28 HGA260020() 30 HGL26110C 26 CYA600L32K3 128 HDL26040 26 HDL36100CU53X 28 HGA260020() 30 HGL26125 26 CYA600L32K4 128 HDL26045C 26 HDL36100CU53X 28 HGA26003() 30 HGL26125 26 CYA600L52K4 128 HDL26045C 26 HDL36100TU31X 34 HGA26035() 30 HGL26150C 26 ELM50HD 105 HDL26050C 26 HDL36100TU31X 34 HGA26040() 30 HGL26150C 26 ELM50HD 105 HDL26050C 26 HDL36100TU31X 34 HGA26045() 30 HGL36150C 26 ELM50HD 105 HDL26050C 26 HDL36100TU31X 34 HGA26050() 30 HGL3615C 26 ELM50JD 105 HDL26050C 26 HDL36100TU43X 34 HGA26050() 30 HGL36015C 26 HDL36100TU31X 34 HGA26050() 30 HGL36015C 26 HDL36100TU31X 34 HGA26050() 30 HGL36015C 26 ELM50JD 104 HDL26060C 26 HDL36100TU43X 34 HGA26050() 30 HGL36015C 26 HDL36100TU43X 34 HGA26050() 30 HGL3602C 26 HDL36100TU43X 34 HGA26050() 30 HGL3602C 26 HDL36100TU43X 34 HGA26050() 30 HGL3602C 26 HDL36100TU53X 34 HGA26050() 30 HGL3602C 26 HDL36100TU54X 38 HGA26100() 30 HGL3602C 26 HDL36100TU54X 28 HGA26100() 30 HGL3602C 26 HDL36100TU54X 28 HGA26150() 30 HGL3602C 26 HDL36100TU54X 28 HGA26150() 30 HGL3603C 26 HDL	CYA150JD	128	HDL26020C26	HDL36090	26	HE3150U44X69	HGL26080C26
CYA400L31K3 128 HDL26030 26 HDL36100 26 HE3150U54X 35 HGL26100 26 CYA400L51K3 128 HDL26030 26 HDL36100 26 HE3150U54X 35 HGL26100 26 CYA400L51K3 128 HDL26030 26 HDL36100C 26 HE3150U54X 89 HGL26110 26 CYA400L51K4 128 HDL26035 26 HDL36100CU31X 28 HGA26015() 30 HGL26110 26 CYA400L51K3 128 HDL26035 26 HDL36100CU31X 28 HGA26015() 30 HGL26110 26 CYA400L51K3 128 HDL26035 26 HDL36100CU33X 28 HGA26020() 30 HGL26110 26 CYA600L32K3 128 HDL26040 26 HDL36100CU33X 28 HGA26025() 30 HGL26155 26 CYA600L32K4 128 HDL26040 26 HDL36100CU33X 28 HGA26030() 30 HGL26155 26 CYA600L52K4 128 HDL26045 26 HDL36100TU33X 28 HGA26030() 30 HGL26150 26 CYA600L52K4 128 HDL26045 26 HDL36100TU31X 34 HGA26035() 30 HGL26150 26 CYA600L52K4 128 HDL26045 26 HDL36100TU31X 34 HGA26040() 30 HGL26150 26 CYA600L52K4 128 HDL26045 26 HDL36100TU31X 34 HGA26040() 30 HGL26150 26 CYA600L52K4 128 HDL26050 26 HDL36100TU31X 34 HGA26050() 30 HGL360155 26 HDL36100TU31X 34 HGA26060() 30 HGL360155 26 HDL36100TU31X 34 HGA26050() 30 HGL360155 26 HDL36100TU31X 34 HGA26050() 30 HGL360155 26 HDL36100TU31X 34 HGA26060() 30 HGL360155 33 HGL36020C 26 HDL36100TU31X 34 HGA26060() 30 HGL360155 36 HDA26035() 30 HDL26070 26 HDL36100TU31X 28 HGA26090() 30 HGL36025 26 HDL36100TU31X 28 HGA26090() 30 HGL36020T 33 HDA26025() 30 HDL26070 26 HDL36100TU31X 28 HGA26090() 30 HGL36025 26 HDL36100U31X 28 HGA26100() 30 HGL36025 26 HDA26035() 30 HDL26080 26 HDL36100U31X 28 HGA26100() 30 HGL36025 26 HDA26035() 30 HDL26080 26 HDL36100U31X 28 HGA26100() 30 HGL36025 26 HDA26035() 30 HDL26080 26 HDL36100U31X 28 HGA26150() 30 HGL36025 26 HDA26035() 30 HDL26080 26 HDL36100U31X 28 HGA26150() 30 HGL36035 26 HDA26035() 30 HDL26090 26 HDL36100U31X 28 HGA26150() 30 HGL36035 26 HDA26035() 30 HDL26100 26 HDL36100U31X 28 HGA26050 30 HGL36035 26 HDA26000(							
CYA400L51K4 128 HDL26030 26 HDL36100 26 HE3150U54X 35 HGL26100 26 CYA400L51K3 128 HDL26030C 26 HDL36100CU31X 28 HGA26015() 30 HGL26110 26 CYA400L51K4 128 HDL26035 26 HDL36100CU31X 28 HGA26015() 30 HGL26110 26 CYA400L51K3 128 HDL26035C 26 HDL36100CU33X 28 HGA26020() 30 HGL26110C 26 CYA600L32K3 128 HDL26040 26 HDL36100CU33X 28 HGA26020() 30 HGL26125 26 CYA600L32K4 128 HDL26040 26 HDL36100CU33X 28 HGA26030() 30 HGL26125 26 CYA600L52K4 128 HDL26045 26 HDL36100CU33X 28 HGA26030() 30 HGL26125 26 CYA600L52K4 128 HDL26045 26 HDL36100TU33X 31 HGA26035() 30 HGL26150 26 CYA600L52K4 128 HDL26045 26 HDL36100TU33X 34 HGA26030() 30 HGL26150 26 ELM150HD 105 HDL26050 26 HDL36100TU33X 34 HGA26040() 30 HGL26150 26 ELM250JD 105 HDL26050 26 HDL36100TU33X 34 HGA26045() 30 HGL36015C 26 ELM250JD 105 HDL26050 26 HDL36100TU33X 34 HGA26050() 30 HGL36015C 26 HDL36100TU33X 34 HGA26050() 30 HGL36015C 26 HDL36100TU43X 34 HGA26050() 30 HGL36015C 26 HDL36100TU53X 34 HGA26050() 30 HGL36015C 26 HDA26015() 30 HDL26070 26 HDL36100TU53X 34 HGA26090() 30 HGL36020 26 HDA26015() 30 HDL26070 26 HDL36100TU53X 34 HGA26090() 30 HGL36020C 26 HDA26030() 30 HDL26070 26 HDL36100U33X 28 HGA26090() 30 HGL36020C 26 HDA26030() 30 HDL26090 26 HDL36100U33X 28 HGA26100() 30 HGL36025C 26 HDA26030() 30 HDL26090 26 HDL36100U33X 28 HGA26100() 30 HGL36025C 26 HDA26030() 30 HDL26090 26 HDL36100U33X 28 HGA26150() 30 HGL36035C 26 HDA26030() 30 HDL26090 26 HDL36100U33X 28 HGA26150() 30 HGL36035C 26 HDA26040() 30 HDL26090 26 HDL36100U33X 28 HGA26150() 30 HGL36035C 26 HDA26040() 30 HDL26090 26 HDL36100U33X 28 HGA26150() 30 HGL36035C 26 HDA26040() 30 HDL26100 26 HDL36110 26 HDA36100U33X 28 HGA26150() 30 HGL36035T 33 HDA26040() 30 HDL26110 26 HDL36110C 26 HDL36100U33X 31 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL2615C 2							
CYA400L51K3         128         HDL26030C         26         HDL36100C         26         HE3150U54X         69         HGL26100C         26           CYA400L51K4         128         HDL26035C         26         HDL36100CU31X         28         HGA26015()         30         HGL26110         26           CYA600L3ZK3         128         HDL26040         26         HDL36100CU43X         28         HGA26025()         30         HGL26125         26           CYA600L3ZK4         128         HDL26040C         26         HDL36100CU53X         28         HGA26035()         30         HGL26125         26           CYA600L3ZK4         128         HDL26045         26         HDL36100TU31X         28         HGA26035()         30         HGL26125C         26           CYA600L5ZK4         128         HDL26045C         26         HDL36100TU31X         34         HGA26035()         30         HGL26150C         26           ELM150HD         105         HDL26050         26         HDL36100TU33X         34         HGA26035()         30         HGL36015C         26           GFM150HD         105         HDL26050         26         HDL36100TU43X         34         HGA26050()         30         HGL36015C<							
CYA400L51K4 128 HDL26035 26 HDL36100CU31X 28 HGA26015() 30 HGL26110 26 CYA400L71K3 128 HDL26035C 26 HDL36100CU33X 28 HGA26020() 30 HGL26110C 26 CYA600L32K3 128 HDL26040 26 HDL36100CU43X 28 HGA26025() 30 HGL26110C 26 CYA600L32K3 128 HDL26040C 26 HDL36100CU43X 28 HGA26030() 30 HGL26125C 26 CYA600L32K4 128 HDL26040C 26 HDL36100CU53X 28 HGA26030() 30 HGL26150C 26 CYA600L52K3 128 HDL26045 26 HDL36100T 33 HGA26035() 30 HGL26150 26 CYA600L52K4 128 HDL26045 26 HDL36100TU31X 34 HGA26035() 30 HGL26150C 26 ELM150HD 105 HDL26050 26 HDL36100TU31X 34 HGA26040() 30 HGL36150C 26 ELM250JD 105 HDL26050 26 HDL36100TU31X 34 HGA26045() 30 HGL36015 26 ELM250JD 105 HDL26050 26 HDL36100TU43X 34 HGA26050() 30 HGL36015 26 ELM250JD 104 HDL26060 26 HDL36100TU44X 34 HGA26050() 30 HGL36015C 26 GFM150HD 104 HDL26060 26 HDL36100TU44X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060C 26 HDL36100TU44X 34 HGA26070() 30 HGL36020 26 HDA26020() 30 HDL26070C 26 HDL36100TU53X 34 HGA26070() 30 HGL36020 26 HDA26020() 30 HDL26070C 26 HDL36100TU53X 34 HGA26090() 30 HGL36020C 26 HDA26020() 30 HDL26070C 26 HDL36100TU53X 34 HGA26090() 30 HGL36020C 26 HDA26025() 30 HDL26070C 26 HDL36100TU53X 34 HGA26090() 30 HGL36020C 26 HDA26025() 30 HDL26070C 26 HDL36100TU53X 34 HGA26090() 30 HGL36020C 26 HDA26025() 30 HDL26070C 26 HDL36100U31X 28 HGA26090() 30 HGL36020C 26 HDA26035() 30 HDL26090 26 HDL36100U31X 28 HGA26100() 30 HGL36025C 26 HDA26035() 30 HDL26090 26 HDL36100U31X 28 HGA26110() 30 HGL36025C 26 HDA26035() 30 HDL26090 26 HDL36100U53X 28 HGA26110() 30 HGL36025C 26 HDA26035() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36035C 26 HDA26035() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36035C 26 HDA26035() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36035C 26 HDA26035() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36035C 26 HDA26035() 30 HDL26100 26 HDA36100U53X 28 HGA26150() 30 HGL36035C 26 HDA26035() 30 HDL26110 26 HDA36100U53X 28 HGA26150() 30 HGL36035C 36 HDA26030() 30 HDL26110 26 HDA36100U53X 28 HGA36035 30 HGL36035C 26 HDA26030() 30 HDL2615							
CYA600L32K3				HDL36100C	26	HE3150U54X69	HGL26100C26
CYA600L32K3	CYA400L51K4	128	HDL2603526	HDL36100CU31X	28	HGA26015()30	HGL2611026
CYA600L32K3 128 HDL26040 26 HDL36100CU43X 28 HGA26025() 30 HGL26125 26 CYA600L32K4 128 HDL26040C 26 HDL36100CU43X 28 HGA26030() 30 HGL26125C 26 CYA600L52K3 128 HDL26045C 26 HDL36100T 33 HGA26035() 30 HGL26150 26 CYA600L52K4 128 HDL26045C 26 HDL36100TU31X 34 HGA26040() 30 HGL26150C 26 ELM150HD 105 HDL26050 26 HDL36100TU31X 34 HGA26045() 30 HGL36015 26 ELM250JD 105 HDL26050 26 HDL36100TU43X 34 HGA26045() 30 HGL36015C 26 ELM250JD 105 HDL26050 26 HDL36100TU43X 34 HGA26050() 30 HGL36015C 26 ELM250JD 104 HDL26060 26 HDL36100TU43X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060 26 HDL36100TU44X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060 26 HDL36100TU44X 34 HGA26060() 30 HGL36015T 33 HDA26015() 30 HDL26070 26 HDL36100TU53X 34 HGA26080() 30 HGL36020 26 HDA26015() 30 HDL26070 26 HDL36100TU54X 34 HGA26080() 30 HGL36020C 26 HDA26015() 30 HDL26070 26 HDL36100TU54X 34 HGA26080() 30 HGL36020C 26 HDA26020() 30 HDL26070 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26025() 30 HDL26080 26 HDL36100U31X 28 HGA26100() 30 HGL36020T 33 HDA26025() 30 HDL26080 26 HDL36100U33X 28 HGA26100() 30 HGL36025C 26 HDA26030() 30 HDL26080 26 HDL36100U33X 28 HGA26100() 30 HGL36025T 33 HDA26040() 30 HDL26090 26 HDL36100U43X 28 HGA26150() 30 HGL36025T 33 HDA26040() 30 HDL26090 26 HDL36100U33X 28 HGA26150() 30 HGL36025T 33 HDA26040() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26050() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26050() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26050() 30 HDL26100 26 HDL36100U53X 28 HGA26150() 30 HGL36035C 26 HDA26050() 30 HDL26100 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26050() 30 HDL26100 26 HDL36110C 26 HGA36020 30 HGL36035C 26 HDA26050() 30 HDL26110C 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26090() 30 HDL26110C 26 HDL36110T 33 HGA36035 30 HGL36035C 26 HDA26090() 30 HDL26150 26 HDL36125C 26 HGA36045 30 HGL36040C 26 HDA26090() 30 HDL26150 26 HDL36150 26 HDA36150 30 HGL36040C 26 HDA26100() 30 HDL26150 26 HDL36150 26 HDA36150 30 HGL36040T 33 HDA2							
CYA600L32K4 128 HDL26040C 26 HDL36100CU53X 28 HGA26030() 30 HGL26125C 26 CYA600L52K3 128 HDL26045 26 HDL36100T 33 HGA26035() 30 HGL26150 26 CYA600L52K4 128 HDL26045C 26 HDL36100TU31X 34 HGA26040() 30 HGL26150C 26 ELM150HD 105 HDL26050 26 HDL36100TU33X 34 HGA26045() 30 HGL36015 26 ELM250JD 105 HDL26050C 26 HDL36100TU43X 34 HGA26045() 30 HGL36015 26 GFM150HD 104 HDL26060C 26 HDL36100TU43X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060C 26 HDL36100TU44X 34 HGA26060() 30 HGL36015T 33 HDA26015() 30 HDL26070C 26 HDL36100TU43X 34 HGA26070() 30 HGL36015T 33 HDA26020() 30 HDL26070C 26 HDL36100TU53X 34 HGA26080() 30 HGL36020C 26 HDA26015() 30 HDL26070C 26 HDL36100TU54X 34 HGA26080() 30 HGL36020T 33 HDA26025() 30 HDL26070C 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26025() 30 HDL26080 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26035() 30 HDL26080C 26 HDL36100U31X 28 HGA26100() 30 HGL36025C 26 HDA26035() 30 HDL26080C 26 HDL36100U31X 28 HGA26110() 30 HGL36025C 26 HDA26035() 30 HDL26090C 26 HDL36100U31X 28 HGA26110() 30 HGL36025T 33 HDA26045() 30 HDL26090 26 HDL36100U44X 28 HGA2615() 30 HGL36025T 33 HDA26045() 30 HDL26090 26 HDL36100U44X 28 HGA26150() 30 HGL36030C 26 HDA26045() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36030T 33 HDA26045() 30 HDL26100 26 HDL36100U54X 28 HGA26150() 30 HGL36030T 33 HDA26045() 30 HDL26100 26 HDL36100U54X 28 HGA36015 30 HGL36030T 33 HDA26045() 30 HDL26100 26 HDL361100 26 HDL36100U53X 30 HGL36030T 33 HDA26040() 30 HDL26100 26 HDL361100 26 HDL36100U54X 30 HGL36030T 33 HDA26050() 30 HDL261100 26 HDL361100 26 HGA36025 30 HGL36035C 26 HDA26080() 30 HDL261100 26 HDL36110T 33 HGA36030 30 HGL36035T 33 HDA26090() 30 HDL261100 26 HDL36110T 33 HGA36030 30 HGL36035T 33 HDA26090() 30 HDL26110C 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26080() 30 HDL26110C 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26080() 30 HDL26110C 26 HDL36125T 33 HGA36040 30 HGL36035C 26 HDA26090() 30 HDL26150 26 HDL36150 26 HDA36150 30 HGL36040T 30 HDA26040() 30 HDA26150() 30 HDA26150 26 HDA36150 30 HGL36040T 3							
CYA600L52K3							
CYA600L52K4 128 HDL26045C 26 HDL36100TU31X 34 HGA26040() 30 HGL26150C 26 ELM150HD 105 HDL26050 26 HDL36100TU33X 34 HGA26045() 30 HGL36015 26 ELM250JD 105 HDL26050C 26 HDL36100TU43X 34 HGA26050() 30 HGL36015C 26 GFM150HD 104 HDL26060 26 HDL36100TU44X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060C 26 HDL36100TU53X 34 HGA26050() 30 HGL36015T 33 GFM250JD 104 HDL26060C 26 HDL36100TU53X 34 HGA26050() 30 HGL36020C 26 HDA26015() 30 HDL26070 26 HDL36100TU54X 34 HGA26080() 30 HGL36020C 26 HDA26015() 30 HDL26070C 26 HDL36100TU54X 34 HGA26080() 30 HGL36020C 26 HDA26020() 30 HDL26070C 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26025() 30 HDL26080C 26 HDL36100U31X 28 HGA26100() 30 HGL36025C 26 HDA26030() 30 HDL26080C 26 HDL36100U31X 28 HGA26100() 30 HGL36025C 26 HDA26035() 30 HDL26080C 26 HDL36100U44X 28 HGA26110() 30 HGL36025C 26 HDA26035() 30 HDL26090C 26 HDL36100U44X 28 HGA2615() 30 HGL36025T 33 HDA26040() 30 HDL26090C 26 HDL36100U44X 28 HGA26150() 30 HGL36025T 33 HDA26040() 30 HDL26090C 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26040() 30 HDL26090C 26 HDL36100U53X 28 HGA26150() 30 HGL36030C 26 HDA26040() 30 HDL26100C 26 HDL361100U53X 28 HGA26150() 30 HGL36030C 26 HDA26040() 30 HDL26100C 26 HDL361100U53X 28 HGA26150() 30 HGL36030C 26 HDA26040() 30 HDL26100C 26 HDL361100U54X 28 HGA36015 30 HGL36030C 26 HDA26040() 30 HDL26100C 26 HDL36110C 26 HGA36025 30 HGL36030C 26 HDA26040() 30 HDL26110C 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26040() 30 HDL26110C 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26090() 30 HDL26110C 26 HDL36110C 26 HGA36035 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36110T 33 HGA36035 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36040C 26 HDA26100() 30 HDL26150C 26 HDL36150 26 HDL36150 30 HGL36040C 26 HDA26100() 30 HDL26150C 26 HDL36150 26 HDL36150 30 HGL36040C 26 HDA26100() 30 HDL26150C 26 HDL36150 26 HDL36150 30 HGL36040C 26 HDA26100() 30 HDL26150C 26 HDL36150 26 HDL36150 30 HGL36040T 33							
ELM150HD 105 HDL26050 26 HDL36100TU33X 34 HGA26045() 30 HGL36015 26 ELM250JD 105 HDL26050C 26 HDL36100TU43X 34 HGA26050() 30 HGL36015C 26 GFM150HD 104 HDL26060C 26 HDL36100TU43X 34 HGA26060() 30 HGL36015T 33 GFM250JD 104 HDL26060C 26 HDL36100TU43X 34 HGA26060() 30 HGL3602D 26 HDA26015() 30 HDL26070 26 HDL36100TU53X 34 HGA26070() 30 HGL36020C 26 HDA26020() 30 HDL26070 26 HDL36100TU54X 34 HGA26080() 30 HGL36020C 26 HDA26020() 30 HDL26070C 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26025() 30 HDL26080 26 HDL36100U33X 28 HGA26100() 30 HGL36025C 26 HDA26030() 30 HDL26080C 26 HDL36100U33X 28 HGA26100() 30 HGL36025C 26 HDA26035() 30 HDL26080C 26 HDL36100U43X 28 HGA26110() 30 HGL36025C 26 HDA26035() 30 HDL26090 26 HDL36100U43X 28 HGA26110() 30 HGL36025T 33 HDA26040() 30 HDL26090C 26 HDL36100U44X 28 HGA26150() 30 HGL36025T 33 HDA26045() 30 HDL26100 26 HDL36100U53X 28 HGA26150() 30 HGL36030C 26 HDA26045() 30 HDL26100 26 HDL36100U54X 28 HGA26150() 30 HGL36030C 26 HDA26050() 30 HDL26100 26 HDL36100U54X 28 HGA36015 30 HGL36030C 26 HDA26050() 30 HDL26100 26 HDL36110C 26 HGA36020 30 HGL36030T 33 HDA26060() 30 HDL26110 26 HDL36110C 26 HGA36025 30 HGL36035T 33 HDA26060() 30 HDL26110 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26050() 30 HDL26110C 26 HDL36110T 33 HGA36035 30 HGL36035C 26 HDA26080() 30 HDL26125 26 HDL36125C 26 HGA36025 30 HGL36035C 26 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36025 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36035 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36045 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36045 30 HGL36040C 26 HDA26100() 30 HDL26150 26 HDL36125C 26 HGA36045 30 HGL36040C 26 HDA26100() 30 HDL26150 26 HDL36125T 33 HGA36045 30 HGL36040C 26 HDA26110() 30 HDL26150 26 HDL36150 26 HDL36150 30 HGL36040C 26 HDA36100() 30 HDL26150 26 HDL36150 26 HDA36150 30 HGL36040C 26 HDA36110() 30 HDL26150 26 HDA36150 46 HDA36150	CYA600L52K3	. 128	HDL2604526	HDL361001	33		HGL2615026
ELM250JD         105         HDL26050C         26         HDL36100TU43X         34         HGA26050()         30         HGL36015C         26           GFM150HD         104         HDL26060C         26         HDL36100TU44X         34         HGA26060()         30         HGL36015T         33           GFM250JD         104         HDL26060C         26         HDL36100TU53X         34         HGA26070()         30         HGL36020         26           HDA26015()         30         HDL26070C         26         HDL36100TU54X         34         HGA26080()         30         HGL36020C         26           HDA26025()         30         HDL26070C         26         HDL36100U31X         28         HGA26090()         30         HGL3602CC         26           HDA26025()         30         HDL26080         26         HDL36100U31X         28         HGA26100()         30         HGL36025         26           HDA26030()         30         HDL26080C         26         HDL36100U33X         28         HGA26110()         30         HGL36025C         26           HDA26035()         30         HDL26080C         26         HDL36100U43X         28         HGA2615()         30         HGL36025T	CYA600L52K4	.128	HDL26045C26	HDL36100TU31X	34	HGA26040()30	HGL26150C26
ELM250JD         105         HDL26050C         26         HDL36100TU43X         34         HGA26050()         30         HGL36015C         26           GFM150HD         104         HDL26060C         26         HDL36100TU44X         34         HGA26060()         30         HGL36015T         33           GFM250JD         104         HDL26060C         26         HDL36100TU53X         34         HGA26070()         30         HGL36020         26           HDA26015()         30         HDL26070C         26         HDL36100TU54X         34         HGA26080()         30         HGL36020C         26           HDA26025()         30         HDL26070C         26         HDL36100U31X         28         HGA26090()         30         HGL3602CC         26           HDA26025()         30         HDL26080         26         HDL36100U31X         28         HGA26100()         30         HGL36025         26           HDA26030()         30         HDL26080C         26         HDL36100U33X         28         HGA26110()         30         HGL36025C         26           HDA26035()         30         HDL26080C         26         HDL36100U43X         28         HGA2615()         30         HGL36025T						HGA26045( ) 30	
GFM150HD 104 HDL26060 26 HDL36100TU44X 34 HGA26060() 30 HGL36015T 33 GFM250JD 104 HDL26060C 26 HDL36100TU53X 34 HGA26070() 30 HGL36020C 26 HDA26015() 30 HDL26070 26 HDL36100TU54X 34 HGA26080() 30 HGL36020C 26 HDA26020() 30 HDL26070C 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26025() 30 HDL26080 26 HDL36100U31X 28 HGA26090() 30 HGL36025T 26 HDA26030() 30 HDL26080 26 HDL36100U33X 28 HGA26100() 30 HGL36025C 26 HDA26035() 30 HDL26080 26 HDL36100U43X 28 HGA26110() 30 HGL36025T 33 HDA26035() 30 HDL26090 26 HDL36100U44X 28 HGA26125() 30 HGL36025T 33 HDA26040() 30 HDL26090 26 HDL36100U44X 28 HGA26150() 30 HGL36030 26 HDA26045() 30 HDL26090C 26 HDL36100U54X 28 HGA26150() 30 HGL36030 26 HDA26045() 30 HDL26100C 26 HDL36100U54X 28 HGA36015 30 HGL36030C 26 HDA26050() 30 HDL26100C 26 HDL36110U54X 28 HGA36015 30 HGL36030C 26 HDA26050() 30 HDL26110C 26 HDL36110C 26 HGA36020 30 HGL36030C 26 HDA26050() 30 HDL26110C 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26070() 30 HDL26110C 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26070() 30 HDL26110C 26 HDL36110T 33 HGA36035 30 HGL36035C 26 HDA26090() 30 HDL26110C 26 HDL36110T 33 HGA36035 30 HGL36035C 26 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36045 30 HGL36040C 26 HDA26010() 30 HDL26150C 26 HDL36125T 33 HGA36045 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HDA36150 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36155C 26 HGA36045 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HDA36150 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HDA36150 30 HGL36040T 33							
GFM250JD         104         HDL26060C         26         HDL36100TU53X         34         HGA26070()         30         HGL36020         26           HDA26015()         30         HDL26070         26         HDL36100TU54X         34         HGA26080()         30         HGL36020C         26           HDA26025()         30         HDL26070C         26         HDL36100U31X         28         HGA26090()         30         HGL36025T         33           HDA26025()         30         HDL26080C         26         HDL36100U33X         28         HGA26100()         30         HGL36025C         26           HDA26035()         30         HDL26080C         26         HDL36100U43X         28         HGA26110()         30         HGL36025C         26           HDA26035()         30         HDL26090         26         HDL36100U44X         28         HGA26125()         30         HGL36025T         33           HDA26040()         30         HDL26090C         26         HDL36100U44X         28         HGA26150()         30         HGL36025T         33           HDA26040()         30         HDL26100C         26         HDL36100U53X         28         HGA26150()         30         HGL36030T							
HDA26015() 30 HDL26070 26 HDL36100TU54X 34 HGA26080() 30 HGL36020C 26 HDA26020() 30 HDL26070C 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26030() 30 HDL260800 26 HDL36100U33X 28 HGA26100() 30 HGL36025 26 HDA26030() 30 HDL26080C 26 HDL36100U43X 28 HGA26110() 30 HGL36025T 26 HDA26035() 30 HDL26090 26 HDL36100U43X 28 HGA2615() 30 HGL36025T 33 HDA26040() 30 HDL26090 26 HDL36100U44X 28 HGA2615() 30 HGL36025T 33 HDA26040() 30 HDL26090 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26045() 30 HDL26100 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26045() 30 HDL26100 26 HDL36100U54X 28 HGA26150() 30 HGL36030C 26 HDA26050() 30 HDL26100 26 HDL361100 26 HGA36020 30 HGL36030C 26 HDA26050() 30 HDL26110 26 HDL36110 26 HGA36025 30 HGL36035T 33 HDA26060() 30 HDL26110 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26070() 30 HDL26110C 26 HDL36110T 33 HGA36035 30 HGL36035T 26 HDA26090() 30 HDL26125 26 HDL36125 26 HGA36055 30 HGL36035T 33 HDA26090() 30 HDL26125 26 HDL36125 26 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL26150 26 HDL36125T 33 HGA36045 30 HGL36040T 26 HDA26110() 30 HDL26150 26 HDL36150 26 HGA36055 30 HGL36040T 33							
HDA26020()         30         HDL26070C         26         HDL36100U31X         28         HGA26090()         30         HGL36020T         33           HDA26025()         30         HDL26080         26         HDL36100U33X         28         HGA26100()         30         HGL36025E         26           HDA26030()         30         HDL26080C         26         HDL36100U43X         28         HGA26110()         30         HGL36025E         26           HDA26035()         30         HDL26090         26         HDL36100U44X         28         HGA26155()         30         HGL36025T         33           HDA26040()         30         HDL26090C         26         HDL36100U54X         28         HGA26150()         30         HGL36030         26           HDA26045()         30         HDL26100         26         HDL36100U54X         28         HGA36015         30         HGL36030C         26           HDA26050()         30         HDL26100C         26         HDL36110         26         HGA36020         30         HGL36030T         33           HDA26060()         30         HDL26110C         26         HDL36110C         26         HGA36025         30         HGL36030T         33	GFM250JD	. 104					
HDA26020() 30 HDL26070C 26 HDL36100U31X 28 HGA26090() 30 HGL36020T 33 HDA26025() 30 HDL26080 26 HDL36100U33X 28 HGA26100() 30 HGL36025C 26 HDA26030() 30 HDL26080C 26 HDL36100U43X 28 HGA26110() 30 HGL36025C 26 HDA26035() 30 HDL26090 26 HDL36100U43X 28 HGA2615() 30 HGL36025T 33 HDA26040() 30 HDL26090C 26 HDL36100U53X 28 HGA2615() 30 HGL36030C 26 HDA26045() 30 HDL26100C 26 HDL36100U53X 28 HGA2615() 30 HGL36030C 26 HDA26045() 30 HDL26100C 26 HDL36100U54X 28 HGA2615() 30 HGL36030C 26 HDA26050() 30 HDL26110C 26 HDL36110C 26 HGA36020 30 HGL36030T 33 HDA26060() 30 HDL26110C 26 HDL36110C 26 HGA36025 30 HGL36030T 33 HDA26060() 30 HDL26110C 26 HDL36110C 26 HGA36025 30 HGL36035C 26 HDA26070() 30 HDL26110C 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26090() 30 HDL26125 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26090() 30 HDL26125C 26 HDL36125 26 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36040C 26 HDA26100() 30 HDL26150C 26 HDL36125T 33 HGA36040 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HGA36055 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HGA36050 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HGA36050 30 HGL36040T 33			HDL2607026	HDL36100TU54X	34	HGA26080()30	
HDA26025() 30 HDL26080 26 HDL36100U33X 28 HGA26100() 30 HGL36025 26 HDA26030() 30 HDL26080C 26 HDL36100U43X 28 HGA26110() 30 HGL36025C 26 HDA26035() 30 HDL26090 26 HDL36100U44X 28 HGA26125() 30 HGL36025T 33 HDA26040() 30 HDL26090C 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26045() 30 HDL26100 26 HDL36100U54X 28 HGA26155() 30 HGL36030 26 HDA26045() 30 HDL26100 26 HDL36100U54X 28 HGA36015 30 HGL36030C 26 HDA26050() 30 HDL26100 26 HDL36110 26 HGA36020 30 HGL36030T 33 HDA26060() 30 HDL26110 26 HDL36110 26 HGA36020 30 HGL36030T 33 HDA26060() 30 HDL26110 26 HDL36110C 26 HGA36025 30 HGL36035 26 HDA26070() 30 HDL26110C 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26070() 30 HDL26125 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26090() 30 HDL26125 26 HDL36125 26 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36040C 26 HDA26100() 30 HDL26150 26 HDL36125T 33 HGA36045 30 HGL36040C 26 HDA26110() 30 HDL26150 26 HDL36150 26 HGA36050 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HDA36150 30 HGL36040T 33						HGA26090()30	
HDA26030()         30         HDL26080C         26         HDL36100U43X         28         HGA26110()         30         HGL36025C         26           HDA26035()         30         HDL26090         26         HDL36100U44X         28         HGA26125()         30         HGL36025T         33           HDA26040()         30         HDL26090C         26         HDL36100U53X         28         HGA26150()         30         HGL36030         26           HDA26045()         30         HDL26100         26         HDL36100U54X         28         HGA36015         30         HGL36030C         26           HDA26050()         30         HDL26100C         26         HDL36110         26         HGA36020         30         HGL36030C         36           HDA26060()         30         HDL26110         26         HDL36110C         26         HGA36025         30         HGL36035         26           HDA26070()         30         HDL26110C         26         HDL36110T         33         HGA36030         30         HGL36035C         26           HDA26080()         30         HDL26125         26         HDL36125         26         HGA36030         30         HGL36035C         26							
HDA26035() 30 HDL26090 26 HDL36100U44X 28 HGA26125() 30 HGL36025T 33 HDA26040() 30 HDL26090C 26 HDL36100U53X 28 HGA26150() 30 HGL36030 26 HDA26045() 30 HDL26100 26 HDL3610U53X 28 HGA26150() 30 HGL36030C 26 HDA26050() 30 HDL26100C 26 HDL36110 26 HGA36020 30 HGL36030T 33 HDA26060() 30 HDL26110 26 HDL36110C 26 HGA36020 30 HGL36030T 33 HDA26060() 30 HDL26110 26 HDL36110C 26 HGA36025 30 HGL36035T 26 HDA26070() 30 HDL26110C 26 HDL36110T 33 HGA36030 30 HGL36035C 26 HDA26070() 30 HDL26125 26 HDL36125 26 HGA36035 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36035T 33 HDA26090() 30 HDL26125C 26 HDL36125C 26 HGA36040 30 HGL36040C 26 HDA26100() 30 HDL26150 26 HDL36125T 33 HGA36045 30 HGL36040C 26 HDA26110() 30 HDL26150C 26 HDL36150 26 HDL36150 30 HGA36040T 33							
HDA26040()       30       HDL26090C       26       HDL36100U53X       28       HGA26150()       30       HGL36030       26         HDA26045()       30       HDL26100       26       HDL36100U54X       28       HGA36015       30       HGL36030C       26         HDA26050()       30       HDL26100C       26       HDL36110       26       HGA36020       30       HGL36030T       33         HDA26060()       30       HDL26110       26       HDL36110C       26       HGA36025       30       HGL36035       26         HDA26070()       30       HDL26110C       26       HDL36110T       33       HGA36030       30       HGL36035C       26         HDA26080()       30       HDL26125       26       HDL36125       26       HGA36035       30       HGL36035T       33         HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040C       26         HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050							
HDA26045()       30       HDL26100       26       HDL36100U54X       28       HGA36015       30       HGL36030C       26         HDA26050()       30       HDL26100C       26       HDL36110       26       HGA36020       30       HGL36030T       33         HDA26060()       30       HDL26110       26       HDL36110C       26       HGA36025       30       HGL360355       26         HDA26070()       30       HDL26110C       26       HDL36110T       33       HGA36030       30       HGL36035C       26         HDA26080()       30       HDL26125       26       HDL36125       26       HGA36035       30       HGL36035T       33         HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040       26         HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33	* * *						
HDA26045()       30       HDL26100       26       HDL36100U54X       28       HGA36015       30       HGL36030C       26         HDA26050()       30       HDL26100C       26       HDL36110       26       HGA36020       30       HGL36030T       33         HDA26060()       30       HDL26110       26       HDL36110C       26       HGA36025       30       HGL360355       26         HDA26070()       30       HDL26110C       26       HDL36110T       33       HGA36030       30       HGL36035C       26         HDA26080()       30       HDL26125       26       HDL36125       26       HGA36035       30       HGL36035T       33         HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040       26         HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33	HDA26040()	30	HDL26090C26	HDL36100U53X	28	HGA26150()30	HGL3603026
HDA26050()       30       HDL26100C       26       HDL36110       26       HGA36020       30       HGL36030T       33         HDA26060()       30       HDL26110       26       HDL36110C       26       HGA36025       30       HGL360355       26         HDA26070()       30       HDL26110C       26       HDL36110T       33       HGA36030       30       HGL36035C       26         HDA26080()       30       HDL26125       26       HDL36125       26       HGA36035       30       HGL36035T       33         HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040       26         HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33							
HDA26060()       30       HDL26110       26       HDL36110C       26       HGA36025       30       HGL36035       26         HDA26070()       30       HDL26110C       26       HDL36110T       33       HGA36030       30       HGL36035C       26         HDA26080()       30       HDL26125       26       HDL36125       26       HGA36035       30       HGL36035T       33         HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040       26         HDA26100()       30       HDL26150       26       HDL36155T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33	( )						
HDA26070()       30       HDL26110C       26       HDL36110T       33       HGA36030       30       HGL36035C       26         HDA26080()       30       HDL26125       26       HDL36125       26       HGA36035       30       HGL36035T       33         HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040       26         HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33							
HDA26080()       30       HDL26125       26       HDL36125       26       HGA36035       30       HGL36035T       33         HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040       26         HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33							
HDA26090()       30       HDL26125C       26       HDL36125C       26       HGA36040       30       HGL36040       26         HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33							
HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33	HDA26080()	30	HDL2612526	HDL36125	26	HGA3603530	HGL36035T33
HDA26100()       30       HDL26150       26       HDL36125T       33       HGA36045       30       HGL36040C       26         HDA26110()       30       HDL26150C       26       HDL36150       26       HGA36050       30       HGL36040T       33	HDA26090()	30	HDL26125C26	HDL36125C	26	HGA3604030	HGL3604026
HDA26110()							
прадотдо ( )	* * *						
	TIDA20123()	30	11DE3001326	11DE30130C	20	11GA3000030	11GL300432b

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Catalog Numbers

HoLS0605C										
Hol.36906T	HGI 36045C	26	H.IA26030( )	30	H.II 26150C	26	H.II 36125T	33	HLL26030C	26
HGL36900										
Hol.26000C  26										
Hold-Seption										
Hold-Sep800  26										
Hold-Sep00C)										
HGL3600CULSTX	HGL36060	26	HJA26060()	30	HJL36020C	26	HJL36150CU43X	28	HLL26045	26
HGL3600CULSTX	HGL36060C	26	HJA26070()	30	HJL36020T	33	HJL36150CU53X	28	HLL26045C	26
HGL36900CU39X   28										
HGL3880CU48X 28 HJA28100] 30 HJL380207 23 HJL38150TU31X 34 HJL2090C 26 HGL3800CU32X 28 HJA28101] 30 HJL380207 25 HJL38150TU31X 34 HJL2090C 26 HGL3800CU31X 34 HJA28150] 30 HJL38030T 33 HJL38150TU31X 34 HJL2090C 26 HGL3800CU31X 34 HJA38150] 30 HJL38030T 33 HJL38150TU34X 34 HJL2090C 26 HGJS800CU3XX 34 HJA38015 30 HJL38030T 33 HJL38030X 34 HJL2090C 26 HGJS800CU3XX 34 HJA38015 30 HJL38030C 28 HJL38150TU34X 34 HJL2090C 26 HGJS800CU3XX 34 HJA3802C 30 HJL38030CC 28 HJL38150TU34X 32 HJL2090C 26 HGJS800CU3XX 34 HJA3802C 30 HJL38030C 28 HJL38150TU34X 32 HJL2090C 26 HGJS800CU3XX 34 HJA3802C 30 HJL3800CC 28 HJL38150U3XX 28 HJL2090C 26 HGJS800CU3XX 34 HJA3803C 30 HJL3800CC 28 HJL38150U3XX 28 HJL2090C 26 HGJS800CU3XX 34 HJA3803C 30 HJL3800HG 28 HJL38150U3XX 28 HJL2090C 26 HGJS800CU3XX 34 HJA3803C 30 HJL3800HG 28 HJL38150U3XX 28 HJL2010C 26 HGJS800CU3XX 37 HJA3803C 30 HJL3800HG 28 HJL38150U3XX 28 HJL2010C 26 HGJS800CU3XX 38 HJA3803C 30 HJL3800HG 28 HJL38150U3XX 28 HJL2010C 26 HGJS800CU3XX 28 HJA3803C 30 HJL3800HG 28 HJL38150U3XX 28 HJL2010C 26 HGJS800CU3XX 28 HJA3803C 30 HJL3800HG 28 HJL38150U3XX 28 HJL2010C 26 HGJS800CU3XX 28 HJL3800CU3XX 28 HJL3800CU3XX 28 HJL3800HG 28 HJL38150U3XX 28 HJL3800CU3XX 28 HJL3800HG 28 HJL38150U3XX 28 HJL3800CU3XX 28 HJL3800HG 28 HJL38015C 26 HGJS800CU3XX 28 HJL3800CU3XX 28 H			( /							
HGL38060CUS3X 28 HJA28110) 30 HJL38030C 26 HJL38150TUS3X 34 HJL20070 26 HGL38060TUS3X 34 HJL20070 26 HGL38060TUS3X 34 HJL20070 26 HGL38060TUS3X 34 HJL20070 26 HJL38060TUS3X 34 HJL30070 30 HJL38060TUS3X 34 HJL30070 26 HJL38060TUS3X 34 HJL30070 27 HJL38060TUS3X 34 HJL30070 27 HJ										
HOL38600T 33 HJA26125) 30 HJ.36030C 26 HJ.3515TJAXX 34 HLL28070 26 HOL38600TUSX 34 HAJ2616() 30 HJ.36030T 33 HJA3515TJAXX 34 HLL28070 26 HOL38600TUSX 34 HAJ2616() 30 HJ.36030T 33 HJA3515TJAXX 34 HLL28070 26 HOL3800TUSX 34 HAJ2616() 30 HJ.36030T 33 HJA3515TJAXX 34 HLL28080 26 HOL3800TUSX 34 HAJ2616() 30 HJ.36035C 26 HJJ.3515UJX 28 HLJ28090 26 HOL3800TUSX 34 HJA36035 30 HJ.36040T 26 HJJ.3515UJX 28 HLJ28090 26 HOL3800TUSX 34 HJA36035 30 HJJ.36040T 26 HJJ.3515UJX 28 HLJ28090 26 HOL3800TUSX 34 HJA36035 30 HJJ.36040T 26 HJJ.3515UJXX 28 HLJ28090 26 HOL3800TUSX 28 HJA36035 30 HJJ.36040T 28 HJJ.3515UJXX 28 HLJ28100 26 HJJ.3515UJXX 28 HJJ.3515UJXX 28 HJJ.3615UJXX 28 HJJ.3										
HGL38060TU31X 34 HJA26156(j) 30 HJL38030M71 50 HJL38150TU4XX 34 HLL28080 26 HGL3806TU4XX 34 HJL3800S 30 HJL3803S 34 HJA3915TU5XX 34 HJL28080 26 HGL3806TU4XX 34 HJL3803S 30 HJL3803S 32 HJL3815TU5XX 34 HJL28080 26 HGL3806TU4XX 34 HJA393S 30 HJL3803S 32 HJL3815TU5XX 32 HJL3815TU5XX 32 HGL3808TU5XX 34 HJA393S 30 HJL3804D 26 HGJ3806TU5XX 34 HJA393S 30 HJL3804D 26 HGJ3806TU5XX 32 HJL3815TU5XX 32 HGJ3815TU5XX 32 HGJ38			, ,							
HGL3660TUSX 3 4 HJA8010 30 HJL56035 26 HJL3615TUSX 3 4 HL26080 26 HGL3600TU4X 3 4 HJA8020 30 HJL56035 26 HJL3615TUSX 3 4 HL26080 26 HGL3600TU4X 3 4 HJA8020 30 HJL56035 26 HJL3615TUSX 3 2 HJL26080 26 HGL3600TU4X 3 4 HJA8020 30 HJL56035 26 HJL3615TUSX 3 2 HJL26030 26 HGL3600TU4X 3 4 HJA8020 30 HJL56040 26 HJA815TUSX 3 2 HJL2610 26 HGL3606UJX 28 HJA8045 30 HJL56040 26 HJA815TUSX 3 2 HJL2610 26 HGL3606UJX 28 HJA8045 30 HJL56040 26 HJA815TUSX 3 2 HJL2610 26 HGL3606UJX 28 HJA8045 30 HJL56040 26 HJA815TUSX 3 2 HJL2610 26 HGL3606UJX 28 HJA8045 30 HJL56040 26 HJA815TUSX 3 2 HJL2610 26 HGL3606UJX 28 HJA8045 30 HJL56040 26 HJA815TUSX 3 2 HJL2610 26 HGL3606UJX 28 HJA8045 30 HJL56040 26 HJA815TUSX 3 2 HJL2610 26 HJA815TUSX 3 2 HJL5605 26 HJA8260UJX 2 HJA8060UJX 3 2 HJL56050 26 HJA8260UJX 2 HJA8060UJX 3 2 HJL56050 26 HJA8260UJX 3 2 HJL56050 26 HJA8260UJX 3 2 HJA8060UJX 3 2 HJL56050 26 HJA8260UJX 3 2 HJA8060UJX 3 2 HJA8060U										
HGL36900TU-43X 43	HGL36060TU31X	34	HJA26150()	30	HJL36030M71	50	HJL36150TU44X	34	HLL26070C	26
HGL38060TU4HX 34 HJA80020 30 HJL3803SC 26 HJL38150U3HX 28 HLL28000 26 HGL38060TU4HX 34 HJA80303 30 HJL38040 28 HJL38150U3HX 28 HJL2800C 26 HGL38060TU4HX 34 HJA80303 30 HJL38040 28 HJL38150U3HX 28 HJL28100 28 HGL38060U3HX 28 HJA80405 30 HJL38040T 33 HJL38150U3HX 28 HJL28110 28 HGL38060U3HX 28 HJA80405 30 HJL38040T 33 HJL38150U3HX 28 HJL28110 28 HGL38060U3HX 28 HJA8060 30 HJL38045 26 HJL38150U3HX 28 HJL28110 28 HGJA8060U3HX 28 HJA8060U3HX	HGL36060TU33X	34	HJA36015	30	HJL36030T	33	HJL36150TU53X	34	HLL26080	26
HGL38060TU4HX 34 HJA80050 30 HJS8003CC 26 HJAS150DJ1X 28 HLL28000C 26 HGL38060TU4HX 34 HJA8003D 30 HJS8014 28 HJAS15DJ1XX 28 HJL2810D 26 HGL38060TU4HX 34 HJA8003D 30 HJS8014 28 HJAS15DJ1XX 28 HJL2810D 26 HGL3806DJXX 28 HJA8005D 30 HJS8014 28 HJA8005X 28 HJA8	HGL36060TU43X	. 34	HJA36020	30	HJL36035	26	HJL36150TU54X	34	HLL26080C	26
HGL36060TUSAX										
HGL38060U35X										
HGL58060U31X   28										
HGL36600U34X   28										
HGL38060U143X   28	HGL36060U31X	28			HJL36040C	26	HJL36150U44X	28	HLL26100C	26
HGL38060U44	HGL36060U33X	28	HJA36045	30	HJL36040T	33	HJL36150U53X	28	HLL26110	26
HGL38060U44	HGI 36060U43X	28	HJA36050	30	H.II 36045	26	H.II 36150U54X	28	HLL 26110C	26
HGL36960U53X   28										
HGL380F00U54X   28										
HGL380070										
HGL380707C   26			HJA36060U33X	32						
HGL36000   26	HGL36070	26	HJA36060U43X	32	HJL36050C	26	HLA26030()	30	HLL26150C	26
HGL36000   26	HGL36070C	26	HJA36060U44X	32	HJL36050M72	50	HLA26035()	30	HLL36015	26
HGL38080										
HGL36080C										
HGL36090T 33 HJA36090 90 HJJ36060CU31X 28 HJA26070() 30 HJL36020C 26 HJA36090 26 HJA36090 30 HJJ36060CU43X 28 HJA26070() 30 HJL36025 26 HJA36100 30 HJJ36060CU43X 28 HJA26600() 30 HJL36025 26 HJA36100 26 HJA36100 30 HJJ36060CU43X 28 HJA26600() 30 HJL36025 26 HJA36100 26 HJA36100U31X 32 HJJ36060CU31X 31 HJA26100() 30 HJL36025 26 HJA36100U31X 32 HJJ36060CU31X 31 HJA26100() 30 HJL36025 26 HJA36100U31X 32 HJJ36060TU31X 31 HJA26100() 30 HJL36025 26 HJA36100U31X 32 HJJ36060TU31X 34 HJA26100() 30 HJL36025 26 HJA36100U31X 32 HJJ36060TU31X 34 HJA26100() 30 HJL36025 26 HJA36100U31X 32 HJJ36060TU31X 34 HJA26110() 30 HJL36025 26 HJA26100CU31X 28 HJA261100U31X 32 HJJ36060TU31X 34 HJA26110() 30 HJL36025 26 HJA26110CU31X 32 HJA36125 30 HJJ36026TU31X 34 HJA36120U31X 32 HJA36120TU31X 34 HJA36150U31X 32 HJJ36060TU31X 34 HJA36120TU31X 34 HJA36150U31X 32 HJJ36060TU31X 34 HJA36130TU31X 32 HJJ36060TU31X 32 HJJ36060U31X 28 HJA36313X 34 HJA36150U31X 32 HJJ36060U31X 28 HJA36313X 34 HJA36150U31X 32 HJJ36060U31X 28 HJA36303 30 HJJ36035T 33 HJA36125 30 HJJ36060U31X 32 HJJ36060U31X 3										
HGL36909C 26 HJA36100 30 HLJ36060CU33X 28 HLA26060() 30 HLJ36020T 33 HGL36090T 36 HLJ36060CU53X 28 HLA26060() 30 HLJ36025C 26 HGL36100 26 HJA36100U31X 32 HJJ36060CU53X 28 HLA26090() 30 HLJ36025C 26 HGL36100 26 HJA36100U33X 32 HJJ36060TU33X 34 HLA26110() 30 HLJ36025C 26 HJA36100CU53X 28 HJA36100U43X 32 HJJ36060TU33X 34 HLA26110() 30 HLJ36025C 26 HGL36100CU53X 28 HJA36100U43X 32 HJJ36060TU33X 34 HLA26110() 30 HLJ36025C 26 HGL3610CU53X 28 HJA36100U54X 32 HJJ36060TU33X 34 HLA26110() 30 HLJ36030 26 HGL3610CU53X 28 HJA36100U554X 32 HJJ36060TU33X 34 HLA26150() 30 HLJ36030M71 50 HGL3610CU53X 28 HJA3610U554X 32 HJJ36060TU34X 34 HLA26150() 30 HLJ36030M71 50 HGL3610CU53X 28 HJA3610U554X 32 HJJ36060TU34X 34 HLA26150() 30 HLJ36030M71 50 HGL3610CU53X 34 HJA36110U554X 32 HJJ36060TU34X 34 HJA36150U554X 32 HJA3610U554X 34 HJA36150U554X 32 HJA3610U554X 34 HJA36150U33X 32 HJA36150U33X										
HGL36990C   26	HGL36080T	33	HJA36080	30	HJL36060CU31X	28	HLA26060()	30	HLL36020C	26
HGL36990C   26	HGL36090	26	HJA36090	30	HJL36060CU33X	28	HLA26070()	30	HLL36020T	33
HGL36100										
HGL361000										
HGLS6100C   26										
HGL38100CU31X   28										
HGL36100CU43X   28	HGL36100C	26	HJA36100U43X	32			HLA26110()	30	HLL36030	26
HGL36100CU43X   28	HGL36100CU31X	28	HJA36100U44X	32	HJL36060TU33X	34	HLA26125()	30	HLL36030C	26
HGL38100CU43X   28	HGI 36100CU33X	28	HJA36100U53X	32					HLL36030M71	50
HGL36100CU53X   28										
HGL36100T										
HGL36100TU31X										
HGL36100TU33X										
HGL36100TU43X	HGL36100TU31X	34	HJA36150	30	HJL36060U31X	28	HLA36030	30	HLL36035T	33
HGL36100TU43X   34	HGL36100TU33X	34	HJA36150U31X	32	HJL36060U33X	28	HLA36035	30	HLL36040	26
HGL36100TU44X   34										
HGL36100TU53X   34										
HGL36100TU54X   34										
HGL36100U31X   28										
HGL36100U33X   28	HGL36100TU54X	34	HJA36150U53X	32			HLA36060	30	HLL36045C	26
HGL36100U43X   28	HGL36100U31X	28	HJA36150U54X(	32	HJL36070	26	HLA36060U31X	32	HLL36045T	33
HGL36100U43X   28	HGL36100U33X	28	HJF36000F06	35	HJL36070C	26	HLA36060U33X	32	HLL36050	26
HGL36100U44X   28										
HCL36100U53X   28										
HGL36100U54X   28										
HGL36110										
HGL36110C   26										
HGL36110T   33	HGL36110	26	HJL26020C	26	HJL36090	26	HLA36070	30	HLL36060C	26
HGL36110T   33	HGI 36110C	26	HJI 26025	26	HJI 36090C	26	HLA36080	30	HLL36060CU31X	28
HGL36125										
HGL36125C   26										
HGL36150T 33 HJL26035 26 HJL36100CU31X 28 HLA36100U33X 32 HLL36060T 33 HGL36150 26 HJL26035C 26 HJL36100CU33X 28 HLA36100U43X 32 HLL36060TU31X 34 HGL36150CU31X 28 HJL26040 26 HJJ36100CU53X 28 HLA36100U44X 32 HLL36060TU31X 34 HGL36150CU31X 28 HJL26040C 26 HJJ36100CU53X 28 HJCA610U53X 32 HLL36060TU43X 34 HGL36150CU33X 28 HJL26045 26 HJJ36100M73 50 HLA36100U54X 32 HLL36060TU44X 34 HGL36150CU43X 28 HJL26045 26 HJJ36100TU31X 34 HLA36150CU33X 28 HJL2605C 26 HJJ36100TU31X 34 HLA36150CU33X 28 HJL26050 26 HJJ36100TU31X 34 HLA36155 30 HLL36060TU53X 34 HGL36150CU53X 38 HJL26050 26 HJJ36100TU31X 34 HLA36155 30 HLL36060TU53X 34 HGL36150TU31X 34 HJL26050 26 HJJ36100TU31X 34 HLA36150 30 HLL36060TU53X 34 HGL36150TU31X 34 HJL26060 26 HJJ36100TU31X 34 HLA36150 30 HLL36060U31X 28 HGL36150TU31X 34 HJL26060 26 HJJ36100TU43X 34 HLA36150 30 HLL36060U31X 28 HGL36150TU31X 34 HJL26060 26 HJJ36100TU43X 34 HLA36150U31 32 HLL36060U31X 28 HGL36150TU43X 34 HJL26070 26 HJJ36100TU53X 34 HLA36150U31 32 HLL36060U33X 28 HGL36150TU43X 34 HJL26070 26 HJJ36100TU53X 34 HLA36150U31X 32 HLL36060U44X 28 HGL36150TU44X 34 HJL26070 26 HJJ36100TU53X 34 HLA36150U43X 32 HLL36060U44X 28 HGL36150TU53X 34 HJL26080 26 HJJ36100TU53X 34 HLA36150U43X 32 HLL36060U54X 28 HGL36150TU53X 34 HJL26080 26 HJJ36100U31X 28 HLA36150U4X 32 HLL36060U54X 28 HGL36150TU53X 34 HJL26080 26 HJJ36100U31X 28 HLA36150U53X 32 HLL36060U54X 28 HGL36150TU53X 34 HJL26080 26 HJJ36100U33X 28 HLA36150U53X 32 HLL36060U54X 28 HGL36150TU53X 34 HJL26080 26 HJJ36100U33X 28 HLA36150U55X 32 HLL36060U54X 28 HGL36150U33X 28 HJL26090 26 HJJ36100U33X 28 HJL26015C 26 HJJ36100U53X 28 HLJ36000F06 35 HLL36070 26 HGL36150U33X 28 HJL26090 26 HJJ36100U53X 28 HLJ56005 26 HJJ36100U53X 28 HJJ56005 26 HJJ36100U55X 28 HJJ56100 26 HJJ36100U55X										
HGL36150										
HGL36150C										
HGL36150C	HGL36150	26	HJL26035C	26	HJL36100CU33X	28	HLA36100U43X	32	HLL36060TU31X	34
HGL36150CU31X 28 HJL26040C 26 HJL36100CU53X 28 HLA36100U53X 32 HLL36060TU43X 34 HGL36150CU33X 28 HJL26045 26 HJL36100M73 50 HLA36100U54X 32 HLL36060TU44X 34 HGL36150CU43X 28 HJL2605C 26 HJL36100T 33 HLA36110 30 HLL36060TU53X 34 HGL36150CU53X 28 HJL26050 26 HJL36100TU31X 34 HLA36125 30 HLL36060TU53X 34 HGL36150TU31X 34 HLA36150T 33 HJL26050C 26 HJL36100TU33X 34 HLA36150 30 HLL36060U31X 28 HGL36150TU31X 34 HJL26060 26 HJL36100TU33X 34 HLA36150 30 HLL36060U31X 28 HGL36150TU31X 34 HJL26060 26 HJL36100TU43X 34 HLA36150U31 32 HLL36060U31X 28 HGL36150TU33X 34 HJL26060C 26 HJL36100TU44X 34 HLA36150U33X 32 HLL36060U43X 28 HGL36150TU43X 34 HJL26070 26 HJL36100TU53X 34 HLA36150U33X 32 HLL36060U43X 28 HGL36150TU44X 34 HJL26070 26 HJL36100TU53X 34 HLA36150U43X 32 HLL36060U44X 28 HGL36150TU53X 34 HJL26080 26 HJL36100TU54X 34 HLA36150U44X 32 HLL36060U54X 28 HGL36150TU53X 34 HJL26080 26 HJL36100U31X 28 HLA36150U44X 32 HLL36060U54X 28 HGL36150TU53X 34 HJL26080 26 HJL36100U31X 28 HLA36150U53X 32 HLL36060U54X 28 HGL36150TU54X 34 HJL26080 26 HJL36100U33X 28 HLA36150U53X 32 HLL36060U54X 28 HGL36150U31X 28 HJL26090 26 HJL36100U33X 28 HLA36150U53X 32 HLL36060U54X 28 HGL36150U31X 28 HJL26090 26 HJL36100U43X 28 HLF36000F06 35 HLL36070 26 HGL36150U33X 28 HJL26090 26 HJL36100U44X 28 HLF36000F06 35 HLL36070C 26 HGL36150U43X 28 HJL26100 26 HJL36100U53X 28 HLF36000F06 35 HLL36070C 26 HGL36150U44X 28 HJL26100 26 HJL36100U53X 28 HLL26015 26 HLL36080C 26 HGL36150U53X 28 HJL26100 26 HJL36100U53X 28 HLL26015 26 HLL36080C 26 HGL36150U53X 28 HJL26100 26 HJL36100U53X 28 HJL26010C 26 HJL36100U53X 28 HJL26020 26 HLL36080C 26 HGL36150U53X 28 HJL26100 26 HJL36110C 26 HJL36110C 26 HJL36090C 26 HJL36090C 26 HJL36010C 26 HJ	HGL36150C	26	HJL26040	26					HLL36060TU33X	34
HGL36150CU33X         28         HJL26045         26         HJL36100M73         50         HLA36100U54X         32         HLL36060TU44X         34           HGL36150CU43X         28         HJL26045C         26         HJL36100T         33         HLA36110         30         HLL36060TU53X         34           HGL36150CU53X         28         HJL26050C         26         HJL36100TU31X         34         HLA36125         30         HLL36060TU54X         34           HGL36150TU31X         34         HJL26050C         26         HJL36100TU33X         34         HLA36155         30         HLL36060U31X         28           HGL36150TU31X         34         HJL26060C         26         HJL36100TU43X         34         HLA36150U31         32         HLL36060U33X         28           HGL36150TU33X         34         HJL26060C         26         HJL36100TU44X         34         HLA36150U33X         32         HLL36060U33X         28           HGL36150TU43X         34         HJL26070C         26         HJL36100TU53X         34         HLA36150U33X         32         HLL36060U44X         28           HGL36150TU53X         34         HJL26080C         26         HJL36100U51X         34         HLA36150U53X <td></td>										
HGL36150CU43X         28         HJL26045C         26         HJL36100T         33         HLA36110         30         HLL36060TU53X         34           HGL36150CU53X         28         HJL26050         26         HJL36100TU31X         34         HLA36125         30         HLL36060TU54X         34           HGL36150T         33         HJL26050C         26         HJL36100TU33X         34         HLA36150         30         HLL36060U31X         28           HGL36150TU31X         34         HJL26060C         26         HJL36100TU43X         34         HLA36150U31         32         HLL36060U33X         28           HGL36150TU33X         34         HJL26060C         26         HJL36100TU4X         34         HLA36150U33X         32         HLL36060U33X         28           HGL36150TU43X         34         HJL26070         26         HJL36100TU53X         34         HLA36150U43X         32         HLL36060U44X         28           HGL36150TU54X         34         HJL26070         26         HJL36100TU54X         34         HLA36150U43X         32         HLL36060U53X         28           HGL36150TU53X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X										
HGL36150CU53X         28         HJL26050         26         HJL36100TU31X         34         HLA36125         30         HLL36060TU54X         34           HGL36150T         33         HJL26050C         26         HJL36100TU33X         34         HLA36150         30         HLL36060U31X         28           HGL36150TU31X         34         HJL26060         26         HJL36100TU43X         34         HLA36150U31         32         HLL36060U33X         28           HGL36150TU33X         34         HJL26070         26         HJL36100TU43X         34         HLA36150U33X         32         HLL36060U43X         28           HGL36150TU44X         34         HJL26070         26         HJL36100TU53X         34         HLA36150U43X         32         HLL36060U43X         28           HGL36150TU53X         34         HJL26070C         26         HJL36100TU54X         34         HLA36150U43X         32         HLL36060U53X         28           HGL36150TU53X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U53X         28           HGL36150U31X         38         HJL26080         26         HJL36100U31X         28         HLA36150U54X										
HGL36150T         33         HJL26050C         26         HJL36100TU33X         34         HLA36150         30         HLL36060U31X         28           HGL36150TU31X         34         HJL26060         26         HJL36100TU43X         34         HLA36150U31         32         HLL36060U33X         28           HGL36150TU33X         34         HJL26070C         26         HJL36100TU43X         34         HLA36150U33X         32         HLL36060U43X         28           HGL36150TU43X         34         HJL26070C         26         HJL36100TU53X         34         HLA36150U43X         32         HLL36060U44X         28           HGL36150TU44X         34         HJL26070C         26         HJL36100TU54X         34         HLA36150U43X         32         HLL36060U44X         28           HGL36150TU53X         34         HJL26080         26         HJL36100U31X         28         HLA36150U44X         32         HLL36060U53X         28           HGL36150TU53X         34         HJL26080C         26         HJL36100U31X         28         HLA36150U54X         32         HLL36060U53X         28           HGL36150U31X         28         HJL26080C         26         HJL36100U33X         28         HLS6000C										
HGL36150TU31X         34         HJL26060         26         HJL36100TU43X         34         HLA36150U31         32         HLL36060U33X         28           HGL36150TU33X         34         HJL26060C         26         HJL36100TU4XX         34         HLA36150U33X         32         HLL36060U43X         28           HGL36150TU4XX         34         HJL26070C         26         HJL36100TU5XX         34         HLA36150U4XX         32         HLL36060U4XX         28           HGL36150TU4XX         34         HJL26080C         26         HJL36100TU54X         34         HLA36150U4XX         32         HLL36060U54X         28           HGL36150TU53X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U54X         28           HGL36150TU54X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U54X         28           HGL36150U31X         28         HJL26090         26         HJL36100U33X         28         HLF36000F06         35         HLL36070C         26           HGL36150U33X         28         HJL26100         26         HJL36100U44X         28         HLF36000F15 <td></td>										
HGL36150TU31X         34         HJL26060         26         HJL36100TU43X         34         HLA36150U31         32         HLL36060U33X         28           HGL36150TU33X         34         HJL26060C         26         HJL36100TU44X         34         HLA36150U33X         32         HLL36060U43X         28           HGL36150TU43X         34         HJL26070         26         HJL36100TU54X         34         HLA36150U43X         32         HLL36060U44X         28           HGL36150TU44X         34         HJL26070C         26         HJL36100TU54X         34         HLA36150U44X         32         HLL36060U44X         28           HGL36150TU53X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U54X         28           HGL36150TU54X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U54X         28           HGL36150U31X         28         HJL26090         26         HJL36100U33X         28         HLF36000F06         35         HLL36070C         26           HGL36150U33X         28         HJL26090C         26         HJL36100U44X         28         HLF36000F15 <td>HGL36150T</td> <td> 33</td> <td>HJL26050C</td> <td> 26</td> <td>HJL36100TU33X</td> <td>34</td> <td>HLA36150</td> <td> 30</td> <td>HLL36060U31X</td> <td>28</td>	HGL36150T	33	HJL26050C	26	HJL36100TU33X	34	HLA36150	30	HLL36060U31X	28
HGL36150TU33X         34         HJL26060C         26         HJL36100TU44X         34         HLA36150U33X         32         HLL36060U43X         28           HGL36150TU43X         34         HJL26070         26         HJL36100TU53X         34         HLA36150U43X         32         HLL36060U44X         28           HGL36150TU44X         34         HJL26070C         26         HJL36100TU54X         34         HLA36150U44X         32         HLL36060U53X         28           HGL36150TU54X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U54X         28           HGL36150TU54X         34         HJL26080C         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U54X         28           HGL36150U31X         28         HJL26090         26         HJL36100U33X         28         HLF36000F06         35         HLL36070C         26           HGL36150U33X         28         HJL26090C         26         HJL36100U44X         28         HLF36000F06         35         HLL36070T         33           HGL36150U43X         28         HJL26090C         26         HJL36100U44X         28         HLE36000F15	HGL36150TU31X	34	HJL26060	26			HLA36150U31	32	HLL36060U33X	28
HGL36150TU43X         34         HJL26070         26         HJL36100TU53X         .34         HLA36150U43X         32         HLL36060U44X         .28           HGL36150TU4XX         .34         HJL26070C         .26         HJL36100TU54X         .34         HLA36150U44X         .32         HLL36060U53X         .28           HGL36150TU53X         .34         HJL26080         .26         HJL36100U31X         .28         HLA36150U53X         .32         HLL36060U54X         .28           HGL36150TU54X         .34         HJL26090         .26         HJL36100U33X         .28         HLA36150U54X         .32         HLL36070C         .26           HGL36150U31X         .28         HJL26090         .26         HJL36100U33X         .28         HLF36000F06         .35         HLL36070C         .26           HGL36150U33X         .28         HJL26090C         .26         HJL36100U43X         .28         HLF36000F16         .35         HLL36070C         .26           HGL36150U43X         .28         HJL26090C         .26         HJL36100U44X         .28         HLL26015         .35         HLL36090T         .33           HGL36150U44X         .28         HJL26100C         .26         HJL36100U54X         .28										
HGL36150TU44X         34         HJL26070C         26         HJL36100TU54X         34         HLA36150U44X         32         HLL36060U53X         28           HGL36150TU53X         34         HJL26080         26         HJL36100U31X         28         HLA36150U53X         32         HLL36060U54X         28           HGL36150TU54X         34         HJL26080C         26         HJL36100U33X         28         HLA36150U54X         32         HLL36070         26           HGL36150U31X         28         HJL26090         26         HJL36100U43X         28         HLF36000F06         35         HLL36070C         26           HGL36150U33X         28         HJL26090C         26         HJL36100U44X         28         HLF36000F16         35         HLL36070C         26           HGL36150U43X         28         HJL26100         26         HJL36100U54X         28         HLL26015         26         HLL36080         26           HGL36150U44X         28         HJL26100C         26         HJL36100U54X         28         HLL26015C         26         HLL36080C         26           HGL36150U54X         28         HJL26110         26         HJL36110         26         HLL26020         26 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>										
HGL36150TU53X         .34         HJL26080         .26         HJL36100U31X         .28         HLA36150U53X         .32         HLL36060U54X         .28           HGL36150TU54X         .34         HJL26080C         .26         HJL36100U33X         .28         HLA36150U54X         .32         HLL36070         .26           HGL36150U31X         .28         HJL26090         .26         HJL36100U43X         .28         HLF36000F16         .35         HLL36070C         .26           HGL36150U33X         .28         HJL26090C         .26         HJL36100U44X         .28         HLF36000F15         .35         HLL36070T         .33           HGL36150U43X         .28         HJL26100         .26         HJL36100U53X         .28         HLL26015         .26         HLL36080         .26           HGL36150U44X         .28         HJL26100C         .26         HJL36100U54X         .28         HLL26015C         .26         HLL36080C         .26           HGL36150U53X         .28         HJL26110         .26         HJL36110         .26         HLL26020         .26         HLL36080T         .33           HGL36150U54X         .28         HJL26110C         .26         HJL36110C         .26         HLL26020C										
HGL36150TU54X       34       HJL26080C       26       HJL36100U33X       28       HLA36150U54X       32       HLL36070       26         HGL36150U31X       28       HJL26090       26       HJL36100U43X       28       HLF36000F06       35       HLL36070C       26         HGL36150U33X       28       HJL26090C       26       HJL36100U44X       28       HLF36000F15       35       HLL36070T       33         HGL36150U43X       28       HJL26100       26       HJL36100U53X       28       HLL26015       26       HLL36080       26         HGL36150U44X       28       HJL26100C       26       HJL36100U54X       28       HLL26015C       26       HLL36080C       26         HGL36150U53X       28       HJL26110       26       HJL36110       26       HJL36110       26       HLL26020       26       HLL36080T       33         HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020C       26       HLL36090       26         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090T       36         HJA26020()       30       HJL26125C <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>										
HGL36150U31X       28       HJL26090       26       HJL36100U43X       28       HLF36000F06       35       HLL36070C       26         HGL36150U33X       28       HJL26090C       26       HJL36100U44X       28       HLF36000F15       35       HLL36070T       33         HGL36150U43X       28       HJL26100       26       HJL36100U53X       28       HLL26015       26       HLL36080       26         HGL36150U44X       28       HJL26100C       26       HJL36100U54X       28       HLL26015C       26       HLL36080C       26         HGL36150U53X       28       HJL26110       26       HJL36110       26       HJL36110       26       HLL26020       26       HLL36080T       33         HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020       26       HLL36090       26         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HLL26025C       26       HLL36090T       33										
HGL36150U31X       28       HJL26090       26       HJL36100U43X       28       HLF36000F06       35       HLL36070C       26         HGL36150U33X       28       HJL26090C       26       HJL36100U44X       28       HLF36000F15       35       HLL36070T       33         HGL36150U43X       28       HJL26100       26       HJL36100U53X       28       HLL26015       26       HLL36080       26         HGL36150U44X       28       HJL26100C       26       HJL36100U54X       28       HLL26015C       26       HLL36080C       26         HGL36150U53X       28       HJL26110       26       HJL36110       26       HJL36110       26       HLL26020       26       HLL36080T       33         HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020       26       HLL36090T       33         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HLL26025C       26       HLL36090T       33	HGL36150TU54X	34	HJL26080C	26	HJL36100U33X	28	HLA36150U54X	32	HLL36070	26
HGL36150U33X       28       HJL26090C       26       HJL36100U44X       28       HLF36000F15       35       HLL36070T       33         HGL36150U43X       28       HJL26100       26       HJL36100U53X       28       HLL26015       26       HLL36080C       26         HGL36150U44X       28       HJL26100C       26       HJL36100U54X       28       HLL26015C       26       HLL36080C       26         HGL36150U53X       28       HJL26110       26       HJL36110       26       HLL2602C       26       HLL36080T       33         HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020C       26       HLL36090       26         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HJL36025C       26       HLL36090T       33										
HGL36150U43X       28       HJL26100       26       HJL36100U53X       28       HLL26015       26       HLL36080       26         HGL36150U44X       28       HJL2610C       26       HJL36100U54X       28       HLL26015C       26       HLL36080C       26         HGL36150U53X       28       HJL26110       26       HJL36110       26       HLL26020       26       HLL36080T       33         HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020C       26       HLL36090       26         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HLL26025C       26       HLL36090T       33										
HGL36150U44X       28       HJL26100C       26       HJL36100U54X       28       HLL26015C       26       HLL36080C       26         HGL36150U53X       28       HJL26110       26       HJL36110       26       HLL26020       26       HLL36080T       33         HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020C       26       HLL36090C       26         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HJL36125       26       HLL26025C       26       HLL36090T       33										
HGL36150U53X       28       HJL26110       26       HJL36110       26       HLL26020       26       HLL36080T       33         HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020C       26       HLL36090       26         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HLL26025C       26       HLL36090T       33										
HGL36150U54X       28       HJL26110C       26       HJL36110C       26       HLL26020C       26       HLL36090       26         HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HLL26025C       26       HLL36090T       33										
HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HLL26025C       26       HLL36090T       33	HGL36150U53X	28	HJL26110	26	HJL36110	26				
HJA26015()       30       HJL26125       26       HJL36110T       33       HLL26025       26       HLL36090C       26         HJA26020()       30       HJL26125C       26       HJL36125       26       HLL26025C       26       HLL36090T       33	HGL36150U54X	28	HJL26110C	26	HJL36110C	26	HLL26020C	26	HLL36090	26
HJA26020()										
10/20025()20   DL2013020   DL20130										
	1 10720020( )	00	1 10 LZ 0 1 3 0	20	10L001200	20	1 ILLEUUJU	20	1 ILLUU 100	20

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Catalog Numbers

HLL36100C	26	HRL36100U31X		JDL26250		JGL2622527	JJL26250C	
HLL36100CU31X	28	HRL36100U33X	28	JDL26250C	27	JGL26225C27	JJL34250WU31X	29
HLL36100CU33X	28	HRL36100U43X	28	JDL34250WU31X	29	JGL2625027	JJL34250WU33X	29
HLL36100CU43X		HRL36100U44X		JDL34250WU33X		JGL26250C27	JJL34250WU43X	
HLL36100CU53X		HRL36100U53X		JDL34250WU43X		JGL34250WU31X29	JJL34250WU44X	
HLL36100M73		HRL36100U54X		JDL34250WU44X		JGL34250WU33X29	JJL34250WU53X	
HLL36100T		HRL36150CU31X		JDL34250WU53X		JGL34250WU43X29	JJL34250WU54X	
HLL36100TU31X		HRL36150CU33X		JDL34250WU54X		JGL34250WU44X29	JJL36150	
HLL36100TU33X	34	HRL36150CU43X	28	JDL36150	27	JGL34250WU53X29	JJL36150C	
HLL36100TU43X	34	HRL36150CU53X	28	JDL36150C	27	JGL34250WU54X29	JJL36150T	33
HLL36100TU44X	34	HRL36150M74	50	JDL36150T	33	JGL3615027	JJL36175	27
HLL36100TU53X	34	HRL36150U31X	28	JDL36175	27	JGL36150C27	JJL36175C	27
HLL36100TU54X		HRL36150U33X		JDL36175C		JGL36150T33	JJL36175T	
HLL36100U31X		HRL36150U43X		JDL36175T		JGL3617527	JJL36200	
HLL36100U33X		HRL36150U44X		JDL36200		JGL36175C27	JJL36200C	
HLL36100U43X		HRL36150U53X		JDL36200C		JGL36175T33	JJL36200T	
HLL36100U44X	28	HRL36150U54X	28	JDL36200T	33	JGL3620027	JJL36225	27
HLL36100U53X	28	HT3015	34	JDL36225	27	JGL36200C27	JJL36225C	27
HLL36100U54X	28	HT3015	61	JDL36225C	27	JGL36200T33	JJL36225T	33
HLL36110		HT3020		JDL36225T		JGL3622527	JJL36250	
HLL36110C		HT3020		JDL36250		JGL36225C27	JJL36250C	
HLL36110T		HT3025		JDL36250C		JGL36225T33	JJL36250CU31X	
HLL36125		HT3025		JDL36250CU31X		JGL3625027	JJL36250CU33X	
HLL36125C	26	HT3030	34	JDL36250CU33X	28	JGL36250C27	JJL36250CU43X	28
HLL36125T	33	HT3030	61	JDL36250CU43X	28	JGL36250CU31X28	JJL36250CU53X	28
HLL36150	26	HT3035	34	JDL36250CU53X	28	JGL36250CU33X28	JJL36250M75	50
HLL36150C		HT3035		JDL36250T		JGL36250CU43X28	JJL36250T	
HLL36150CU31X		HT3040		JDL36250TU31X		JGL36250CU53X 28	JJL36250TU31X	
HLL36150CU33X		HT3040		JDL36250TU33X		JGL36250T33	JJL36250TU33X	
HLL36150CU43X	28	HT3045	34	JDL36250TU43X	34	JGL36250TU31X34	JJL36250TU43X	34
HLL36150CU53X	28	HT3045	61	JDL36250TU44X	34	JGL36250TU33X34	JJL36250TU44X	34
HLL36150M74		HT3050		JDL36250TU53X		JGL36250TU43X34	JJL36250TU53X	
HLL36150T		HT3050		JDL36250TU54X		JGL36250TU44X34	JJL36250TU54X	
HLL36150TU31X		HT3060		JDL36250U31X		JGL36250TU53X34	JJL36250U31X	
HLL36150TU33X		HT3060		JDL36250U33X	28	JGL36250TU54X34	JJL36250U33X	28
HLL36150TU43X	34	HT3070	34	JDL36250U43X	28	JGL36250U31X28	JJL36250U43X	28
HLL36150TU44X	34	HT3070	61	JDL36250U44X	28	JGL36250U33X28	JJL36250U44X	28
HLL36150TU53X		HT3080		JDL36250U53X		JGL36250U43X28	JJL36250U53X	
HLL36150TU54X		HT3080		JDL36250U54X		JGL36250U44X28	JJL36250U54X	
HLL36150U31X		HT3090		JE3250U31X		JGL36250U53X28	JLA34250WU31X	
HLL36150U33X		HT3090		JE3250U31X		JGL36250U54X28	JLA34250WU33X	
HLL36150U43X	28	HT3100	34	JE3250U33X	35	JGL37100D8118	JLA34250WU43X	32
HLL36150U44X	28	HT3100	61	JE3250U33X	68	JGL37125D81 18	JLA34250WU44X	32
HLL36150U53X	28	HT3110	34	JE3250U43X	35	JGL37150D8118	JLA34250WU53X	32
HLL36150U54X		HT3110		JE3250U43X		JGL37175D8118	JLA34250WU54X	
HRA36060U31X		HT3125		JE3250U44X		JGL37200D82 18	JLA36150	
HRA36060U33X		HT3125		JE3250U44X		JGL37225D8218	JLA36175	
HRA36060U43X	32	HT3150	34	JE3250U53X		JGL37250D8218	JLA36200	
HRA36060U44X	32	HT3150	61	JE3250U53X	69	JJA26150( )31	JLA36225	31
HRA36060U53X	32	JDA26150()	31	JE3250U54X	35			
HRA36060U54X				JL3230034A		JJA26175( )31	JLA36250	31
	32							
HBA36100U31X		JDA26175()	31	JE3250U54X	69	JJA26200( )31	JLA36250U31X	32
HRA36100U31X	32	JDA26175() JDA26200()	31 31	JE3250U54X JGA26150( )	69 31	JJA26200()31 JJA26225()31	JLA36250U31X JLA36250U33X	32 32
HRA36100U33X	32 32	JDA26175() JDA26200() JDA26225()	31 31 31	JE3250U54X JGA26150( ) JGA26175( )	69 31 31	JJA26200()31 JJA26225()31 JJA26250()31	JLA36250U31X JLA36250U33X JLA36250U43X	32 32 32
HRA36100U33X HRA36100U43X	32 32 32	JDA26175()	31 31 31 31	JE3250U54X JGA26150( ) JGA26175( ) JGA26200( )	69 31 31 31	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X	32 32 32 32
HRA36100U33X	32 32 32	JDA26175() JDA26200() JDA26225() JDA26250() JDA34250WU31X	31 31 31 31 32	JE3250U54X JGA26150() JGA26175() JGA26200() JGA26225()	69 31 31 31	JJA26200()31 JJA26225()31 JJA26250()31	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X	32 32 32 32
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X	32 32 32 32	JDA26175()	31 31 31 31 32	JE3250U54X JGA26150() JGA26175() JGA26200() JGA26225()	69 31 31 31 31	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X	32 32 32 32 32
HRA36100U33X HRA36100U43X HRA36100U44X	32 32 32 32	JDA26175() JDA26200() JDA26225() JDA26250() JDA34250WU31X	31 31 31 31 32 32	JE3250U54X JGA26150() JGA26175() JGA26200() JGA26225()	69 31 31 31 31	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X	32 32 32 32 32
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X	32 32 32 32 32	JDA26175()	31 31 31 31 32 32 32	JE3250U54X JGA26150() JGA26175() JGA26200() JGA26225()	69 31 31 31 31 31	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25	32 32 32 32 32 35
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X HRA36100U54X HRA36150U31	32 32 32 32 32 32	JDA26175()	31 31 31 32 32 32 32	JE3250U54X	69 31 31 31 31 31 32	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25 JLL26150	32 32 32 32 32 35 27
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X HRA36150U31 HRA36150U33X	32 32 32 32 32 32	JDA26175()	31 31 31 31 32 32 32 32 32	JE3250U54X	69 31 31 31 31 31 32 32	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25 JLL26150	32 32 32 32 32 35 27
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X HRA36150U31 HRA36150U33X HRA36150U43X	32 32 32 32 32 32 32	JDA26175()	31 31 31 31 32 32 32 32 32	JE3250U54X	69313131313131323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25 JLL26150 JLL26150 JLL26175	32 32 32 32 32 35 27 27
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U44X	32 32 32 32 32 32 32 32	JDA26175()	31 31 31 32 32 32 32 32 32 32	JE3250U54X	69313131313131323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25 JLL26150 JLL26150 JLL26175	32 32 32 32 32 35 27 27 27
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X HRA36150U31 HRA36150U33X HRA36150U43X	32 32 32 32 32 32 32 32	JDA26175()	31 31 31 32 32 32 32 32 32 32	JE3250U54X	69313131313131323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U53X JLA36250U53X JLF36000F25 JLL26150 JLL26150 JLL26175 JLL26175	32 32 32 32 32 35 27 27 27 27
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U53X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U44X	32 32 32 32 32 32 32 32 32	JDA26175()	31 31 31 32 32 32 32 32 32 32 31	JE3250U54X	69313131313131323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25 JLL26150 JLL26150 JLL26175	32 32 32 32 32 35 27 27 27 27
HRA36100U33X	32 32 32 32 32 32 32 32 32 32	JDA26175()	31 31 31 32 32 32 32 32 32 32 31 31	JE3250U54X	69313131313232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U53X JLA36250U53X JLF36000F25 JLL26150 JLL26150 JLL26175 JLL26175	32 32 32 32 32 35 27 27 27 27
HRA36100U33X	32 32 32 32 32 32 32 32 32 32 32 32	JDA26175()	31 31 31 32 32 32 32 32 32 31 31 31 31 31 31 31 31	JE3250U54X	69313131313232323232323231313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL26150 JLL26175 JLL26175 JLL26175 JLL26200 JLL26200 JLL26200	32 32 32 32 32 32 35 27 27 27 27 27 27
HRA36100U33X	32 32 32 32 32 32 32 32 32 32 32 32 32	JDA26175()	31 31 31 31 32 32 32 32 32 32 31 31 31 31	JE3250U54X	6931313131323232323232323131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JLL26150 JLL2615C JLL26175 JLL26175 JLL26200 JLL26200 JLL2620C JLL26225	32 32 32 32 32 32 35 27 27 27 27 27 27 27
HRA36100U33X	32 32 32 32 32 32 32 32 32 32 32 32 32	JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31	JE3250U54X	693131313232323232323231313131313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26225 JLL26225	32 32 32 32 32 35 27 27 27 27 27 27 27
HRA36100U33X	32 32 32 32 32 32 32 32 32 32 32 32 32 32 32 32 32	JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31	JE3250U54X	69313131313232323232313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLF36000F25 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26250 JLL26250 JLL26250 JLL26250	32 32 32 32 32 35 27 27 27 27 27 27 27 27
HRA36100U33X		JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 31 31 31 31	JE3250U54X	693131313232323232313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLE36150 JLL26150 JLL26175 JLL26175 JLL26200 JLL2620C JLL26225 JLL26225 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250C JLL34250WU31X	32 32 32 32 32 35 27 27 27 27 27 27 27 27
HRA36100U33X		JDA26175()	31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 31 31 32 32 32 32 32 32 32 32	JE3250U54X	693131313232323231313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL2615C JLL26175 JLL26175 JLL26200 JLL26200 JLL2625C JLL2625C JLL26250 JLL34250WU31X	32 32 32 32 32 35 27 27 27 27 27 27 27 27 27
HRA36100U33X		JDA26175()	31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 31 31 32 32 32 32 32 32 32 32	JE3250U54X	693131313232323231313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLE36150 JLL26150 JLL26175 JLL26175 JLL26200 JLL2620C JLL26225 JLL26225 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250 JLL26250C JLL34250WU31X	32 32 32 32 32 35 27 27 27 27 27 27 27 27 27
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U54X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U44X HRA36150U54X HRA36150U54X HRA36150U54X HRL36050M72 HRL36060CU31X HRL36060CU33X HRL36060CU43X HRL36060CU43X HRL36060CU43X HRL36060CU43X HRL36060CU43X HRL36060CU43X HRL36060CU53X HRL36060CU53X HRL36060CU53X		JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 32 32 32 32 32 32 32 32 32	JE3250U54X	693131313232323231313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL2615C JLL26175 JLL26200 JLL2620C JLL2625C JLL2625C JLL2625C JLL34250WU31X JLL34250WU33X JLL34250WU43X	32 32 32 32 32 35 27 27 27 27 27 27 27 27 27 29
HRA36100U33X		JDA26175()	31 31 31 31 32 32 32 32 31 31 31 31 31 31 31 31 32 32 32 32 32 32 32 32 32 32 32	JE3250U54X	693131313132323232313131313131313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U53X JLA36250U54X JLE36150 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26200 JLL26250 JLL2625C JLL2625C JLL2625C JLL34250WU31X JLL34250WU33X JLL34250WU44X	32 32 32 32 32 35 27 27 27 27 27 27 27 27 27 27 27 27 27 29 29
HRA36100U33X		JDA26175()	31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 31 31 32 32 32 32 32 32 32 32 32 32 32 32 32	JE3250U54X	693131313232323231313131313131	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U43X JLA36250U44X JLA36250U53X JLA36250U54X JLE3150 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26225 JLL26225 JLL26250 JLL26250 JLL26250 JLL34250WU31X JLL34250WU33X JLL34250WU44X JLL34250WU44X	32 32 32 32 35 27 27 27 27 27 27 27 27 27 27 27 29 29 29
HRA36100U33X		JDA26175()	31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 31 31 32	JE3250U54X	69313131323232323131313131313131313131313131313232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26250 JLL26250 JLL26250 JLL34250WU31X JL34250WU31X JL34250WU43X JLL34250WU43X JLL34250WU53X JLL34250WU53X	32 32 32 32 32 35 27 27 27 27 27 27 27 27 29 29 29
HRA36100U33X HRA36100U44X HRA36100U44X HRA36100U44X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U44X HRA36150U54X HRA36150U54X HRA36150U54X HRA36050M71 HRL36060CU33X HRA36060CU33X HRA36060CU33X HRA36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060U33X HRL36060U43X HRL36060U53X		JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 32	JE3250U54X	6931313131323232323131313131313131313131313132323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26250 JLL26250 JLL34250WU31X JL34250WU31X JL34250WU44X JLL34250WU44X JLL34250WU54X JLL34250WU54X JLL34250WU54X	32 32 32 32 32 35 27 27 27 27 27 27 27 29 29 29 29 29
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U54X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U54X HRA36150U54X HRA36150U54X HRA36150U54X HRA36050M72 HRL36060CU31X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU43X HRL36060CU43X HRL36060CU43X HRL36060CU53X HRL36060CU53X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U44X HRL36060U45X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U54X		JDA26175()	31 31 31 31 32 32 32 32 31 31 31 31 31 31 31 31 32	JE3250U54X	69313131323232323231313131313131313131313131313131323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U53X JLA36250U54X JLS36000F25 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26200 JLL26250 JLL26250 JLL26250 JLL34250WU31X JLL34250WU33X JLL34250WU43X JLL34250WU43X JLL34250WU53X JLL34250WU54X JLL34250WU54X JLL36150 JLL36150	32 32 32 32 35 27 27 27 27 27 27 27 27 29 29 29 29 29
HRA36100U33X HRA36100U44X HRA36100U44X HRA36100U44X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U44X HRA36150U54X HRA36150U54X HRA36150U54X HRA36050M71 HRL36060CU33X HRA36060CU33X HRA36060CU33X HRA36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060U33X HRL36060U43X HRL36060U53X		JDA26175()	31 31 31 31 32 32 32 32 31 31 31 31 31 31 31 31 32	JE3250U54X	69313131323232323231313131313131313131313131313131323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26250 JLL26250 JLL34250WU31X JL34250WU31X JL34250WU44X JLL34250WU44X JLL34250WU54X JLL34250WU54X JLL34250WU54X	32 32 32 32 35 27 27 27 27 27 27 27 27 29 29 29 29 29
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U54X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U54X HRA36150U54X HRA36150U54X HRA36150U54X HRA36050M72 HRL36060CU31X HRL36060CU33X HRL36060CU33X HRL36060CU33X HRL36060CU43X HRL36060CU43X HRL36060CU43X HRL36060CU53X HRL36060CU53X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U44X HRL36060U45X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U54X		JDA26175()	31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 32	JE3250U54X	693131313132323232313131313131313131313232323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U53X JLA36250U54X JLS36000F25 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26200 JLL26250 JLL26250 JLL26250 JLL34250WU31X JLL34250WU33X JLL34250WU43X JLL34250WU43X JLL34250WU53X JLL34250WU54X JLL34250WU54X JLL36150 JLL36150	32 32 32 32 32 32 32 27 27 27 27 27 27 27 27 27 29 29 29 29 29 29 29 29 29
HRA36100U33X		JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 32	JE3250U54X	693131313232323231313131313131313131323232323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JLS36000F25 JLL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26225 JLL26225 JLL26250 JLL26250 JLL34250WU31X JLS4250WU31X JLS4250WU43X JLL34250WU43X JLL34250WU53X JLL34250WU54X JLL36150 JLL36150 JLL36150 JLL36150T	32 32 32 32 32 32 35 27 29
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U54X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U43X HRA36150U53X HRA36150U54X HRA36150U54X HRA36150U54X HRA36150U54X HRL36060CU51X HRL36060CU31X HRL36060CU33X HRL36060CU33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U54X HRL36060U54X HRL36100CU31X HRL36100CU31X HRL36100CU31X HRL36100CU31X HRL36100CU33X HRL36100CU33X HRL36100CU33X HRL36100CU33X HRL36100CU33X		JDA26175()	31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 31 31 31 32 3	JE3250U54X	6931313131323232323131313131313131313131323232323232323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26250 JLL26250 JLL26250 JLL34250WU31X JL34250WU31X JL34250WU43X JLL34250WU43X JLL34250WU53X JLL34250WU53X JLL36150 JLL36175	32 32 32 32 32 32 35 27 27 27 27 27 27 27 27 27 27 27 27 27 27 27 27 29 29 29 29 29 29 29 27 27 27 27 27 27 27 27 27 27 27
HRA36100U33X HRA36100U44X HRA36100U44X HRA36100U54X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U54X HRA36150U54X HRA36150U54X HRA36150U54X HRA36050M72 HRL36060CU31X HRL36060CU31X HRL36060CU33X HRL36060CU33X HRL36060CU43X HRL36060CU43X HRL36060CU43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U43X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36060U53X HRL36100CU31X HRL36100CU31X HRL36100CU33X HRL36100CU33X HRL36100CU33X		JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 32 3	JE3250U54X	693131313132323232313131313131313131313131323232323232323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26200 JLL26250 JLL26250 JLL36250 JLL34250WU31X JLL34250WU31X JLL34250WU44X JLL34250WU44X JLL34250WU53X JLL36150 JLL36150 JLL36150 JLL36150 JLL36175 JLL36175 JLL36175	32 32 32 32 32 35 27 29
HRA36100U33X HRA36100U43X HRA36100U44X HRA36100U54X HRA36100U54X HRA36150U31 HRA36150U33X HRA36150U43X HRA36150U43X HRA36150U53X HRA36150U54X HRA36150U54X HRA36150U54X HRA36150U54X HRL36060CU51X HRL36060CU31X HRL36060CU33X HRL36060CU33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U33X HRL36060U54X HRL36060U54X HRL36100CU31X HRL36100CU31X HRL36100CU31X HRL36100CU31X HRL36100CU33X HRL36100CU33X HRL36100CU33X HRL36100CU33X HRL36100CU33X		JDA26175()	31 31 31 31 32 32 32 32 32 31 31 31 31 31 31 31 32 3	JE3250U54X	693131313132323232313131313131313131313131323232323232323232323232323232	JJA26200()	JLA36250U31X JLA36250U33X JLA36250U44X JLA36250U53X JLA36250U54X JLA36250U54X JL26150 JLL26175 JLL26175 JLL26200 JLL26200 JLL26250 JLL26250 JLL26250 JLL34250WU31X JL34250WU31X JL34250WU43X JLL34250WU43X JLL34250WU53X JLL34250WU53X JLL36150 JLL36175	32 32 32 32 32 35 27 29

## PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Catalog Numbers

	07	I D 4 0 4 0 0 0 1 4 1 5 4 1 4 1 6 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	1 D1 000001140V	20	1.5400011501/	1 O 1 00 100 T 100 V 40
JLL36200C		LDA34600WU54X 39	LDL36600U43X		LE4600U53X69	LGL36400TU33X40
JLL36200T		LDA36250CU31X 40	LDL36600U44X3		LE4600U54X69	LGL36400TU43X40
JLL36225		LDA36250CU33X 40	LDL36600U53X3	36	LGA34250WU31X 39	LGL36400TU44X40
JLL36225C	27	LDA36250U31X39	LDL36600U54X3	36	LGA34250WU33X 39	LGL36400TU53X40
JLL36225T	33	LDA36250U33X39	LDL44250WU31X3	38	LGA34400WU31X 39	LGL36400TU54X40
JLL36250		LDA36400CU31X 40	LDL44250WU33X3		LGA34400WU33X 39	LGL36400U31X36
JLL36250C		LDA36400CU33X 40	LDL44400WU31X3		LGA34400WU43X 39	LGL36400U33X36
JLL36250CU31X			LDL44400WU33X3			LGL36400U43X36
		LDA36400CU43X 40			LGA34400WU44X 39	
JLL36250CU33X		LDA36400CU44X 40	LDL44400WU43X3		LGA34400WU53X 39	LGL36400U44X36
JLL36250CU43X		LDA36400CU53X 40	LDL44400WU44X3		LGA34400WU54X 39	LGL36400U53X36
JLL36250CU53X	28	LDA36400CU54X 40	LDL44400WU53X3	38	LGA34600WU31X 39	LGL36400U54X36
JLL36250M75	50	LDA36400U31X	LDL44400WU54X3	38	LGA34600WU33X 39	LGL36600TU31X40
JLL36250T	33	LDA36600U31X39	LDL44600WU31X3	38	LGA34600WU43X 39	LGL36600TU33X40
JLL36250TU31X		LDA36400U33X39	LDL44600WU33X3		LGA34600WU44X 39	LGL36600TU43X40
JLL36250TU33X		LDA36400U43X39	LDL44600WU43X3		LGA34600WU53X 39	LGL36600TU44X40
JLL36250TU43X		LDA36400U44X39	LDL44600WU44X3		LGA34600WU54X 39	LGL36600TU53X40
JLL36250TU44X		LDA36400U53X39	LDL44600WU53X3		LGA36000S40X45	LGL36600TU54X40
JLL36250TU53X	34	LDA36400U54X39	LDL44600WU54X3	38	LGA36000S60X45	LGL36600U31X36
JLL36250TU54X	34	LDA36600U33X39	LDL46250CU31X3	38	LGA36250CU31X 40	LGL36600U33X36
JLL36250U31X		LDA36600U43X39	LDL46250CU33X3		LGA36250CU33X 40	LGL36600U43X36
JLL36250U33X		LDA36600U44X39	LDL46250U31X3		LGA36250U31X39	LGL36600U44X36
JLL36250U43X		LDA36600U53X39	LDL46250U33X		LGA36250U33X39	LGL36600U53X36
JLL36250U44X	28	LDA36600U54X39	LDL46400CU31X3		LGA36400CU31X 40	LGL36600U54X36
JLL36250U53X	28	LDF36000F2541	LDL46400CU33X3	38	LGA36400CU33X 40	LGL44250WU31X38
JLL36250U54X	28	LDF36000F4041	LDL46400CU43X3	38	LGA36400CU43X 40	LGL44250WU33X38
JRA36150		LDF36000F6041	LDL46400CU44X3		LGA36400CU44X 40	LGL44400WU31X38
JRA36175		LDL34250WU31X 37	LDL46400CU53X3		LGA36400CU53X 40	LGL44400WU33X38
JRA36200		LDL34250WU33X 37	LDL46400CU54X3		LGA36400CU54X 40	LGL44400WU43X38
JRA36225	31	LDL34400WU31X 37	LDL46400U31X3	38	LGA36400U31X39	LGL44400WU44X38
JRA36250	31	LDL34400WU33X 37	LDL46400U33X3	38	LGA36400U33X39	LGL44400WU53X38
JRA36250U31X		LDL34400WU43X 37	LDL46400U43X3	38	LGA36400U43X39	LGL44400WU54X38
JRA36250U33X		LDL34400WU44X 37	LDL46400U44X3		LGA36400U44X39	LGL44600WU31X38
JRA36250U43X		LDL34400WU53X 37	LDL46400U53X3		LGA36400U53X39	LGL44600WU33X38
JRA36250U44X		LDL34400WU54X 37	LDL46400U54X3	38	LGA36400U54X39	LGL44600WU43X38
JRA36250U53X	32	LDL34600WU31X 37	LDL46600U31X3	38	LGA36600U31X39	LGL44600WU44X38
JRA36250U54X	32	LDL34600WU33X 37	LDL46600U33X3	38	LGA36600U33X39	LGL44600WU53X38
JRL36150		LDL34600WU43X 37	LDL46600U43X3		LGA36600U43X39	LGL44600WU54X38
JRL36150C		LDL34600WU44X 37	LDL46600U44X3		LGA36600U44X39	LGL46000S40X45
JRL36175		LDL34600WU53X 37	LDL46600U53X3		LGA36600U53X39	LGL46000S60X45
JRL36175C	27	LDL34600WU54X 37	LDL46600U54X3	38	LGA36600U54X39	LGL46250CU31X38
JRL36200	27	LDL36250CU31X 36	LE3250U31X4	41	LGF36000F2541	LGL46250CU33X38
JRL36200C	27	LDL36250CU33X 36	LE3250U31X6	38	LGF36000F4041	LGL46250U31X38
JRL36225		LDL36250RU31X 40	LE3250U33X4		LGF36000F6041	LGL46250U33X38
JRL36225C		LDL36250RU33X 40	LE3250U33X6		LGL34250WU31X 37	LGL46400CU31X38
JRL36250		LDL36250TU31X 40	LE3400U31X4		LGL34250WU33X 37	LGL46400CU33X38
JRL36250C		LDL36250TU33X 40	LE3400U31X6		LGL34400WU31X 37	LGL46400CU43X38
JRL36250CU31X	28	LDL36250U31X36	LE3400U33X4	41	LGL34400WU33X 37	LGL46400CU44X38
JRL36250CU33X	28	LDL36250U33X36	LE3400U33X6	68	LGL34400WU43X 37	LGL46400CU53X38
JRL36250CU43X	28	LDL36400CU31X 36	LE3400U43X4	41	LGL34400WU44X 37	LGL46400CU54X38
JRL36250CU53X		LDL36400CU33X 36	LE3400U43X6		LGL34400WU53X37	LGL46400U31X38
			LE3400U44X4			
JRL36250M75		LDL36400CU43X 36			LGL34400WU54X 37	LGL46400U33X38
JRL36250U31X		LDL36400CU44X 36	LE3400U44X6		LGL34600WU31X 37	LGL46400U43X38
JRL36250U33X	28	LDL36400CU53X 36	LE3400U53X4	41	LGL34600WU33X 37	LGL46400U44X38
JRL36250U43X	28	LDL36400CU54X 36	LE3400U53X6	69	LGL34600WU43X 37	LGL46400U53X38
JRL36250U44X	28	LDL36400RU31X 40	LE3400U54X4	41	LGL34600WU44X 37	LGL46400U54X38
JRL36250U53X		LDL36400RU33X 40	LE3400U54X6		LGL34600WU53X 37	LGL46600U31X38
JRL36250U54X		LDL36400RU43X 40	LE3600U31X4		LGL34600WU54X 37	LGL46600U33X38
JT3150		LDL36400RU44X 40	LE3600U31X6		LGL36000S40X45	LGL46600U43X38
JT3150		LDL36400RU53X 40	LE3600U33X4		LGL36000S60X45	LGL46600U44X38
JT3175	34	LDL36400RU54X 40	LE3600U33X6	68	LGL36250CU31X 36	LGL46600U53X38
JT3175	61	LDL36400TU31X 40	LE3600U43X4	41	LGL36250CU33X 36	LGL46600U54X38
JT3200		LDL36400TU33X 40	LE3600U43X6		LGL36250RU31X 40	LJA34250WU31X39
JT3200		LDL36400TU43X 40	LE3600U44X		LGL36250RU33X 40	LJA34250WU33X39
JT3225		LDL36400TU44X 40	LE3600U44X6		LGL36250TU31X 40	LJA34400WU31X39
JT3225		LDL36400TU53X 40	LE3600U53X4		LGL36250TU33X 40	LJA34400WU33X39
JT3250	34	LDL36400TU54X 40	LE3600U53X6	69	LGL36250U31X36	LJA34400WU43X39
JT3250		LDL36400U31X36	LE3600U54X4		LGL36250U33X36	LJA34400WU44X39
LDA34250WU31X		LDL36400U33X36	LE3600U54X6		LGL36400CU31X36	LJA34400WU53X39
LDA34250WU33X		LDL36400U43X36	LE4250U31X		LGL36400CU33X36	LJA34400WU54X39
	03					
LDA34400WU31X	20	LDL36400U44X	LE4250U33X6		LGL36400CU43X 36	LJA34600WU31X39
LDA34600WU31X		LDL36400U53X36	LE4400U31X6		LGL36400CU44X 36	LJA34600WU33X39
LDA34400WU33X	39	LDL36400U54X36	LE4400U33X6	68	LGL36400CU53X 36	LJA34600WU43X39
LDA34400WU43X	39	LDL36600TU31X 40	LE4400U43X6	69	LGL36400CU54X 36	LJA34600WU44X39
LDA34400WU44X		LDL36600TU33X 40	LE4400U44X6		LGL36400RU31X 40	LJA34600WU53X39
LDA34400WU53X		LDL36600TU43X 40	LE4400U53X6		LGL36400RU33X 40	LJA34600WU54X39
LDA34400WU54X			LE4400U54X		LGL36400RU43X 40	
		LDL36600TU44X 40				LJA36250CU31X40
LDA34600WU33X		LDL36600TU53X 40	LE4600U31X6		LGL36400RU44X 40	LJA36250CU33X40
LDA34600WU43X		LDL36600TU54X 40	LE4600U33X6		LGL36400RU53X 40	LJA36250U31X39
LDA34600WU44X	39	LDL36600U31X36	LE4600U43X6	69	LGL36400RU54X 40	LJA36250U33X39
LDA34600WU53X		LDL36600U33X36	LE4600U44X6		LGL36400TU31X40	LJA36400CU31X40

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Catalog Numbers

LJA36400CU33X	40	LJL44400WU31X	38	LLL34400WU44X	.37	LLL46400CU54X	38	LRL46600U33X	38
LJA36400CU43X		LJL44400WU33X		LLL34400WU53X		LLL46400U31X		LRL46600U43X	
LJA36400CU44X		LJL44400WU43X		LLL34400WU54X		LLL46400U33X		LRL46600U44X	
LJA36400CU53X	40	LJL44400WU44X		LLL34600WU31X		LLL46400U43X		LRL46600U53X	
LJA36400CU54X	40	LJL44400WU53X	38	LLL34600WU33X	.37	LLL46400U44X	38	LRL46600U54X	38
LJA36400U31X	39	LJL44400WU54X	38	LLL34600WU43X	37	LLL46400U53X	38	MICROTUSEAL	113
LJA36400U33X		LJL44600WU31X		LLL34600WU44X		LLL46400U54X		MICROTUSEAL	
LJA36400U43X		LJL44600WU33X		LLL34600WU53X		LLL46600U31X		PDC12DG4L3	
LJA36400U44X	39	LJL44600WU43X		LLL34600WU54X		LLL46600U33X		PDC3HD2	126
LJA36400U53X	39	LJL44600WU44X	38	LLL36000S40X	.45	LLL46600U43X	38	PDC3JD20	126
LJA36400U54X	39	LJL44600WU53X	38	LLL36000S60X	45	LLL46600U44X	38	PDC5DG20L3	126
LJA36600U31X		LJL44600WU54X		LLL36250CU31X		LLL46600U53X		PDC6HD6	
LJA36600U33X		LJL46250CU31X		LLL36250CU33X		LLL46600U54X		PDC6JD4	
LJA36600U43X		LJL46250CU33X		LLL36250RU31X		LRA36000S40X		S29272	
LJA36600U44X	39	LJL46250U31X	38	LLL36250RU33X	.40	LRA36000S60X	45	S29273	122
LJA36600U53X	39	LJL46250U33X	38	LLL36250TU31X	40	LRA36250CU31X	40	S29273	122
LJA36600U54X		LJL46400CU31X		LLL36250TU33X		LRA36250CU33X		S29273	
LJF36000F25		LJL46400CU33X		LLL36250U31X		LRA36250U31X		S29274	
LJF36000F40		LJL46400CU43X		LLL36250U33X		LRA36250U33X		S29274	
LJF36000F60	41	LJL46400CU44X	38	LLL36400CU31X	.36	LRA36400CU31X	40	S29275	122
LJL34250WU31X	37	LJL46400CU53X	38	LLL36400CU33X	.36	LRA36400CU33X	40	S29275	122
LJL34250WU33X	37	LJL46400CU54X	38	LLL36400CU43X	.36	LRA36400CU43X	40	S29278	122
LJL34400WU31X		LJL46400U31X		LLL36400CU44X		LRA36400CU44X		S29278	
		LJL46400U33X		LLL36400CU53X				S29282	
LJL34400WU33X						LRA36400CU53X			
LJL34400WU43X		LJL46400U43X		LLL36400CU54X		LRA36400CU54X		S29283	
LJL34400WU44X	37	LJL46400U44X	38	LLL36400RU31X	.40	LRA36400U31X	39	S29284	114
LJL34400WU53X	37	LJL46400U53X	38	LLL36400RU33X	40	LRA36400U33X	39	S29284	122
LJL34400WU54X		LJL46400U54X		LLL36400RU43X		LRA36400U43X		S29284	
LJL34600WU31X		LJL46600U31X		LLL36400RU44X		LRA36400U44X		S29286	
LJL34600WU33X		LJL46600U33X		LLL36400RU53X		LRA36400U53X		S29286	
LJL34600WU43X	37	LJL46600U43X	38	LLL36400RU54X	.40	LRA36400U54X	39	S29287	122
LJL34600WU44X	37	LJL46600U44X	38	LLL36400TU31X	40	LRA36600U31X	39	S29287	122
LJL34600WU53X		LJL46600U53X		LLL36400TU33X		LRA36600U33X		S29287	
LJL34600WU54X		LJL46600U54X				LRA36600U43X		S29313	
				LLL36400TU43X					
LJL36250CU31X		LLA34250WU31X		LLL36400TU44X		LRA36600U44X		S29315	
LJL36250CU33X	36	LLA34250WU33X	39	LLL36400TU53X	.40	LRA36600U53X	39	S29317	113
LJL36250RU31X	40	LLA34400WU31X	39	LLL36400TU54X	.40	LRA36600U54X	39	S29319	114
LJL36250RU33X	40	LLA34400WU33X	39	LLL36400U31X	36	LRL36000S40X	45	S29375	113
LJL36250TU31X		LLA34400WU43X		LLL36400U33X		LRL36000S60X		S29382	
LJL36250TU33X		LLA34400WU44X		LLL36400U43X		LRL36250CU31X		S29383	
LJL36250U31X	36	LLA34400WU53X	39	LLL36400U44X	.36	LRL36250CU33X	36	S29384	
LJL36250U33X	36	LLA34400WU54X	39	LLL36400U53X	.36	LRL36250U31X	36	S29385	101
LJL36400CU31X	36	LLA34600WU31X	39	LLL36400U54X	.36	LRL36250U33X	36	S29386	
LJL36400CU43X		LLA34600WU33X		LLL36600TU31X		LRL36400CU31X		S29387	
LJL36400CU44X		LLA34600WU43X		LLL36600TU33X		LRL36400CU33X		S29388	
LJL36400CU53X	36	LLA34600WU44X		LLL36600TU43X		LRL36400CU43X		S29389	
LJL36400CU54X	36	LLA34600WU53X	39	LLL36600TU44X	.40	LRL36400CU44X	36	S29390	101
LJL36400RU31X	40	LLA34600WU54X	39	LLL36600TU53X	40	LRL36400CU53X	36	S29391	101
LJL36400RU33X		LLA36000S40X		LLL36600TU54X		LRL36400CU54X		S29392	
LJL36400RU43X						LRL36400U31X		S29393	
		LLA36000S60X		LLL36600U31X					
LJL36400RU44X		LLA36250CU31X		LLL36600U33X		LRL36400U33X		S29394	
LJL36400RU53X	40	LLA36250CU33X	40	LLL36600U43X	.36	LRL36400U43X		S29402	
LJL36400RU54X	40	LLA36250U31X	39	LLL36600U44X	.36	LRL36400U44X	36	S29403	101
LJL36400TU31X	40	LLA36250U33X	39	LLL36600U53X	36	LRL36400U53X		S29404	101
LJL36400TU33X		LLA36400CU31X		LLL36600U54X		LRL36400U54X		S29405	
LJL36400TU43X		LLA36400CU33X		LLL44250WU31X		LRL36600U31X		S29406	
LJL36400TU44X		LLA36400CU43X		LLL44250WU33X		LRL36600U33X		S29407	
LJL36400TU53X	40	LLA36400CU44X	40	LLL44400WU31X	.38	LRL36600U43X		S29408	
LJL36400TU54X	40	LLA36400CU53X	40	LLL44400WU33X	.38	LRL36600U44X	36	S29409	101
LJL36400U31X	36	LLA36400CU54X	40	LLL44400WU43X	.38	LRL36600U53X	36	S29410	101
LJL36400U33X		LLA36400U31X		LLL44400WU44X		LRL36600U54X		S29411	
								S29412	
LJL36400U43X		LLA36400U33X		LLL44400WU53X		LRL46000S40X			
LJL36400U44X		LLA36400U43X		LLL44400WU54X		LRL46000S60X		S29413	
LJL36400U53X	36	LLA36400U44X	39	LLL44600WU31X	.38	LRL46250CU31X	38	S29414	101
LJL36400U54X	36	LLA36400U53X	39	LLL44600WU33X	.38	LRL46250CU33X	38	S29433	103
LJL3640C0U33X	36	LLA36400U54X		LLL44600WU43X		LRL46250U31X		S29434	
LJL36600TU31X		LLA36600U31X		LLL44600WU44X		LRL46250U33X		S29435	
LJL36600TU33X		LLA36600U33X		LLL44600WU53X		LRL46400CU31X		S29436	
LJL36600TU43X		LLA36600U43X		LLL44600WU54X		LRL46400CU33X		S29437	
LJL36600TU44X		LLA36600U44X		LLL46000S40X		LRL46400CU43X		S29438	
LJL36600TU53X	40	LLA36600U53X	39	LLL46000S60X	45	LRL46400CU44X	38	S29439	103
LJL36600TU54X		LLA36600U54X		LLL46250CU31X		LRL46400CU53X		S29440	
LJL36600U31X		LLF36000F25		LLL46250CU33X		LRL46400CU54X		S29450	
LJL36600U33X		LLF36000F40		LLL46250U31X		LRL46400U31X		S29450	
LJL36600U43X		LLF36000F60		LLL46250U33X		LRL46400U33X		S29452	
LJL36600U44X	36	LLL34250WU31X	37	LLL46400CU31X		LRL46400U43X		S29452	
LJL36600U53X	36	LLL34250WU33X	37	LLL46400CU33X	.38	LRL46400U44X	38	S31540	
LJL36600U54X		LLL34400WU31X		LLL46400CU43X		LRL46400U53X		S31541	
LJL44250WU31X		LLL34400WU33X		LLL46400CU44X		LRL46400U54X		S31542	
LJL44250WU33X	30	LLL34400WU43X	31	LLL46400CU53X	.50	LRL46600U31X	30	S31543	103

## PowerPact™ H-, J-, and L-Frame Circuit Breakers Catalog Numbers

S31544103	S434204BS 83
S31545103	S434205 83
S31546	S434206 84
S31548103	S434210 83
S32514122	S434212 92
S32514122	S434300 93
S32515122	S43430193
S32515122	S43430293
S32523122	S434303 82
S32525122	S434303BS83
S32532122	S43450093
\$32533122	S43450193
S32534114	\$434502 93
S32534122	S43450393
S32558113	\$434504
S32560114	\$434505
S32562122 S32562122	\$434506
S32562122 S32563122	\$434507 93 \$434508 93
S32563122	SN100FA116
S32648103	SN100FA 116
S32649103	SN400LA 116
S36967123	SN400LA116
S36967125	SN400LA 116
S37420103	SN400LA116
S37420103	STRV0012179
S37423124	STRV0021081
S37423124	STRV00211 81
S37424124	STRV0091085
S37424124	STRV0091185
S37425125	TCSWAAC13FB 85
S37426125	TRV0012879
S37427125	TRV00217 81
S37428125	TRV0080386
S37429124 S37430124	TRV0080686
S37430124 S37436122	TRV00810 86 TRV0082086
S37440122	TRV0083086
S37442122	TRV0085086
S37443122	TRV0087086
S37444125	TRV0088086
S37445125	TRV0091585
S41940103	TRV0091785
S41940103	VW3A8306DRC86
S41940103	YA060HD 127
S42888103	YA150HD127
S42888103	YA150JD 127
S42888103 S429424100	YA250J35 127 YA400L31K3 127
S429441103	YA400L51K3 127
S429449103	YA400L51K4 127
S429449103	YA400L71K3 127
S42947869	YA400L71K4 127
S42948169	YA600L32K3 127
S42948369	YA600L32K4 127
S42948469	YA600L52K3 127
S42952192	YA600L52K4 127
S429532100	
S43056292	
S43056392 S431549103	
S43245969	
S43246169	
S432553114	
S43257592	
S432639103	
S432640103	
S432641103	
S432642103	
S432643103	
\$432644103	
\$432645103	
S432646103 S432647103	
\$432652103	
S43420182	



 S434201
 82

 S434201BS
 83

 S434202
 82

 S434202BS
 83

 S434204
 82

# PowerPact™ H-, J-, and L-Frame Circuit Breakers Glossary

## **Glossary**

**accessory** = An electrical or mechanical device that performs a secondary or minor function apart from overcurrent protection.

**accessory cover** = A removable cover on the front of a circuit breaker behind which are mounted the trip unit and all electrical accessories.

adjustable rating plug = A component which plugs into the trip unit, establishing the ampere rating of the circuit breaker

AIC = Amperes interrupting capacity.

**AIR** = See amperes interrupting rating.

alarm switch (bell alarm) = See overcurrent trip switch.

**ambient temperature rating** = Temperature at which the continuous current rating (handle rating) of a circuit breaker is based; the temperature of the air immediately surrounding the circuit breaker which can affect the thermal (overload) tripping characteristics of thermal-magnetic circuit breakers. Electronic trip circuit breakers, however, are insensitive to normal (-10° to 50°C) ambient conditions.

**ammeter (local current meter)** = A module that mounts directly to the circuit breaker trip unit and reports RMS phase and ground-fault current values as seen by the trip unit. Current values are displayed one phase at a time.

**ampacity** = The current, in amperes, that a conductor or circuit breaker can carry continuously under the conditions of use without exceeding its temperature rating.

**ampere** = The equivalent of one coulomb per second or the steady current produced by one volt applied across a resistance of one ohm.

**amperes interrupting rating** = The highest current at rated voltage that an overcurrent protective device is intended to interrupt under specified test conditions (NEC).

**ANCE (National Association of Standardization and Certification for the Electrical Sector)** = The standards and certification agency accredited by the Mexican government.

**ANSI**® = American National Standards Institute.

**automatic molded case switch** = A switch with construction similar to a molded case circuit breaker except that the switch opens only instantaneously at a non-adjustable trip point calibrated to protect only the molded case switch itself.

**auxiliary switch** = A switch mechanically operated by the main device for signaling, interlocking, or other purposes.

**bell alarm** = A mechanically-operated switch used to indicate the main contact position of a circuit breaker, which indicates when a circuit breaker has tripped. Also see *overcurrent trip switch*.

**BPFE** = See *electrical closing push button*.

branch circuit = The circuit between the final overcurrent device protecting the circuit and the outlet(s).

**BCM** = See *circuit breaker communications module*.

**Canadian Standards Association® (CSA®)** = Canadian product safety testing and certification organization.

carriage= See cradle.

**CCM** = See cradle communication module.

CD = See cell switch.

**CDM** = See mechanical operation counter.

CE = See cell switch.



### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Glossary

**cell switch** = A switch which indicates the position of a drawout circuit breaker in relation to the cradle.

- CD = Disconnected position cell switch.
- CE = Connected position cell switch.
- CT = Test position cell switch.

**CH** = A spring-charged contact inside of the spring charging motor on insulated-case and low-voltage power circuit breakers.

charging handle= See spring charging handle.

**circuit breaker** = A device designed to open and close a circuit by non-automatic means and to open the circuit automatically on an overcurrent without damage to itself when properly applied within its rating.

**circuit breaker communications module (BCM)** = A module which, when installed in a circuit breaker, receives and transmits information on the communication network.

**circuit breaker frame** = (1) The circuit breaker housing which contains the current carrying components, the current sensing components, and the tripping and operating mechanism. (2) That portion of an interchangeable trip molded case circuit breaker remaining when the interchangeable trip unit is removed.

**close button** = A button for manually closing the main contacts after the closing springs are charged.

**close button cover** = A cover which fits over the close button and blocks access to it. Access to the close button may be permitted through the use of a tool or rod inserted through a small hole in the front of the close button cover.

**closing coil (shunt close)** = A coil which closes the circuit breaker electrically using an external voltage source when a specified voltage is applied across the coil.

**coil clearing switch** = A mechanically-operated switch in series with the coil of a shunt trip device which breaks the coil current when the circuit breaker opens.

**communication network** = A network allowing the flow of information between electrical components, comprised of programmable controller interface units, protocol software and modems.

conductor = A substance or body that allows a current of electricity to pass continuously along it.

**continuous current rating (handle rating) (ampere rating)** = The designated RMS alternating or direct current in amperes which a device or assembly will carry continuously in free air without tripping or exceeding temperature limits.

continuous load = A load where the maximum current on the circuit is expected to continue.

**cradle communications module (CCM)** = An external module which allows addressing of the cradle and retention of the address when the drawout circuit breaker is in the disconnected position and which is used to transmit information about the position of the circuit breaker in the cradle to the communication network.

**cradle compartment** = A compartment containing all connectors, shields, adapters, barriers, spreaders, shutters, keys and interlocking devices for a drawout circuit breaker.

CSA® = See Canadian Standards Association.

CT = Current transformer. See also *cell switch*.

**current path (of a circuit breaker)** = The current-carrying conductors within a circuit breaker between, and including, line and load terminations.

**current transformer (current sensor) (CT)** = An instrument to measure current, encircling a conductor carrying the current to be measured or controlled.

**demand metering** = The metering of power or current demand seen by a circuit breaker. It is calculated over a fixed or sliding time window that can be programmed from five to 60 minutes. Depending on the contract signed with the power supplier, specific programming makes it possible to avoid or minimize the cost of overrunning the subscribed power. Maximum demand values are systematically stored and time stamped.

**disconnecting contacts** = See *main disconnecting contacts* and *secondary disconnecting contacts*.



# PowerPact™ H-, J-, and L-Frame Circuit Breakers Glossary

**drawout circuit breaker** = An assembly of a circuit breaker and a supporting structure (cradle) so constructed that the circuit breaker is supported and can be moved to either the main circuit connected or disconnected position without removing connections or mounting supports.

**drawout mechanism** = A mechanism which engages the drawout cradle assembly and draws the circuit breaker into or out of the equipment. The drawout mechanism includes the drawout mechanism shaft, drawout levering device arms and a drawout position indicator.

**drawout position indicator** = An indicating means which shows the position of the circuit breaker in the drawout structure.

**drawout access cover (drawout shaft cover)** = A shutter which allows or restricts access to the drawout shaft.

**electrical closing push button (BPFE)** = A push button used to electrically close a circuit breaker using a shunt close with communication option. This takes into account all safety functions that are part of the control and monitoring system of the installation.

**electrical operator (motor operator)** = An electrical device used to open and close a circuit breaker or switch and reset a circuit breaker. See also *spring charging motor*.

**electronic trip circuit breaker** = A circuit breaker which uses current sensors and electronic circuitry to sense, measure and respond to current levels.

**fixed-mounted circuit breaker** = A circuit breaker so mounted that it cannot be removed without removing primary and sometimes secondary connections and/or mounting supports.

**frame size** = The largest ampere rating available in a group of circuit breakers of similar physical configuration.

**frequency** = The number of cycles per second for an alternating current system.

**frequency rating** = The range of frequencies within which a product can be applied.

ground fault = An unintentional current path, through ground, back to the source.

**ground-fault delay** = The length of time the circuit breaker trip unit will delay before initiating a trip signal to the circuit breaker after a ground fault has been detected.

**ground-fault module** = An electronic accessory used in combination with thermal-magnetic circuit breakers to provide branch circuit ground-fault protection and ground-fault indication.

ground-fault pickup = The level of ground-fault current at which the trip system begins timing.

handle rating = Continuous current rating.

**IDMTL** = Long-time delay curve which can be varied in slope to enhance selectivity.

IEC® = International Electrotechnical Commission.

**IEEE®** = Institute of Electrical and Electronics Engineers.

Ig = See ground-fault pickup.

li = See instantaneous pickup.

In = See sensor rating.

**individually-mounted circuit breaker** = A circuit breaker so mounted that it cannot be removed without removing primary and sometimes secondary connections and/or mounting supports.

**instantaneous pickup** = The current level at which the circuit breaker will trip with no intentional time delay.

**instantaneous trip** = A qualifying term indicating that no delay is purposely introduced in the tripping action of the circuit breaker during short-circuit conditions.

**insulated case circuit breaker (ICCB)** = UL Standard 489 Listed non-fused molded case circuit breakers which utilize a two-step stored energy closing mechanism, electronic trip system and drawout construction.



01/2014

### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Glossary

**integral ground-fault protection for equipment** = Equipment ground-fault protection on grounded neutral systems provided by components internal to the circuit breaker.

**interchangeable trip unit** = A trip unit which can be interchanged by a user among circuit breaker frames of the same design.

**interrupting rating** = The highest current at rated voltage available at the incoming terminals of the circuit breaker. When the circuit breaker can be used at more than one voltage, the interrupting rating will be shown on the circuit breaker for each voltage level. The interrupting rating of a circuit breaker must be equal to or greater than the available short-circuit current at the point at which the circuit breaker is applied to the system.

**inverse time** = A qualifying term indicating there is purposely introduced a delay in the tripping action of the circuit breaker, which delay decreases as the magnitude of the current increases.

 $I_r$  = See *long-time pickup*.

I<sub>sd</sub> = See *short-time pickup*.

I2t = See let-through current.

I2 t IN (I2 t ON) = An inverse time delay characteristic.

I2 t OUT (I2 t OFF) = A constant time delay characteristic.

latch check switch = A mechanically-operated switch which senses if the trip latch is reset.

**let-through current** = The peak current (measured in amperes) which passes through an overcurrent protective device during an interruption.

**let-through I**<sup>2</sup>**t** = An expression related to energy (measured in ampere-squared seconds) which passes through an overcurrent protective device during an interruption.

**LI** = A combination of adjustable trip functions including long-time ampere rating, long-time delay, and instantaneous pickup.

**lifting adapter** = A device used with a crane, chain block or an optional lifting mechanism supplied with switchgear for removing and installing a drawout circuit breaker or fuse truck.

**LIG** = A combination of adjustable trip functions including long-time ampere rating, long-time delay, instantaneous pickup, ground-fault pickup and ground-fault delay.

**limit switch** = A switch mechanically operated by a device.

local current meter = An ammeter installed as part of the trip unit.

**long-time ampere rating** = An adjustment which, in combination with the installed rating plug, establishes the continuous current rating of a full-function electronic trip circuit breaker.

**long-time delay** = The length of time the circuit breaker will carry a sustained overcurrent (greater than the long-time pickup) before initiating a trip signal.

long-time pickup = The current level at which the circuit breaker long-time delay function begins timing.

**low voltage power circuit breaker (LVPCB)** = A circuit breaker tested to the ANSI C37 Standards with a two-step stored-energy mechanism, an electronic trip system, and drawout construction.

**LS** = A combination of adjustable trip functions including long-time ampere rating, long-time delay, short-time pickup, short-time delay and a defeatable instantaneous pickup.

**LSG** = A combination of adjustable trip functions including long-time ampere rating, long-time delay, short-time pickup, short-time delay, defeatable instantaneous pickup, ground-fault pickup and ground-fault delay.

**LSI** = A combination of adjustable trip functions including long-time ampere rating, long-time delay, short-time pickup, short-time delay and defeatable instantaneous pickup.

**LSIG** = A combination of adjustable trip functions including long-time ampere rating, long-time delay, short-time pickup, short-time delay, defeatable instantaneous pickup, ground-fault pickup and ground-fault delay.



### PowerPact™ H-, J-, and L-Frame Circuit Breakers Glossary

main disconnecting contacts = Spring-loaded and self-aligning contact on the rear of a drawout circuit breaker that provide positive electrical contact when the circuit breaker is in the connected position.

Masterpact™ = The family of universal power circuit breakers including insulated case circuit breakers and low-voltage power circuit breakers.

**MCH** = See *spring-charging motor*.

**MDGF** = Modified differential ground-fault system.

manual charging handle = A manually-operated handle which charges the circuit breaker closing springs.

mechanical operation counter (CDM) = A mechanical device which indicates the total number of circuit breaker operating cycles.

Micrologic™ = The family of electronic trip systems available on molded case circuit breakers, insulated case circuit breakers and low-voltage power circuit breakers.

miniature circuit breaker (MCB) = A small circuit breaker which is assembled as an integral unit in a supportive and enclosed housing of insulating material, rated 150 A or less and used in 120 V, 120/240 V, 240 V and 480Y/277 V ac systems and dc systems up to 125 Vdc.

MN = See undervoltage release.

Modbus™ communication network = A communication network comprised of programmable controller interface units, protocol software and modems.

molded case circuit breaker (MCCB) = A circuit breaker which is assembled as an integral unit in a supportive and enclosed housing of insulating material, generally 20 to 3000 A in size and used in systems up to 600 Vac and 500 Vdc.

motor circuit protector = A recognized component of construction similar to a circuit breaker except with no thermal elements so that it provides short-circuit protection only.

MX = See shunt trip.

National Association of Standardization and Certification for the Electrical Sector = See ANCE.

**neutral current transformer** = A current transformer which encircles the neutral conductor; required on circuit breakers with ground-fault protection, when applied on a grounded system.

NMX® (Norma Mexicana X) = Listing mark indicating certification to non-mandatory Mexican safety standards.

NOM = Listing mark indicating certification to mandatory Mexican safety standards

**OF** = See auxiliary switch.

open/closed indicator = An indicating means which displays the position (open or closed) of the main contacts.

operating mechanism = An internal mechanical system which opens and closes the circuit breaker contacts.

OTS = Overcurrent trip switch (alarm switch, bell alarm). A mechanical switch that operates when the circuit breaker is tripped by the trip system.

overcurrent = Any current in excess of the rated continuous current of equipment or the ampacity of a conductor.

overcurrent mechanism = An internal mechanical system which trips the circuit breaker during an overcurrent.

overcurrent trip element = A device which detects an overcurrent and transmits the energy necessary to open the circuit automatically (UL only).

overcurrent trip switch (SDE) = A mechanically-operated switch which indicates when a circuit breaker has tripped due to overcurrent conditions.



01/2014

### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Glossary

**overload delay** = The length of time the circuit breaker will carry a sustained low-level overcurrent before initiating a trip signal.

peak current sensing = A method of determining the current by means of detecting the current peaks.

peak let-through current = The maximum peak current flowing in a circuit during an overcurrent condition.

PF = A switch used to indicate a circuit breaker is ready to close.

phase barrier = A barrier which provides phase-to-phase or phase-to-ground isolation.

**PowerLogic™** = The family of electronic circuit monitoring systems available on molded case circuit breakers, insulated case circuit breakers and low-voltage power circuit breakers.

**Power-Zone™** = The family of low-voltage and medium-voltage switchgear.

**programmable contact module (M6C and M2C)** = A programmable module which indicates the type of fault and the instantaneous and delayed threshold overruns. It may be programmed with instantaneous return to the initial state, without return to the initial state, or with return to the initial state following a delay.

**primary disconnect contacts** = An electrical plug-on connector in the main current path between the drawout components and the cradle mounted in the equipment.

**push-to-close button** = A button for manually closing the main contacts after the closing springs are charged.

**push-to-open button** = A button for manually opening the circuit breaker.

**push-to-trip button** = A button for manually tripping the circuit breaker.

racking device shutter = See drawout shaft cover.

**racking interlock** = An interlock to prevent racking of a drawout circuit breaker when the enclosure door is open by not allowing the racking crank to be inserted into the circuit breaker.

**rating plug** = A component which plugs into the full-function electronic trip unit, establishing the maximum continuous current rating of the circuit breaker.

**remote reset after fault (RES)** = A component which resets the overcurrent trip switch (SDE) and the mechanical operator after tripping.

RES = See remote reset after fault.

**residual ground-fault sensing** = A means of providing equipment ground-fault protection utilizing sensors on each individual phase.

restraint interface module (RIM) = A component which allows zone-selective interlocking communication between Square D<sup>™</sup> full-function electronic trip systems, add-on ground-fault modules and zero-sequence ground-fault relays.

**RIM** = Restraint interface module.

**RMS** = Root-mean-square.

**RMS current sensing** = A method of determining the true RMS current of sinusoidal and non-sinusoidal waveforms by sampling the current waveform a number of times per cycle, then calculating the true RMS value.

**safety shutter** = A device that closes to block access to the main disconnects when the circuit breaker is in the disconnected, test or withdrawn position.

**SDE** = See *overcurrent trip switch*.

**secondary disconnect contacts** = An electrical plug-on connector in the secondary (control) circuit between a drawout circuit breaker and its cradle in the equipment.

**sensor** = The current sensing element within the circuit breaker which provides the sensing function for that circuit breaker.

sensor plug = A component used with a Micrologic trip system to set the sensor size of a circuit breaker.



### PowerPact™ H-, J-, and L-Frame Circuit Breakers Glossary

sensor size = Maximum ampere rating possible for a specific circuit breaker, based on the size of the current sensor inside the circuit breaker. Sensor size is less than or equal to frame size.

**SGR** = Source ground return system.

short-circuit delay (STD) = The length of time the circuit breaker will carry a short circuit (current greater than the short-circuit pickup) before initiating a trip signal.

short-circuit pickup = The current level at which the circuit breaker short-circuit delay function begins timing.

short-time delay = The length of time the circuit breaker will carry a short circuit (current greater than the short-time pickup) before initiating a trip signal.

short-time pickup = The current level at which the circuit breaker short-time delay function begins timing.

shunt close (closing coil) (XF) = An accessory which closes the circuit breaker from a remote location using an external voltage source.

shunt trip (MX) = An accessory which trips the circuit breaker from a remote location using an external voltage source.

spring-charging handle = A handle located on the front of the circuit breaker used to manually charge the stored energy mechanism.

spring charging motor = A motor which electrically charges the stored energy closing spring(s).

STD = Short-time delay.

stored energy mechanism (SEM) = A spring mechanism that is compressed or "charged" and then released or "discharged" to close the circuit breaker.

terminal block = The connections for control wiring.

tg = See ground-fault delay.

thermal imaging = A trip unit function that accurately maps the heating and cooling effects of load behavior on rated conductors to provide thermal protection without nuisance tripping.

thermal-magnetic circuit breaker = A general purpose term for circuit breakers that use bimetals and electromagnetic assemblies to provide both thermal and magnetic overcurrent protection.

thermal memory = Provides continuous temperature rise status of the wiring for a period of time both before and after the device trips. This allows the circuit breaker to respond to a series of overload conditions which would otherwise go undetected.

 $t_r$  = See *long-time delay*.

 $t_{sd}$  = See short-time delay.

two-step stored energy mechanism = See stored energy mechanism.

transformer = A static device with primary winding, connected in series with the conductor (bus) carrying the current to be measured or controlled within the switchgear.

**trip button** = See *push-to-trip button*.

**trip curve** = A graphical representation of the response of a circuit breaker to current over a period of time.

trip indicator = A module that mounts directly to the circuit breaker trip unit that displays whether the circuit breaker tripped due to an overload, a short-circuit or a ground-fault condition.

trip indicator reset = A button on the trip indicator module used to reset the trip indicator.

trip system = A system which consists of a Micrologic trip unit and current transformers.

trip unit = A programmable device which measures and times current flowing through the circuit breaker and initiates a trip signal when appropriate.

**UL®** = See *Underwriters Laboratories Inc.* 



01/2014

### PowerPact<sup>™</sup> H-, J-, and L-Frame Circuit Breakers Glossary

**undervoltage trip (MN, UVR)** = An accessory which trips the circuit breaker automatically when the monitored circuit voltage falls below a predetermined percentage of its specified value.

**Underwriters Laboratories Inc.**® **(UL**®**)** = An independent, not-for-profit standards development, product safety testing and certification organization.

**unit-mount circuit breaker** = A circuit breaker mounted such that it cannot be removed without removing primary and sometimes secondary connections or mounting supports.

withstand rating = The level of RMS symmetrical current that a circuit breaker can carry with the contacts in a closed position for a stated period of time—usually stated in cycles.

**zero-blind time** = Metering method used by the Micrologic H trip unit where a dedicated metering data chain is separate from the protection data chain so that a greater number of data samples can be used for metering. This increases the number of samples taken per time period, which in turn gives the H trip unit a higher degree of metering accuracy.

**zero-sequence ground-fault sensing** = A means of providing equipment ground-fault protection utilizing an external sensor (surrounding all phase and neutral conductors).

**zone-selective interlocking (ZSI)** = A communication capability between electronic trip systems and ground-fault relays which permits a short circuit or ground fault to be isolated and cleared by the nearest upstream device with no intentional time delay.

**ZSI** = Zone-selective interlocking.

